

ED 025 584

08

VT 001 637

Landscape Design. A Student Handbook. Teacher Education SER-9-NO-3S. Interim Report.

Pennsylvania Agricultural Experiment Station, University Park.

Spons Agency- Office of Education (DHEW), Washington, D.C.

Bureau No- BR-5-0022

Pub Date 68

Contract- OEC-8-85-014

Note- 145p.

EDRS Price MF- \$0.75 HC- \$7.35

Descriptors- Employment Opportunities, Job Skills, \*Landscaping, Management, Occupational Information, \*Ornamental Horticulture, Plant Science, Reference Materials, Site Development, \*Textbooks, \*Vocational Agriculture

This student handbook is one of a series of instructional aids prepared and edited by the Department of Agricultural Education at the Pennsylvania State University. Its organization and content was field tested, evaluated, and improved by vocational agriculture teachers attending summer institutes in ornamental horticulture in 1966 and 1967. The content includes sections of: (1) Occupational Opportunities in Landscape Design, (2) Importance of Landscaping, (3) Analysis of Landscape Requirements, (4) Ideas for Solving Landscape Problems, (5) Structures and Plants, and (6) Estimating Landscape Costs. Each problem area lists objectives, key questions, new words, and the subject content. The textual material is supplemented with photographs, sketches, drawings, forms, and a reference list. Appendixes contain a plant material list, landscape symbols, information for identification and classification of plant material, and addresses for agricultural extension publications. Applications relate to the northeastern United States. The teacher's manual in this series is available as VT 007 681. (DM)

Interim Report


BR 5-0022  
RA-08

# LANDSCAPE DESIGN

## A Student Handbook

U.S. DEPARTMENT OF HEALTH, EDUCATION & WELFARE  
OFFICE OF EDUCATION

THIS DOCUMENT HAS BEEN REPRODUCED EXACTLY AS RECEIVED FROM THE PERSON OR ORGANIZATION ORIGINATING IT. POINTS OF VIEW OR OPINIONS STATED DO NOT NECESSARILY REPRESENT OFFICIAL OFFICE OF EDUCATION POSITION OR POLICY.



The Pennsylvania State University  
College of Agriculture  
Agricultural Experiment Station  
Department of Agricultural Education  
University Park, Pennsylvania

Teacher Education Series  
Volume 9 Number 3s  
1968

ED025584

VT001637

This publication was prepared and edited by the following staff members of the Department of Agricultural Education, College of Agriculture, The Pennsylvania State University: N. Laurence Miller, Graduate Assistant, William J. Brown, Jr., Instructor, R. Jack Mercer, Instructor, Gene M. Love, Associate Professor, and Richard F. Stinson, Associate Professor.

Technical assistance was received from the following staff members of the Department of Landscape Architecture, College of Arts and Architecture, The Pennsylvania State University: Wayne H. Wilson, Professor and Head and James R. DeTuerk, Assistant Professor.

Illustrations, photographs, and an accompanying series of color slides were largely the work of Richard W. Tenney, Graduate Assistant, Department of Agricultural Education.

The research reported herein was performed pursuant to a contract with the Office of Education, U. S. Department of Health, Education, and Welfare. Contractors undertaking such projects under Government sponsorship are encouraged to express freely their professional judgment in the conduct of the project. Points of view or opinions stated do not, therefore, necessarily represent official Office of Education position or policy.

## Introductory Statement

Landscape Design - A Student Handbook is one of a series of instructional aids being prepared and edited by the Department of Agricultural Education through a contractual agreement between The Pennsylvania State University and the United States Office of Education, Division of Adult and Vocational Research. In addition to the development of instructional aids, the contract provides for two teachers' institutes in ornamental horticulture. The first was held July 5-22, 1966. The second was held July 3-21, 1967.

Teachers from the northeastern states who participated in the second teachers' institute field-tested, evaluated, and helped improve the organization and the content of the unit of instruction.

A special advisory committee has provided guidance in the selection of areas of emphasis for which several units of instruction in ornamental horticulture have been prepared. The committee has assisted by outlining key problem areas and by suggesting important subject matter information to be included in the content of each unit. In addition to Wayne H. Wilson and James DeTuerk, who have been cited previously, the following persons have served in an advisory capacity for the development of this unit of instruction: Darrell E. Walker, Professor and Head, Robert P. Meahl, Professor, and Craig Oliver, Assistant Professor, Department of Horticulture, The Pennsylvania State University.

Richard F. Stinson, Project Director  
David R. McClay, Associate Project  
Director  
Glenn Z. Stevens, Associate Project  
Director

## TABLE OF CONTENTS

	Page
I. Occupational Opportunities in Landscape Design . . . . .	1
Landscape Architect . . . . .	3
Landscape Designer . . . . .	4
Horticultural Extension Agent . . . . .	5
Landscape Nurseryman . . . . .	6
II. Importance of Landscaping . . . . .	7
Landscaping for Use . . . . .	8
Landscaping for Beauty . . . . .	8
Landscaping Increases Property Value . . . . .	9
III. Analysis of Landscape Requirements . . . . .	11
Site Analysis . . . . .	11
Analysis of Family Needs . . . . .	20
Area Layout Plan . . . . .	25
IV. Ideas for Solving Landscape Problems . . . . .	29
Layout of Landscape Areas . . . . .	30
Ideas for Solving Landscape Problems . . . . .	31
Landscaping the Public Area . . . . .	33
Landscaping the Private Area . . . . .	50
Landscaping the Service Area . . . . .	58
Placing Plant Materials . . . . .	59
Planning . . . . .	61
V. Structures and Plants . . . . .	63
Planning Landscape Structures . . . . .	64
Structural Materials . . . . .	74
The Structural Plan . . . . .	79
The Kinds of Plants . . . . .	82
The Planting Plan . . . . .	91
Selection of Plant Materials . . . . .	91
VI. Estimating Landscape Cost . . . . .	97
References . . . . .	101
Appendix A - Plant Materials List	
Appendix B - Landscape Symbols	
Appendix C - Identification and Classification of Plant Materials Commonly Used for Landscape Plantings	
Appendix D - Addresses for Agricultural Extension Publications Services	

## PROBLEM AREA 1

### OCCUPATIONAL OPPORTUNITIES IN LANDSCAPE DESIGN

#### Student Learning Objectives

The major objective of this Problem Area is to explore the occupational opportunities in landscape design. Students should develop a knowledge and understanding about the:

1. Types of occupations in landscape design.
2. Competencies required for successful employment in the various occupations.
3. Types and level of education needed to attain the competencies required for successful performance in an occupation.
4. Future of landscape design.

#### Key Questions

1. What occupational opportunities exist in landscape design and what competencies are required to enter these occupations?
2. What educational opportunities are available for securing the competencies needed for the various occupations?
3. What opportunities exist for work experience in the various occupations?
4. What is the outlook for the future of landscape design?

#### Occupational Opportunities in Landscape Design

Occupational opportunities in landscape design vary with the amount of specialized education and experience possessed by individuals. A very important fact is that many well trained people are needed who can provide landscape design services. Nurseries and landscape designers sell over 300 million dollars of plant materials and services each year. They employ thousands of people to provide these services. By all indications, these phases of agriculture will continue to increase in importance. The occupations in landscape design should appeal to people who enjoy drawing, working outdoors, meeting people, and working with plants.

Before beginning to learn to design landscapes, you must have had some practical experience in maintaining lawns, trees, shrubs, and flowers in a landscape. You must have had similar experience in constructing walks, steps, walls, fences, terraces and other garden structures. You must be able to

understand the symbols in a planting plan, and have followed plans in making plantings. You must be able to identify several hundred kinds of trees and shrubs with a glance, and know the purposes for which each can be used.

You are then ready for the material covered in this handbook. Here you will learn architectural drawing, planning, and construction, and gain the experiences needed to be able to devise the best solutions to the problems of making landscapes both useful and pleasant.

This handbook is aimed at preparing you to be a landscape designer. With additional study in nursery operations and management you would be prepared to enter the area of landscape-nursery work. Additional study at the collegiate level could lead to the positions of a landscape architect, horticultural extension agent, or other professional occupations.



### Landscape Architect

The landscape architect is a professional designer and often overseer of large scale land development projects. Typical projects involve land use for industrial parks, large residential subdivisions, parks, schools, highways, and golf courses. Some landscape architects specialize in residential and industrial designing. Development of landscape designs demands an extensive knowledge of plant and structural materials, engineering, art appreciation, and the mechanics of design. A landscape architect may operate his own firm, or may be employed by a large one. Entry into the profession generally comes through completion of a four year college training program and practical experience. Some states require an examination for a state license before one may practice as a landscape architect.

For more information see Careers as Landscape Architect and Landscape Nurseryman, Reference No. 7.





#### Landscape Designer

The landscape designer is a professional designer who generally specializes in residential and small-scale designs. Development of these designs demands an extensive knowledge of plant and structural materials, engineering, art appreciation, and the mechanics of design. A landscape designer may operate his own firm, or might be employed by a landscape nurseryman or a garden store.

A great need for landscape designers is developing. This is because landscape architects cannot keep up with the demands for their services on residential and other smaller properties. Landscape designers are not required to hold a license to practice in most states.

The amount of knowledge required of a good landscape designer is such that two years of study beyond the high school level is necessary for the development of the needed knowledge and skills.

For more information see Careers as Landscape Architect and Landscape Nurseryman, Reference No. 7.



#### Horticultural Extension Agent

Persons in a position as horticultural extension agent instruct, advise, and inform individuals and organizations regarding horticultural problems. Lecturing, demonstrating recommended practices, preparing extension publications, and problem solving are examples of the types of duties performed. This is a professional field demanding at least a four year college education in horticulture. Experience in nursery and turf industries are extremely helpful.

For further reading see Handbook of Agricultural Occupations, Reference No. 21, pp. 189-212.



#### Landscape Nurseryman

The landscape nurseryman designs, establishes, and maintains small scale landscaping projects. He may also establish a landscape from plans developed by a landscape architect. Many landscape nurserymen operate nursery or garden centers. The landscape nurseryman must have extensive knowledge of plant materials, their care, and their uses. He needs to understand landscape design, construction, and business principles. Entry into the profession is through technical training and work experience. A college education is desirable, but not essential.

More details are given in Careers as Landscape Architect and Landscape Nurseryman, Reference No. 7, and The Nursery Business, Reference No. 50.

## PROBLEM AREA 2

### IMPORTANCE OF LANDSCAPING

#### Student Learning Objectives

The primary objectives of this problem area are to:

1. Develop an understanding of the reasons for landscaping.
2. Develop an appreciation for the economics and aesthetic value of landscaping.

#### Key Questions

1. Why is it important to landscape a home and/or large-scale land development project?
2. What determines the type of landscaping to be applied to an area of land?
3. What are the benefits received from landscaped property?
4. How does landscaping increase property value?

#### New Words

Aesthetic values - personal values of persons for the beautiful and the satisfying

Utility - useful, having a purpose

#### Importance of Landscaping

A site is landscaped to increase its usefulness, beauty, and economic value. Residential property space is usually scarce and existing living areas crowded. Therefore, a landscape plan is needed to make the best use of the available space in providing for the needs of the homeowner. The same reasons extend into park and industrial site planning. They also apply to city and regional land use planning.

For further reading see Landscape Architecture: The Shaping of Man's Environment, Reference No. 27, Sunset - Landscaping for Modern Living, Reference No. 48, pp. 7-16, and Urban Landscape Design, Reference No. 56.



Figure 1. A well-designed landscape is useful and pleasing to the eye.

#### Landscaping for Use

Proper landscaping should have utility as well as beauty. Walks, drives, patios, and parking areas are necessary in order to carry on the daily routine of the family. Walks and drives should be constructed to provide ready access to the house, garage, and terrace. The walks and drives should be an appropriate size for comfortable use. They should be durable, non-slippery and as attractive as possible. Their placement should make allowances for attractive positioning of plant materials. Likewise, parking areas can be located and shaped so that they are useful and attractively blend into the landscape. They may be shaped to be useful for both parking and outdoor games, such as basketball, and still be aesthetically pleasing.

#### Landscaping for Beauty

One purpose of a landscape is to provide an attractive environment for the owner, the neighbors, and passing traffic. Streets with well landscaped houses give a good impression. Their beauty reflects the owner's pride in the appearance of his home ground.

An attractively landscaped house is aesthetically pleasing. People see and appreciate the beauty that can be added with plant and structural materials and take pride in their landscaped property. If a neighbor's property is well landscaped, the homeowner can enjoy the view rather than having to screen out unattractive off-site factors.

The public's opinion of an area largely depends upon its landscaping. Neighborhoods with attractively landscaped properties usually have a reputation of being a good section in which to live. Neglected landscapes create a "negative" impression of the neighborhood.

#### Landscaping Increases Property Value

Good landscaping improves the value of the property in several indirect ways. The house will be more appealing to a prospective buyer because of the usefulness and attractiveness of the landscape features. Buyers also realize the value of having an established landscape rather than having to bear the expense and effort involved in establishing landscape materials around a new house. An attractive landscape in a good section of the city may be the final selling point needed to complete the sale of the house.

An established landscape also can be enjoyed immediately rather than having a delay of several years until a new landscape becomes established. In dollars and cents, an established and well designed landscape adds approximately ten percent to the value of the property. The value increases each year as the plant materials, especially trees, grow toward maturity.

Landscaping will continue to become more important as more people become aware of how well landscaped homes, commercial establishments, and public areas contribute to their convenience, comfort, and feeling of well being.

## PROBLEM AREA 3

### ANALYSIS OF LANDSCAPE REQUIREMENTS

#### Student Learning Objectives

Before a landscape can be planned and installed, the landscape designer must be able to think through the landscape requirements. Therefore, the basic objectives of this problem area are to learn how to:

1. Determine the landscape needs of both a site and the family living on the site.
2. Develop the ability to integrate site analysis and family needs.
3. Develop the ability to use the "Site Analysis Check Off List" and the "Analysis of Family Needs Check-Off List."

#### Key Questions

1. How are the landscaping needs of a site determined?
2. What equipment is needed to analyze landscape requirements?
3. Of what importance is the relationship of on-site factors to off-site factors?

#### New Words

Compromise - to unite two or more opposing factors (example-different family desires for a landscape design)

Easements - rights-of-way for utilities (sewers, power lines, etc.)

Field Stone - flat stone gathered from a field

Rock Outcropping - rocks exposed above ground level but firmly anchored in the ground

Stabilize - to be made lasting, without movement, permanent

#### Site Analysis

The term "site" refers to the area being landscaped. One of the more important types of basic information needed before developing a property design is an evaluation of the site. One must actually visit the site to perform the evaluation. The site analysis includes both "on-site" factors (the house and lot area) and "off-site" factors (neighboring properties, distant views, etc.).

10/11

For further reading see Budget Landscaping, pp. 120-145, Reference No. 6, Sunset - Landscaping for Modern Living, pp. 17-34, Reference No. 48, The Art of Home Landscaping, pp. 17-76, Reference No. 49.

The "Site Analysis Check-Off List" is a helpful guide for determining the basic information needed for landscape planning. Detailed information is gathered at the property by filling out this form. After each item has been plotted on the plan, it is checked off on the list.

It is easiest to draw the site features on graph paper while one is on the site. See page 19 for instructions on drawing. The following equipment should be taken on the first visit: (1) drawing boards, (2) a T-square, (3) an architectural scale, (4) a directional compass, (5) an art gum eraser, (6) No. 2 or No. 3 pencils, (7) graph paper (1 inch equals 8 feet scale preferred), (8) an 8 inch, 30° - 60° triangle, (9) a 50-foot metal tape, (10) a drawing compass, (11) spring clips, (12) a carpenter's string, (13) stakes, and (14) a string level. A second person will be needed for taking measurements. For taking a soil sample, a spade and a one-pint jar will be needed.

The drawing, the "Site Analysis Plan," is the first in a series, each based on information added to the previous one(s). The series includes: (1) The Site Analysis Plan, (2) The Area Layout Plan, (3) The Structural Plan, (4) Planting Plan, and (5) The Finished Landscape Plan.

#### On-Site Factors

When conducting an on-site evaluation, detailed information concerning the property should be gathered and plotted on a site analysis plan. The data must be collected in the field in rough form and brought back to the office where it can be carefully plotted to scale on a base plan. Accuracy of the plan may have to be checked by a second visit to the site. If the owner or builder can give you a property plan prior to the first visit to the site, data collection may be simplified. Such a plan must still be redrawn upon return to the office. This on-site evaluation must be exact and detailed. Each of the following must be carefully noted:

Slopes: Be careful to note both the direction and the amount or degree of the slope. The information will be necessary later to






Figure 2. Contour lines may be determined and plotted by using the following steps:

1. Start at one point, A, for example, and call it 100 ft. in elevation. Plot it on your plan.
2. Drive a stake in the ground at any convenient distance down hill, (A').
3. Run a string from A to A'; level the string by means of a string level.
4. Measure the distance along the string from A to A'; mark this point on your plan.
5. Measure the distance from the point where the string is tied to the stake, A', to the base of the stake, B.
6. Subtract this measurement from 100 ft. and you have the elevation of point B, (94 ft.).
7. Knowing the elevation of point B, you can find the elevation of the base of the tree, B', by following the steps given in 1 through 6.
8. By a similar procedure, you can determine a number of elevation points, plot them on the plan, and draw contour lines joining all the points having the same elevation.
9. Contour lines are usually plotted in 2 ft. intervals for residential plans, (often in terms of feet above sea level because this eliminates negative numbers).




Figure 3. Plotting the exact location of a house on a lot is most easily done by making careful measurements from two lot corner pins for each corner of the house. For example, the precise location of house corner "I" is determined by measuring the distance from Pin "A" and Pin "D".

develop the lot. Direction and amount of slope contours are most important in determining the drainage pattern. In cases of steep slopes, contour lines will have to be established on the plan. See Budget Landscaping, Reference No. 6, and Landscaping Your Home, Reference No. 36, p. 25. A simple way to determine contours is shown in Figure 2.

Soil: Note the type, depth, fertility, structure, and drainage qualities of the soil on the site. Soil type refers to whether it is a clay, loam, or sandy soil. Each type of soil has a different influence on the development of the site. Take soil samples and have them analyzed. In cases of poorly drained sites, drainage tile lines may be needed.

Rock outcroppings: Some rock outcroppings have charm and beauty which can be blended into a landscape; others simply present difficulties and must be removed. It is important to show on the site plan the type of rock and the size and location of outcroppings.

Water: Every site plan must include information on the location of springs, brooks, marshy terrain, ponds, and other bodies of water if present.

Existing vegetation: The size, shape, age, condition, location and species of existing trees, shrubs, and plant beds must all be included in the site evaluation. Also, the size and condition of grass and bare soil areas should be indicated.

Structures: Structures on the site are evaluated in terms of location, exposure and orientation, type, style, condition, and construction. Examples of structures include walls, drives, walks, patios, homes, and fences. The exposure of structures to prevailing winds and their orientation to the sun will influence the selection of plant material. The method for determining the exact location of the building on the site is shown in Figure No. 3.

Climate of site (micro-climate): Record information about the amounts of sun, wind, and shade for each area of the site. Determine the hardiness zone, winter temperature range, prevailing winds, and average summer rainfall. These factors may restrict later plant material selections.

Utilities: Underground and overhead utilities should be plotted on the site map. The information will enable the designer to avoid planting trees where their branches or roots will interfere with water pipes or electric lines.

Legal Aspects: Plot boundary lines, rights-of-way, and setbacks on the site plan. Notes regarding deed restrictions, easements, and building and zoning regulations must be made. Some city ordinances will not permit obstruction of a view across a corner. Some will not permit planting of certain undesirable trees such as poplars and female boxelders. Some have restrictions on fence dimensions and locations. And others restrict out-building construction.

#### Off-Site Factors

The analysis of off-site factors means to consider the site in relation to distant views and neighboring areas. Common examples of favorable views include mountains, valleys, bodies of water, forests, towns, and cities (especially at night). Neighboring properties have a distinct influence upon a site's landscape needs. A mature oak tree may be located ten feet outside a portion of the site being landscaped, but visually it becomes part of the landscape picture. If a neighbor has a pleasant-looking backyard, the view of his landscape may be accented. Sometimes control of pedestrian traffic across the property becomes necessary. Noise, dust, and bright lights sometimes present problems. Sometimes it is desirable to screen portions of the view into neighboring properties. Common examples of unfavorable views include utility lines, billboards, roads, schools, factories, junkyards, and unkempt neighboring yards.

Study the following Site Analysis Check-Off List (pp. 17-18) and the Site Analysis Plan (p. 19). You may wish to analyze your own home site using the check-off list. Suggest to your teacher that the class select a newly built home in the community and develop a Site Analysis Plan.

SITE ANALYSIS CHECK-OFF LIST

Location \_\_\_\_\_ Lot No. \_\_\_\_\_ Date \_\_\_\_\_  
Client Name \_\_\_\_\_ Telephone No. \_\_\_\_\_

On Site Factors

Lot: Dimensions - length \_\_\_\_\_ width \_\_\_\_\_ plotted \_\_\_\_\_  
Rights-of-way \_\_\_\_\_ plotted \_\_\_\_\_  
Easements \_\_\_\_\_ kind \_\_\_\_\_ plotted \_\_\_\_\_  
Legal restrictions - setback \_\_\_\_\_ plotted \_\_\_\_\_  
lot lines \_\_\_\_\_ plotted \_\_\_\_\_  
corner obstruction \_\_\_\_\_ plotted \_\_\_\_\_  
fence, setback \_\_\_\_\_ height \_\_\_\_\_  
length \_\_\_\_\_ type \_\_\_\_\_  
outbuilding \_\_\_\_\_  
trees not permitted -  
boxelder (female) \_\_\_\_\_ poplar \_\_\_\_\_  
willow \_\_\_\_\_ other \_\_\_\_\_

Sidewalk: Installed \_\_\_\_\_ location plotted \_\_\_\_\_  
Not installed \_\_\_\_\_ future location plotted \_\_\_\_\_  
done by owner \_\_\_\_\_ city \_\_\_\_\_  
Never to be installed \_\_\_\_\_ Contours plotted \_\_\_\_\_  
Drainage - adequate \_\_\_\_\_ inadequate \_\_\_\_\_  
install tile lines \_\_\_\_\_ plotted \_\_\_\_\_  
Soil type - clay \_\_\_\_\_ loam \_\_\_\_\_ sand \_\_\_\_\_ muck \_\_\_\_\_  
Soil sample taken \_\_\_\_\_  
Soil test results - pH \_\_\_\_\_ N \_\_\_\_\_ P \_\_\_\_\_ Ca \_\_\_\_\_ other \_\_\_\_\_  
Rock outcropping \_\_\_\_\_ plotted \_\_\_\_\_

Water : Spring \_\_\_\_\_ brook \_\_\_\_\_ pond \_\_\_\_\_ marsh \_\_\_\_\_ other \_\_\_\_\_ plotted \_\_\_\_\_

Existing vegetation:  
Trees \_\_\_\_\_ species \_\_\_\_\_ height \_\_\_\_\_ width \_\_\_\_\_ plotted \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Shrubs \_\_\_\_\_ species \_\_\_\_\_ height \_\_\_\_\_ width \_\_\_\_\_ plotted \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Turf areas \_\_\_\_\_ plotted \_\_\_\_\_  
satisfactory \_\_\_\_\_ renovate \_\_\_\_\_ replace \_\_\_\_\_  
Bare soil \_\_\_\_\_ plotted \_\_\_\_\_

Structures: House \_\_\_\_\_ length \_\_\_\_\_ width \_\_\_\_\_ plotted \_\_\_\_\_  
 Front faces north \_\_\_\_\_ east \_\_\_\_\_ south \_\_\_\_\_ west \_\_\_\_\_  
 other \_\_\_\_\_  
 Style \_\_\_\_\_ color(s) \_\_\_\_\_  
 Material - brick \_\_\_\_\_ frame \_\_\_\_\_ stone \_\_\_\_\_ other \_\_\_\_\_

Outer Buildings - length \_\_\_\_\_ width \_\_\_\_\_ plotted \_\_\_\_\_  
 Materials \_\_\_\_\_ plotted \_\_\_\_\_  
 Driveway \_\_\_\_\_ width \_\_\_\_\_ length \_\_\_\_\_ material \_\_\_\_\_ plotted \_\_\_\_\_  
 Walks \_\_\_\_\_ width \_\_\_\_\_ length \_\_\_\_\_ material \_\_\_\_\_ plotted \_\_\_\_\_  
 Terraces \_\_\_\_\_ width \_\_\_\_\_ length \_\_\_\_\_ material \_\_\_\_\_ plotted \_\_\_\_\_

Climate: Hardiness zone \_\_\_\_\_ on plan \_\_\_\_\_ prevailing wind direction \_\_\_\_\_  
 on plan \_\_\_\_\_  
 Orientation - north indicated on plan \_\_\_\_\_ shade areas plotted \_\_\_\_\_  
 sunlight control area plotted \_\_\_\_\_  
 wind control area plotted \_\_\_\_\_  
 snowdrift control area plotted \_\_\_\_\_

Utilities: Overhead poles plotted \_\_\_\_\_ wires plotted \_\_\_\_\_  
 Underground water line \_\_\_\_\_ plotted \_\_\_\_\_  
 water valve \_\_\_\_\_ plotted \_\_\_\_\_  
 electric lines \_\_\_\_\_ plotted \_\_\_\_\_  
 electric meter \_\_\_\_\_ plotted \_\_\_\_\_  
 drainage lines \_\_\_\_\_ plotted \_\_\_\_\_  
 septic tank \_\_\_\_\_ drainage field \_\_\_\_\_ plotted \_\_\_\_\_  
 dry wells \_\_\_\_\_ plotted \_\_\_\_\_  
 gas line \_\_\_\_\_ plotted \_\_\_\_\_  
 gas valve \_\_\_\_\_ plotted \_\_\_\_\_  
 gas meter \_\_\_\_\_ plotted \_\_\_\_\_

Off Site Factors

Favorable views -

Kind _____	height _____	width _____	season _____	plotted _____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

Unfavorable views -


Kind _____	height _____	width _____	season _____	plotted _____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

Pedestrian traffic: Control needed \_\_\_\_\_ not needed \_\_\_\_\_ pattern plotted \_\_\_\_\_

Noise: Control needed \_\_\_\_\_ area plotted \_\_\_\_\_

Dust: Control needed \_\_\_\_\_ area plotted \_\_\_\_\_

Bright lights: Car \_\_\_\_\_ parking \_\_\_\_\_ neighbor \_\_\_\_\_ other \_\_\_\_\_ area plotted \_\_\_\_\_



Underground  
Elect.  
&  
Tele.

N  
Wind

Back of site kept fairly open to visually  
borrow space from other properties.

Screening for privacy  
and to enclose the  
service area.

Screening needed to insure  
privacy and create inclosure.

Immediate access to  
living areas of house

service and  
play area.

Entry

Lightly screen  
entry

Water & Sewage  
88

Plant Hardiness Zone V

Scale: 1/16" = 1'

150'

### Analysis of Family Needs

An analysis of family needs is an important beginning point for providing information necessary for designing home grounds. Each family has a personality of its own. All members of the family should be asked to list facilities for outdoor activities and outdoor living needs which they desire. To any such list must be added basic plantings and structures necessary to make the site livable. For example, walks, steps, drives, terraces, play areas, and turf to prevent erosion are usually necessary. The need for shade or windbreaks should be considered. Owner preferences for types of materials and plants should be noted.

Family size and ages influence the landscape design. Young parents with large families will want facilities designed for the play of small children. In this situation, an area might need to be set aside for swings, a sandbox, a slide, etc. Areas such as these which are somewhat "temporary" should be designed to allow for different uses in the future. Planning for hobbies and sports must be considered. Some common facilities which can be included in the landscape plan are badminton courts, croquet courts, flower and vegetable plots, and possibly a pool for swimming. Families who enjoy the outdoors would require hard surfaced areas such as a terrace or a patio. Outdoor sculpture, planters, or benches might be a part of the terrace. People wishing to entertain, eat, or simply relax outdoors may desire screening and/or plantings to provide privacy. An active family that does not wish to spend time maintaining its residence will demand landscape planning which reduces maintenance to a minimum. When several family members want conflicting facilities included in the landscape plan, it is necessary to compromise.

Most homeowners want landscape features that are not only useful, but also beautiful and pleasing to the eye. An example, in many situations a field-stone wall has aesthetic values which are preferred to those of one made from concrete block.



While economics may establish absolute cost limits for landscaping costs, the capable designer usually can design an attractive landscape which will satisfy family needs at a modest cost. One way to estimate an appropriate cost is to work within a figure of ten percent of the value of the house and land. Many homes are beautifully landscaped for much less. Economic limitations of the family will often limit the landscaping plans. Execution of the landscape plan is sometimes done in stages over a three to four year period in order to spread the cost over a longer period of time.

Study the following Analysis of Family Needs Check-Off List. Suggest to your teacher that the class complete this form, preferably using the same home for which the Site Analysis Plan was prepared. Study Figure 2 to develop skill in drawing items in the Site Analysis Plan.




Figure 4. Scale. If you measure the diameter of the large circle (representing a small tree) in each sketch, and compare it with the scale indicated for that sketch, you will find that the tree is the same size in sketches "A," "B," and "C".

All objects represented in a drawing are assumed to be drawn to the scale indicated on the drawing, unless it is labeled "not to scale."

ANALYSIS OF FAMILY NEEDS CHECK-OFF LIST

Location \_\_\_\_\_ Lot No. \_\_\_\_\_ Date \_\_\_\_\_

Client Name \_\_\_\_\_ Telephone No. \_\_\_\_\_

Number of Children - Pre-school \_\_\_\_\_ Elementary \_\_\_\_\_ High School \_\_\_\_\_

Activities

Needs

Entertaining: Paved area - capacity (people) \_\_\_\_\_ size \_\_\_\_\_  
color \_\_\_\_\_ material \_\_\_\_\_ plotted \_\_\_\_\_

Shade - canopy \_\_\_\_\_ trellis \_\_\_\_\_  
umbrella \_\_\_\_\_ tree \_\_\_\_\_ plotted \_\_\_\_\_

Seating - benches \_\_\_\_\_ capacity \_\_\_\_\_  
no. \_\_\_\_\_ style \_\_\_\_\_ plotted \_\_\_\_\_

chairs \_\_\_\_\_ no. \_\_\_\_\_ style \_\_\_\_\_ plotted \_\_\_\_\_

chairs - folding \_\_\_\_\_ no. \_\_\_\_\_ style \_\_\_\_\_  
storage \_\_\_\_\_

tables \_\_\_\_\_ no. \_\_\_\_\_ style \_\_\_\_\_ plotted \_\_\_\_\_

table - dining \_\_\_\_\_ capacity \_\_\_\_\_ style \_\_\_\_\_  
plotted \_\_\_\_\_

Garden lighting \_\_\_\_\_ kind \_\_\_\_\_ style \_\_\_\_\_ no. \_\_\_\_\_ plotted \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Cooking: Grill - permanent \_\_\_\_\_ size \_\_\_\_\_ style \_\_\_\_\_ plotted \_\_\_\_\_  
portable \_\_\_\_\_ size \_\_\_\_\_ style \_\_\_\_\_ storage plotted \_\_\_\_\_

Table - work \_\_\_\_\_ dimensions \_\_\_\_\_ style \_\_\_\_\_ plotted \_\_\_\_\_

Storage for cooking \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_

Electrical outlets \_\_\_\_\_ no. \_\_\_\_\_ plotted \_\_\_\_\_

Games: Croquet \_\_\_\_\_ dimensions \_\_\_\_\_ 30' x 60' plotted \_\_\_\_\_

Badminton \_\_\_\_\_ dimensions \_\_\_\_\_ 24' x 54' plotted \_\_\_\_\_

Bowling on the green \_\_\_\_\_ dimensions \_\_\_\_\_ 10' x 50' or 20' x 100' plotted \_\_\_\_\_

Volleyball \_\_\_\_\_ dimensions \_\_\_\_\_ 40' x 70' plotted \_\_\_\_\_

Basketball hoop \_\_\_\_\_ dimensions \_\_\_\_\_ 40' x 40' plotted \_\_\_\_\_

Tetherball \_\_\_\_\_ dimensions \_\_\_\_\_ 20' dia. circle plotted \_\_\_\_\_

Horseshoes \_\_\_\_\_ dimensions \_\_\_\_\_ 20' x 40' plotted \_\_\_\_\_

Archery \_\_\_\_\_ dimensions \_\_\_\_\_ 20' x 100' min. plotted \_\_\_\_\_

Putting green \_\_\_\_\_ dimensions \_\_\_\_\_ 30' dia. circle min. plotted \_\_\_\_\_

Shuffleboard \_\_\_\_\_ dimensions \_\_\_\_\_ 6' x 45' plotted \_\_\_\_\_

Other \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_

Game storage \_\_\_\_\_ length \_\_\_\_\_ width \_\_\_\_\_ height \_\_\_\_\_  
plotted \_\_\_\_\_

Playing: Sandbox \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_

Swings \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_

Slide \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_

Playhouse \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_

Monkeybars \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_

Wading pool \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_

Blackboard \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_

Other (specify) \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_

Storage, wheel toys, etc. \_\_\_\_\_ dimensions \_\_\_\_\_ plotted \_\_\_\_\_



Activities

Needs

Laundry: Lines - permanent \_\_\_\_\_ linear ft. \_\_\_\_\_ plotted \_\_\_\_\_  
 temporary \_\_\_\_\_ linear ft. \_\_\_\_\_ plotted \_\_\_\_\_

Storage: Trash \_\_\_\_\_ no. containers \_\_\_\_\_ sq.ft. required \_\_\_\_\_  
 plotted \_\_\_\_\_

Trailers \_\_\_\_\_ dimensions required \_\_\_\_\_ plotted \_\_\_\_\_

Boat \_\_\_\_\_ dimensions required \_\_\_\_\_ plotted \_\_\_\_\_

Other - specify \_\_\_\_\_ sq.ft. required \_\_\_\_\_  
 plotted \_\_\_\_\_

COST

Approximate landscaping allowance (based on about 10% of the market value of the house and land): \$ \_\_\_\_\_.

Cost limitation set by client: from \$ \_\_\_\_\_ to \$ \_\_\_\_\_.

Execution period:

Years	Approximate cost per year
1 _____	_____
2 _____	_____
3 _____	_____
4 _____	_____

### Area Layout Plan

By working simultaneously with the site analysis and the analysis of the family needs, the landscape designer can combine all the ingredients to give a useful and pleasing plan. Ingenuity is sometimes needed to solve some of the problems. Compromise solutions may be necessary.

At this point an Area Layout Plan is usually developed (see p. 27). A sheet of tracing paper is fastened firmly in place over the Site Analysis Plan, and the designer does some "doodling" on the tracing paper by drawing on it a large circle indicating the approach (public) area of the property. This is usually at the front of the house toward the street, but is sometimes at the side of the house. Its primary function is to provide easy and pleasant access to the house.

Next, the designer sketches in an area to be designated as the Service Area. This is the area where the trash containers are kept. It may include an outdoor work area, a clothes drying yard, or a dog run. It is desirable to screen these functions and activities from view.

The third area is the private area. It is usually at the rear of the house, but may be at the side, or, in unusual cases, at the front of the house. This area usually requires some screening to provide privacy, but may also require lawn areas for games, paved areas for entertaining, and garden areas for flowers and vegetables.


After designating the three areas, the approach area, the service area, and the private area, you should roughly sketch in some ideas to show how the parts of them may be organized. Indicate where the driveway will be. Show also the location of the walk that will lead from the street or driveway to the door of the house. You might want to sketch in the location of the clothes lines in the service area. You may wish to put in dotted lines to indicate a lawn space for badminton, or sketch in a tentative position for a paved terrace.

First consideration should be given to size, shape, and placement of structures designed to make the site livable (walks, etc.). Occasionally, features such as drives can serve a dual purpose as sport or entertainment areas. Using off-street parking for a basketball court is an example.

Space for sport and recreation facilities must be well selected and planned. Remember that the space needed for playing badminton or gardening is more readily satisfied on the small lot than the space needed for playing baseball. When possible, combine land uses. For example, the area needed for the lawn and the area needed for badminton might be combined. (See A Guide to Home Landscaping, pp. 201-226, Reference No. 1).

Legal restrictions usually play a minor role in compromising family desires with the landscaping limitations of small landscapes. The most common legal restrictions designate: (1) what types of trees cannot be planted along utility lines, (2) the height of fences and walls between abutting properties, (3) drainage regulations, and (4) deed restrictions. Legal restrictions usually benefit the whole community and do not handicap the designer.

Study the Area Layout Plan on page 27. Follow up the Site Analysis Plan by developing an Area Layout Plan. Preferably, this should be for the same residence used in the development of the Site Analysis Plan.



Plant Hardiness Zone V

Scale: 1/16" = 1'

## PROBLEM AREA 4

### IDEAS FOR SOLVING LANDSCAPE PROBLEMS

#### Student Learning Objectives

The primary objectives of this problem area are to:

1. Understand the functions of the three parts of a landscape - the public area, the private area, and the service area.
2. Develop the ability to lay out the three landscape areas in accordance with the integrated family needs and Site Analysis Check-Off Lists.
3. Develop an understanding and a working knowledge of a variety of solutions to landscape problems.

#### Key Questions

1. What are the three major areas of a landscape? What are their separate purposes? How can they be combined?
2. What are the important considerations a landscape designer needs to be aware of when designing the public area? The private area? The service area?
3. How can a landscape designer keep up to date with new ideas for landscape designs?

#### New Words

Accented - made to stand out

Adjoining - next to, connecting, bordering

Balance - appearing to be stable because of equally distributed  
"weight"

Canopy - covering, plant cover, overhead structure that shades and  
shelters the material below

Complimented (complementary) - making complete

Components - the single parts of a whole item

Contrasted - opposite to or different from

Design - a plan

Dominant - ruling or controlling influence

Embellishment - that which adds beauty or elegance



Focus - to attract attention to an object

Harmonious - having parts that blend together

Incinerator - furnace for burning trash

Objectional - not suitable, undesirable

Proportion - size relationship of one object to another or the whole

Restricted - to be limited or confined

Rhythm - a feeling of free-flowing

Scale - size relationships

Specimen - a single plant

Subordinate - not as important as another item

Technique - method or procedure of performing a function or duty

Underplantings - plants growing or planted under a taller plant canopy

Unity - put together in such a way that the parts obviously belong to a whole

#### Layout of the Landscape Areas

As we indicated in the last unit the site to be landscaped is usually divided into three sections: the public area, the private area, and the service area. Each area is landscaped for different purposes; however, all three must be designed to blend together well.

In the home landscape, the public area is what is seen by people as they pass by the house or approach it. In general, this area includes the land located between the house and the street. Corner lots have larger public areas than others. The driveway, front walk and plantings, some side plantings, and a lawn area usually make up the areas to be landscaped in the public area. In some locations the public area may be very small. These public area components are designed to give the house an attractive setting on the lot.

On a home site the private area is often located behind the house and screened from public view. A private area is an extension of the living and relaxation areas of the house; therefore, it is often located near the dining room, living room, or family room of the house.

This area is used mainly by the family for games, outdoor hobbies, parties, and relaxation. The design of the private area should consider the family's needs for sports, hobbies, and outdoor fun. The plan must also consider the amount of family time and money available for maintenance of the area. The maintenance of a complicated landscape can become a burden rather than a pleasure.

The service area is a work area; it is developed primarily for its utility. Some common things included in the service area are:

Clotheslines	Play areas
Trash and garbage cans	Vegetable and flower gardens
Incinerators	Cold frames
Equipment storage shed	Compost bin

The needs of an owner will determine the size and degree to which the service area must be developed. His desires should be discussed before locating and developing the service area. The service area is best located where it is easy to get to from the house - especially the kitchen, utility room, and garage. Play areas for children should be easily seen from the kitchen. Large service areas may be divided. Place commonly used items, such as trash cans, near the kitchen and less often used items, such as vegetable and flower gardens, further away.

You may wish to do some further reading about these three areas of the residential landscape in Budget Landscaping, Reference No. 6, pp. 9-14.

#### Ideas for Solving Landscaping Problems

Before developing the landscape plan further, it would be a good idea to learn more about landscaping ideas. The more ideas you can get, the better equipped you will be to make a satisfactory landscape plan.

How does one emphasize the front entry? How can one "lead" people easily from one area to another? How can one "play down" a service door next to the front entry? What should be done with a main entrance that is at the side of the house instead of at the front?

How can one make a small area appear larger? How does one make a tall house seem lower; a low one taller; a long one shorter?

How many ways are there to screen an objectionable view; enhance a pleasant view? Where would one use a partial screen?

How can you "control" pedestrian traffic; keep people from driving off the driveway?

How can you block noise; filter out dust?

What are some alternative solutions for getting people easily up a steep slope? How can you make a steep slope appear lower? How does one control erosion on a steep slope?

What shapes have been used for paved terraces? What materials may be used? How does one get "instant shade" for a terrace? What are some practical kinds of outdoor furniture?

How much space is needed for hanging laundry outdoors? What temporary devices can be used for hanging laundry? How can you hide a vegetable garden; a compost bin; a dog yard?

Answers to many of these questions can be found in your own or nearby residential areas. Look over your neighbors' properties and see what ideas they have used. Additional ideas can be obtained from garden magazines. The "Sunset" booklet series and other books may be helpful. Study the sections of this book on landscaping the public, private, and service areas. Explore the section on selection of landscape structures.

Professional landscape architects and designers make a life-long study of solutions to landscape problems. Many accumulate extensive clipping files and photograph files for ideas to help them in their work. You may wish to start such a collection.

When you find yourself making a "critique" of every home you pass as you walk down the street, you are ready to assemble ideas into a "Structural Plan" and "Alternative Structural Plan" for the home grounds. These can be added to the "Site Analysis Plan" and the "Area Layout Plan" which you have already developed.

The following references give many ideas for solving landscape problems:

Sunset - Landscaping for Modern Living, Reference No. 48, pp. 35-58, 161-164.

Sunset - Garden Plans, Reference No. 48.

Sunset - How to Improve Your Home by Landscaping, Reference No. 25.

The Art of Home Landscaping, Reference No. 49, pp. 77-112, 143-184.

Gardens Are for People, Reference No. 18.

Landscaping Your Home, Reference No. 35

Landscape Planning, Reference No. 30.

Budget Landscaping, Reference No. 6, pp. 15-107.

#### Landscaping the Public Area

Start to develop some ideas for landscaping the public area by viewing it from the street, from the driveway, and from the walk leading to the main entrance. Good references are Sunset - Landscaping for Modern Living, Reference No. 48, pp. 75-84, and Sunset - Ideas for Entries and Front Gardens, Reference No. 48.

#### Planning Walks and Drives

Walks and driveways must be located to provide means for easy entrance and exit from properties. Wide use of the automobile has influenced the placement of walks. People often enter a property through the driveway. For this reason, many walks are placed to lead to the main entrance from the driveway. This design feature avoids splitting of the public area into small sections. Sometimes, when the house is near the street or when the parking area is behind the house, it is easier and more attractive to have the front walk lead directly from the street. All walks and steps should be at or near ground level. They should not be more than one inch above the ground. A walk should be at least four feet wide so two people may use it at the same time; six feet would be better. A drive should be at least 12 feet wide to allow passengers to alight on paving. Walks and drives should be straight unless there is an obvious physical reason for making them otherwise. It is difficult to drive on tightly curved driveways because the driver cannot see well enough to avoid accidentally driving on the lawn.

### Establishing a Focal Point

Next, study the house and any plant material present in the public area. Picture what must be done to lead the viewer's eye to the most important feature - the front entry. A formula for doing this is to make a sketch to scale of the front of the house or place a sheet of tracing paper over a photograph and make a sketch. Then make three points: one at the bottom center of the door, one at a point about  $\frac{2}{3}$  of the distance up the left corner of the house, and one  $\frac{2}{3}$  of the distance up the right corner of the house. Sketch in two dotted lines that join the dots on the corners with the dot at the door. Plantings that do not extend above these lines will give a "V" pattern which directs the eye toward the door. This emphasis upon one object is called "focus". Figure 11 illustrates how this may be done. If the foundation wall is low, the lawn may extend to it for about  $\frac{1}{3}$  of the wall space.



Figure 5. A beautiful house needs complementary landscaping. This is the "site analysis" stage.



Figure 6. Trees unify the planting.

#### Grouping Trees and Shrubs

Trees establish a size relationship (or "scale") between the house and other parts of the landscape, (See Figure 10). Houses with dominant horizontal lines may be contrasted by the vertical lines of tree trunks. A tall house with vertical lines may be "tied" to the ground with large trees of rounded form. Often a canopy of tree branches over the house will help soften the lines of the house. Trees may provide a "frame" for the house. (See Figure 7). This may be done by planting them between the house and the sidewalk at an angle off each front corner of the house. Trees planted at the rear of the house form a background and unify the planting scheme. You should at the same time keep in mind that trees should be planted about 20 feet southwest of an area where shade is needed, such as a terrace or southfacing windows. (See Figure 8).

Care must be taken to select trees which will mature at a height in scale with the house. Small to medium height trees should be used with one-story houses. Trees which mature at low heights can be used to screen views in front of the house. On some occasions these low maturing




Figure 7. Trees may be used for background and enframement.




Figure 8. Trees provide shade on a terrace.

trees or similar height shrubs may be positioned to prevent people who pass by the public area from looking directly into the picture window. Place the plants in the line of sight, but at some distance from the window. This is one means for giving privacy to owners of a house with a picture window facing the street. Standard trees should be spaced no closer than 40 to 60 feet apart, while smaller growing species are planted 10 to 20 feet apart. (See Figure 10.)



Figure 9. Shrubs form a low enclosure at the house entrance.

After the proper positioning for trees has been determined, the placement of shrubs should be decided. Shrubs are usually thought of as tall (8 to 10 ft.), medium (4 to 6 ft.), and short (2 to 4 ft.). Within each size group there are upright, rounded, and spreading forms. The groups may be divided into deciduous, needle-leaved evergreens, and broad-leaved evergreens.





Figure 10. Scale (Size Relationship). Tall trees make a tall house seem shorter; small trees make a one-story house seem taller.

Appropriate spacing of shrubs will avoid either a "choked" or "gapisis" appearance when they reach mature size. Most shrubs are spaced the same distance from center to center as the mature width. Shrub centers should be from 4 to 6 feet from a house, wall, or fence. Hedges are planted much closer together than other plants.

In a highly formal planting, there are equal numbers of shrubs on each side of a dominant landscape feature. This balance may be gained with equal amounts of material (equal numbers and placement of species) placed in beds on both sides of the dominant feature (or "focal point"). Informal landscapes do not require such rigid planning of balance. In informal plantings small "heavy" looking plant groups may be balanced by larger amounts of "lighter" looking materials.




Figure 11. Focus on the entrance is obtained by selecting plant forms that fit within the dotted lines. Note that "C" illustrates symmetrical balance, while "A", "B", and "D" show asymmetrical balance; in both cases the visual "weight" is equal on opposite halves of the house.




Figure 12. Corner plantings. A. Rounded deciduous shrub with low, spreading evergreens. B. Small tree with low, rounded evergreens.

Developing proper balance requires planning as to plant shapes, forms, textures, and colors. When plant and structural materials are in proper balance, attention is drawn to the focal point, which is often the entrance to the house.



Figure 13. The viewer is led visually to the front entrance.




Figure 14. Side Yard Planting. A small tree at the right, with spreading evergreens is balanced by a wider planting of a rounded evergreen and low deciduous shrubs. Note that turf runs to the building wall for 1/3 of the space.

The use of both deciduous and evergreen material is usually desirable - a good proportion is about 1/3 evergreen to 2/3 deciduous. An entire planting of evergreens looks heavy in summer, while one of all deciduous materials looks thin and lacks interest in winter.

How different plant species are grouped within the bed is also very important. A tall shrub or tree may be made to look lower or "tied" to the ground by underplanting with lower, spreading shrubs. When grouping different height shrubs in a bed, remember to place the taller growing species at the back. Within a bed of more than one species, it is often good to place each species in informal subgroups, using odd numbers of plants (three, five, seven, etc.). The repeating of small groups of a species within a bed, or several beds close together creates "rhythm." This repetition "connects" parts of a bed (or closely located beds) together. This also gives "unity" to the design. These guides also hold true for grouping plants by form, color, or texture. It is better to repeat a few species or types in one area of the landscape than to use each species only once.



Figure 15. Changes in elevation should be made to appear gradual.

### Using Texture, Color, and Contrasts

In the completed landscape, texture or color changes may be gradual or sharp. Sharp changes in the texture or color of elements gives bold contrasts. Gradual changes result in the smooth blending of elements. For the even blending of plant material, each plant group in a series should have a texture one-half as coarse or fine (as rough or as smooth - as heavy or as light) as the following groups of plants. The same is true for changes in color. Fine textures and subdued colors are better suited for small areas. Coarse textured materials with bright colors tend to "overpower" small areas. Plant materials with these characteristics are more attractive when viewed from a distance. Often strong contrasts in plant form or leaf size is used to attract attention. For example, Taxus pruned in a spherical shape might be used at each side of the front door to attract attention to the entrance. Strong contrasts should only be used for a specific purpose; otherwise, harmony, rhythm, and unity are lost and the design becomes an unpleasant distraction.

Landscape materials along walks and entrances should have characteristics which can be seen by people viewing them close at hand. People often walk slowly or pause in these areas. The nearness of the landscape materials allows a person to examine the fine texture of branches and leaves, pastel colors, and the smell of delicate flowers. These are landscape qualities that are not easy to enjoy at a distance.



Figure 16. Walks should be wide, comfortable, and attractive.

Entrances should always be attractive and inviting. An entrance may be made more useful with the provision of a 6 to 8 foot landing area where people may pause as they enter or depart. An unusual (but serviceable) paving treatment would be good. Plants such as an espaliered shrub or tree, or a colorful specimen plant attractively grouped about an entrance can also accent the entrance. Attractive plant beds can be developed under picture windows and along the inside of walks running from the door to the driveway, but these should be secondary to the emphasis on the doorway itself. An often used technique is to plant such areas with low spreading shrubs and connect or "tie" these shrubs together with groundcover plantings. A small flowering tree underplanted with spreading shrubs or groundcovers might also be appropriate.



Figure 17. Plant materials along a walk may be "tied together" (or unified) with a groundcover planting.

#### Selecting Colors to Complement Structures

Homes are built from different materials. Notice that some building materials such as stone, dark brick, and dark painted or stained wood attract attention by looking "heavier" than nearby lighter colored areas. Such heavy areas may be contrasted or balanced by planting "heavy" appearing plants in front of "light" looking portions of the home. Colorful or bright plantings, such as orange-berried pyracantha, can also be used to contrast these "heavy" portions of the house. On an occasion when the designer desires to balance plantings about the dominant area, he may do this by using identical plant species and shapes on both sides of the most dominant part of the area being accented. Another way is to place small heavy appearing plant masses in one part of the dominant area and balance these with larger, lighter looking plant masses placed in other parts of the area.

Plantings against the front of the house should present a pleasant view both from the street and to a person walking from the drive to the entrance. Groupings should be natural and informal looking. They need not be continuous unless a high foundation must be hidden. Grass or groundcover plantings are useful for connecting these plant groups together into one pleasant composition.



Figure 18. A low hedge provides enclosure and unifies the planting.

To enclose entrance areas and to help "connect" the horizontal lines of some homes with the ground, one may use low hedges or fences. This treatment gives the landscape a three-dimensional effect which is pleasing when viewed from any position within or outside it. These plantings capture and hold the eye of a visitor walking toward the door. Fine textured foliage plants and small flowering plants are more readily enjoyed in this area than when planted at a distance.






Figure 19. Large ground cover areas reduce lawn maintenance.



Figure 20. Property lines established with shrubs should be thin.



Figure 21. An attractive entrance planting.

It is not always necessary to place tall plantings at the corners of the house. Plantings here or in any location should be planned only if they serve a purpose in the landscape. Homes can be made to appear larger and lower by having plantings which sweep past the house and by using small, spreading shrubs for underplantings.

#### Using Flower Beds

Flower beds and roses have only very limited use in public area plantings. They are most often used in small gardens behind the hedges or fences. These plantings would be screened from the street, but they can be enjoyed by people looking from the entrance area. Spring bulbs

are exceptions. Flowering bulbs are used in most public area plantings. Bulbs add color and beauty at a time when the owner will be anxious to see some signs of spring. Place bulbs in small, natural looking groups in groundcovers, among shrubs, and in planting beds.

### Screening

Screening in the public area may be necessary to overcome unpleasant views of neighboring properties. Attractive neighboring views should, however, be accented if possible. Open lawns between adjacent houses gives the feeling of greater space because the boundaries are not indicated. If plantings on property lines are in the public area, plantings or fences with a light appearance should be used. Heavy plantings and fences restrict the feeling of flow between adjoining properties.




Figure 22. Screening. Use shrubs or small trees that are taller or shorter than the fence, but not the same height as the fence. Unplanted sections should be wider than the height of the fence. If the view is desirable, but enclosure is needed, substitute a lower, open-work fence, or a low planting of shrubs for the screening fence in the illustration.

On corner lots, it is best to leave the area at the intersection of the two streets undefined by fencing or plantings if possible. Sometimes corner plantings are needed to prevent pedestrian traffic from forming a path in the lawn. These "traffic controllers" can be developed with groups of low plantings or fencing. Roses, barberry, firethorn, and other low plants with thorns or sharp pointed leaves are especially effective for this purpose.



Figure 23. An open fence controls foot traffic without obstructing vision.

#### Landscaping the Sidewalk Area

Planting of trees on grass strips between the sidewalk and street is governed by three factors: (1) legal limitations, (2) utilities, and (3) width of the planting strip.

Many towns and cities have regulations regarding the types of trees which may be planted along sidewalks. These rules exist because some species of trees have bad rooting, fruiting, and height characteristics. Tree species noted for clogging sewer and water mains, such as poplars and willows, are often not permitted. Spacing between trees and the minimum distance that trees may be planted from intersections are often regulated by communities. This latter rule assures good vision for drivers. If trees are planted closer than 5 to 7 feet from sidewalks and curbs, their roots may cause the pavement to break.

The presence of utility wires will limit the planting selection to species which will mature without growing into the wires. Only small growing tree species should be planted in narrow planting strips.

For more information on landscaping the public area read Budget Landscaping, Reference No. 6, pp. 15-58.

#### Landscaping the Private Area



Figure 24. Pleasant views from a terrace should be enhanced.

Study the private area carefully. Stand next to the house and look away toward the boundary lines. Are there neighboring areas which should be screened and others which can be accented? Walk to the back of the private area and see if the views from this position can be enhanced. The private area should be developed toward some dominant feature in the landscape. A dominant feature may be a distant view, an interesting rock formation, a specimen plant, or a combination of plantings and a fountain or sculpture. Attempt to develop the private area to make use of the existing desirable plant materials and structures. Use lawn and planting beds to complement the dominant feature. Lot shape and size influence the choice of directions in which the private area may be developed.

Square lots allow for the greatest choice in development. Narrow, rectangular, or pie-shaped lots limit the possible ways in which the private area can be developed, but can provide an interesting challenge.

Private areas should include some open space for games. These open areas are also relaxing when viewed from the house or patio. The combination of lawn areas with the patterns of planting beds and buildings should be attractive and inviting.

Formal or informal patterns may be used in the private area, but informal designs are usually appropriate, especially for houses with modern architectural lines. However, designers often combine aspects of both.

Private areas should be considered as an extension of the living and relaxation areas of the house. Sliding glass doors, glass walls, and picture windows are often used for viewing the private area from inside the home. If flower beds or pools are desired, place them near the house where they can be easily seen and enjoyed.

Privacy is a key consideration in landscaping this area. Without privacy, a family does not feel free to use this area for parties, games, relaxation, and outdoor meals. The creation of a feeling of privacy without an impression of confinement is worth the effort involved. Review family needs before starting to design the private area.

#### Planning the Terrace

Many families desire "patios" (more properly -- paved terraces), in the private area. A paved terrace can be designed as a connecting link between the house and the private area. This can provide a point around which the private area may be developed. Terraces are useful for outdoor lounging, cook-outs, and summer parties. They may be almost any shape. Rectangular, oval, square, or "L" shaped ones are common. The form may be determined by the type of material to be used. Some paving materials are restricted as to the shapes and patterns for which they may be used. The selection of terrace materials, patterns, colors, and shapes allows a designer to express his ideas.

"Patios" often include raised planting beds, low walls and hedges, plant islands, crocks and pottery, pools, and fountains. Some of the formal or informal lines used in the terrace are often repeated in plant beds and lawn borders.



Figure 25. Wooden decks are serviceable. Screening fences can be beautiful.



Figure 26. A paved terrace links the indoor and outdoor living rooms.

### Screening the Private Area

Screening and enclosures for the private area must be designed to control the view into and from the area. Screening materials should be placed to give enough privacy, but to avoid a harsh, cell-like enclosure. The screening materials should also give necessary control over the traffic of people and pets and should help to moderate wind, exposure, and noise. Both the type and the amount of screening will be limited to a large degree by neighboring properties. When it is possible to enjoy viewing a neighboring property without losing personal privacy, this view should be developed rather than screened. Planning such as that just described greatly "enlarges" the private area beyond its physical boundaries.



Figure 27. Screening materials may be evergreen or deciduous.

The type of screening materials selected will be determined by the characteristics of the site and the owner's desires. If the site requires a low screen (six feet or under) and space is not a limiting factor, then a wide variety of plant material may be selected. Deciduous shrubs give a greater range of fruit, flowers, and seasonal changes, but they do not have the year long density of evergreens. Where space is at a premium, solid fences or columnar evergreens are used to provide privacy. All



screening situations will not call for solid plantings. Trees with underplantings often are used instead of hedges. Plant and structural material are sometimes combined to give dense screening. For example, a fence with Austrian pine or hemlock planted behind it may be very attractive.

The backside of structures and plantings should always be attractive to nearby houses. When desirable, plan for gates or other openings for crossing to adjoining properties.



Figure 28. A combination of deciduous and evergreen plants is interesting.



Figure 29. A service area screened by a fence and shrubs.




Figure 30. Appropriate plants combine well with a screening fence.



Figure 31. A dense hemlock hedge reduces noise and dust.

Using plants and structures to reduce wind, noise, and sun is generally most efficient when combined with the screening materials. Tall plantings and solid fences are very useful for windbreaks. Evergreens are more useful for windbreaks than are deciduous materials. Dense plantings, especially evergreens, help to reduce noise. Trees, awnings, and other devices may be used to shade specific areas. Trees should be planted about 20 feet southwest of the area to be shaded in the afternoon.

#### Placing Hedges, Shrubs, and Walls

Low hedges, fences, and walls can be used within the private area to control traffic and to suggest separation. A low wall along the edge of a terrace gives a sense of "division" but not a barrier from the nearby lawn area. Low hedges will direct people to walks and paths. These dividers achieve their purpose without blocking the view.

### Planning the Planting Bed

Planting beds are designed to complement both the private area development and patterns of the lawn and patio. These beds can contain other features of interest to attract one's attention as his eye is led to a dominant feature at a distant end of the private area. In shallow private areas where it is hard to develop one dominant feature these beds will become primary sources of interest. In such cases the designer must take special care to design the beds to be attractive and gain attention. Each bed must be in harmony and unity with the others in the private area.

### Planning the Lawn

Do not destroy the open lawn area with the use of several scattered plants. This same rule applies in the public area. A lawn area does not have to be square or rectangular to double as a play area. An informal design large enough to cover the needed square or rectangular size may be used. Some examples of game space requirements are: croquet, 30' x 60'; badminton, 24' x 54'; and volleyball, 40' x 70'. Some private areas may be too small for a lawn area. Where space is at a premium or in cases where maintenance would be difficult, it is often better to develop a paved (with brick, stone, etc.) courtyard with planting beds for shrubbery, trees, and bedding plants. Where space permits and a lawn is desired, the paved area should be in proportion to surrounding beds and structures. Attention to scale and proportion keeps one element in the landscape from being "overpowered" by another.

Decoration of the public and private areas makes them interesting. Ornamental objects such as sculptures, birdbaths, fountains, pools, or specimen plants are often used for this purpose. When combined with plantings these items may be used as main features or focal points to be complemented by beds and lawn patterns. Use good taste and restraint in selecting ornaments. Avoid items which look entirely out of place. For example, pink plastic tropical birds look out of place in a Pennsylvania landscape. Ornaments which stand out by themselves as dominant features will spoil or detract from the landscape unless the rest of the garden is made subordinate to them.

Private areas are not always level. Areas that slope uphill or away from the home are especially challenging to develop. This situation calls for experience with screening and structural problems usually not needed when designing level private areas. Steeply sloped land lends itself to terracing, rock gardens, and other more creative uses.

In developing the private area, always keep in mind the maintenance requirements of the lawn and plant materials. For more reading about developing the private area, see Budget Landscaping, Reference No. 6, pp. 59-107.

### Landscaping the Service Area

#### Planning the Facilities




Figure 32. Shrubs soften grade changes in the service area.

The service area should be conveniently located. Its size is determined by the service needs of the family. The location of facilities in the service area should be carefully planned. Walks are needed for easy access to and from the service area. They should be paved to avoid tracking dirt and mud into the house. Hard surfacing materials like asphalt can be used for paving. Areas under clotheslines often are paved

to allow easier movement of laundry carts and to eliminate the inconvenience of early morning dew and of soiling dropped clothes. If garbage and trash cans are stored within this area, an attractive rack or holder is needed to prevent the cans from overturning.

#### Screening the Service Area

Service areas should be screened from public and private areas. Screening needs are determined by viewing the service area from different portions of the public and private area. Both structural and plant materials may be used for screening purposes. If the service area is used as a play area for small children, for safety reasons it should be clearly visible from the kitchen or other work area in which the mother spends most of her time.

#### Placing Plant Materials



Figure 33. Specimen trees may be deliberately positioned to block a direct view into living room windows.

### Using Specimen Plants

Some plant materials are particularly interesting because of some outstanding quality. These plants are often used as specimen plants. They may be selected for interesting form, leaf shape or color, outstanding flowers, or brilliant fruit. Specimen plants are usually planted individually. Planting them in open lawn areas provides maximum opportunity for the plant to be viewed. Specimen plants are usually restricted to trees and medium or large shrubs. Many homeowners make the mistake of breaking up lawn areas with too many "specimen" plants. One or two in the public or private area are usually enough. The placement of specimen plants should not clutter the lawn.

### Grouping Plant Materials

Except for specimen plants, shrubs and trees look best when planted in groups or beds. This avoids dividing the lawn into several small sections. Scattered placement of plant materials destroys unity and harmony by dividing the landscaped area into many disconnected pieces. Groupings of plant material should be at the edges of the lawn area, and should conform to the shape of the lawn area. Plants used in beds should be in proper scale to each other and to nearby structures. Avoid sudden contrasts in scale. For example, small shrubs would not be planted in beds around a large, massive tree or a large house.



Figure 34. This wooded lot was carefully thinned to let in more light so the underplanting material will grow well.

### Thinning and Underplanting

Sometimes the plant materials on the site need thinning, especially in heavily wooded lots. Removal of some trees may be done to increase the amount of light reaching the ground or to create a pattern from a mass of existing vegetation. When thinning trees on a lot, be careful to keep the best species and specimens. Occasionally, underplantings on a wooded lot may be desired. Shade tolerant species such as hemlock, dogwood, rhododendron, and mountain laurel can be used in groups along the border of the wooded area. Placing these species along the border of the wooded area allows enough light to reach the plants to encourage flower bed development.

### Planning

While you were reading this problem area, we hope you yielded to the temptation to do more "doodling" with the Area Layout Plan you have made. You should, by this time, have a good idea of what should go into your landscape plan.

In the next problem area we will take up the mechanical aspects of landscape structures and give you some further ideas on selecting appropriate plants for the plan on which you are working.



PROBLEM AREA 5  
STRUCTURES AND PLANTS  
Student Learning Objectives

Problem Area 5 is concerned with learning about structures and plant materials used in landscapes. The primary objective of this problem area may be to develop the ability to design a plan for landscaping a site. The primary objective may be divided into the following secondary objectives:

1. To develop a working knowledge of landscape structures and their planning.
2. To develop the ability to prepare structural plans.
3. To develop the ability to develop planting plans.
4. To develop a working knowledge about the kinds of plants and their correct uses for a site.

Key Questions

1. How are landscape structures used in a landscaping problem?
2. What are the structural materials and how can they be used?
3. What selection factors are important when selecting plant material for the site?
4. How are the various kinds of plants used to get the desired effects from a landscape?
5. How are the structural plan, the planting plan, and the finished landscape plan developed by the landscape designer?

New Words

Characterized - referring to a trait, quality, or property of a  
plant

Conical - cone-shaped

Cultivar - variety

Durability - the property of being strong

Hardiness - ability of a plant to grow in a particular climate

Individuality - the quality which makes one plant different from  
another

Opaque - something which will not permit light to pass through it

Perennial - continuing to live from year to year

62/63

Preservative - a material that helps prevent decay or loss

Species - a distinct kind of plant with a particular genetic composition

Susceptible - weak, capable of being infected by diseases or insects

Trellis - a structure or frame to support creeping plants and vines

### Planning Landscape Structures

Some kinds of structures are used in every landscape. These include:

(1) walks and drives (transport structures), (2) walls (retention structures), (3) fences (division and screening structures), and (4) terraces or lawns (recreational structures). All of these have size, form, texture, and color. The appropriate materials should be selected, and the design should be such that these structures contribute unity and harmony to the landscape. You may wish to read further about these ideas in Landscape Architecture: The Shaping of Man's Environment, pp. 173-194, Reference No. 27.

#### Transport Structures

Transport structures include drives, walks, and steps. They facilitate movement to and from the house. Transport structures are used where turf and hard packed soil are not adequate for pedestrians and vehicles. The shape, size, and location of these structures will vary to meet the needs of different properties.

Walks - Major walks should be wide enough to allow two people to walk abreast. They should be about 4 to 6 feet wide. Secondary walks may be narrower. Two and one-half to three feet is usually adequate. Walks should be placed so that they are convenient and attractive.

Avoid putting walks where they will divide lawns into small sections. Major walks should be hard surfaced. Hard surfaced walks are safer, easier to walk on, easier to remove snow from, and longer lasting than walks of gravel, tanbark, or similar materials. Gravel, tanbark, hard surfacing, and stepping stones may, however, be used for secondary walks. Stepping stones include flagstone, concrete squares and rectangles, patio blocks, and other hard surfaced materials. Flagstone may be very slippery in shaded areas because of algae growth. Stepping stones should be placed with centers 26-28 inches apart. You should select materials which blend with the area in which the walk will be placed. Use medium color tones to avoid glare from light colors and heat from dark colors.



Figure 35. Walks should be smooth and at least four feet wide.

Driveways - Driveways must be carefully planned to accommodate family vehicles and vehicles which service the home. The number of family vehicles, the space needed for off-street parking and turn-arounds, and the garage location influence driveway design and positioning. A minimum width of 10 to 12 feet is necessary for driveways used for only one auto. To allow room for passing a parked vehicle, the minimum width of the driveway should be 18 feet. Rather than designing the whole driveway to allow for passing a parked automobile the designer may develop a parking area adjacent to one section of the driveway. The parking area also can be used for turn-around space. See Budget Landscaping, p. 52, Reference No. 6, for details. Turning a car around on the lot eliminates the dangerous practice of backing into busy streets. Paved parking bays are usually more practical than circular driveways. Circular drives do have the advantage of reducing the need for large wide masses of paving in one area. However, in planning them, one should keep in mind that the outside wheels of a car in a tight turn trace a circle about 60 feet in diameter.



Figure 36. An asphalt driveway also serves as the walk to the house.

Driveways can be surfaced with either loose aggregate or with hard surfacing like asphalt and concrete. Surfacing with loose aggregate costs less initially, but lacks durability. It is not suited for mechanical snow removal and it scatters on the lawn. It also may be uncomfortable for walking. Materials such as asphalt and concrete are more expensive but have greater durability, lower maintenance, and an even surface. Concrete can present a somewhat cold, harsh, and glaring appearance unless it is finished with a roughened surface.

Curbs along a driveway help to control drainage. This may be especially important in winter when salt is used on the driveway. Concrete, stone, or steel curbine are more durable than asphalt or brick. The driveway should not be lined with pointed stones, bricks, or other hazardous ornaments.

Steps - Steps may be used where the elevation on the site changes abruptly. Steps may be used without walks if traffic is light enough so paths will not be worn in the lawn. When the walks are combined with steps, the steps should be at least as wide as the walk. Steps with landings and changes in direction are more attractive and easier to use than long flights of steps. Ramps or a few steps placed several feet apart can

be used on very gradual slopes. Design and place steps so that they are convenient and safe for the users and in harmony with their surroundings. Well designed steps should be inviting to the person viewing them. This is especially true for the private area and for natural settings.




Figure 37. Steps should be set into a bank.




Figure 38. Safe step designs.

To design steps properly, determine the rise needed and the horizontal distance to be traveled. The number of steps needed can then be readily determined by dividing the height of the bank by the height or rise desired for each step. The tread width can be determined by dividing the number of steps into the horizontal distance to be traveled. The height of the step over the width of the step is called the riser-tread ratio. Not all riser-tread ratios fit a natural pace, and some may cause people to fall. A maximum rise for outdoor use is 6 inches and a minimum tread width is 12 inches. Where children use steps more than adults, the riser should not exceed 5 1/2 inches. A good rule of thumb for determining the tread width is that the sum of the height of two risers and the width of one tread should equal 27 inches. Filling or cutting into the bank allows for some flexibility in establishing the riser-tread ratios.




Figure 39. Steps alternated with landings for easy climbing.

Common materials for step construction include stone, flagstone, concrete, brick, and wood. Frequently, two materials such as wooden risers and brick treads are combined to give a pleasing effect. Large flat stones can be set without mortar when only a few steps are planned. Steps made from brick or small stones must be laid with mortar. Steps should be built into a slope. Avoid setting steps higher than ground level.




Figure 40. Railroad ties and diagonally laid bricks make attractive ramped steps.

#### Retention Structures



Figure 41. A dry wall is attractive, inexpensive, and easily constructed.

Retention structures are used to hold back soil where slopes are too steep for plantings to be used for erosion control, or where plantings may be undesirable for some reason. Walls may be constructed without mortar (dry walls) or they may be built with mortar or concrete (masonry walls). Dry walls may be constructed from fieldstone, rectangular or flat quarried stone, or railroad ties. Stones used in the walls should be large and heavy

enough to anchor the wall to withstand pressure. The heavier stones are used at the base. Dry walls more than five feet high cannot withstand the pressures that develop behind them and will eventually collapse. The construction of a dry wall is shown in Figure 42.




Figure 42. The base of a dry wall should be half as wide as the height of the wall; stones should slant slightly toward the rear; water must be drained from behind the wall.



## Fences and Walls

Wide selections of fence designs and materials are available to satisfy most landscape needs. Obviously, landscape needs will influence the style of fence selected by the designer. "Open" fences may be used to divide properties without creating a "closed-in" feeling. "Solid" fences provide privacy and screening. Durable fence designs and materials which require a minimum of maintenance should be selected. Fences are especially useful when space is limited and privacy or division is desired. Fences provide more immediate screening than plants. Branches of plants growing on painted or stained fences will have to be removed and repositioned every 2 to 4 years to allow repainting. Upright supports are usually spaced at 8 foot intervals. They should extend below the frost line and should be anchored with concrete collars to prevent frost action from pushing them out of line.




Figure 43. An openwork brick wall is durable and attractive.

Walls may also be used for division and screening, but they cost more than most fences and require masonry skills. Well constructed footings are essential. Low walls may be used to divide areas on the site and to regulate pedestrian traffic without impairing views or creating a "closed-in" feeling.

Paved Terraces



Figure 44. Bricks laid on a two-inch, tamped, sand base make an attractive terrace.



Figure 45. Outdoor steps should have broad treads and shallow risers.

The design and size of the terrace (patio) will depend upon the use for which it is intended. A good rule of thumb is that a paved terrace should have the same square footage as the adjoining room. A terrace may

be shaped either formally or informally and is usually hard surfaced. One should select paving materials that do not glare or absorb heat and that have level surfaces that do not become slippery when wet. Commonly used materials are concrete, bricks, stones, and "patio" tiles. Combinations of materials or the use of one material to form different patterns in a paved terrace is especially pleasing.

### Pools and Fountains

Small pools and fountains add charm and beauty to private areas. The sound of moving water is soothing and relaxing. Pools may be plastic, steel, or free-form masonry. Plastic and steel pools are sold commercially and free-form masonry pools can be constructed with basic masonry skills. Pools should be 18 to 24 inches deep to allow sufficient depth for water lilies and to overcome shallow-water algae accumulation. Masonry pools must receive special care to avoid cracking due to ice pressure during the winter months. Submersible electric pumps for fountains and artificial waterfalls recirculate the water in the pool and allow the water to remain at a constant temperature for fish and plants.




Figure 46. A free-form concrete garden pool beautifies a landscape.

Swimming pools have special detailed structural requirements that should be planned by a pool construction firm. Generally a swimming pool on residential property should not be less than 25 feet in length, nor less than 15 feet in width. A diving board requires a water depth of 9 feet. A paved area at least 12 feet wide should surround the pool to prevent grass clippings and leaves from fouling the water. Safety dictates that the deep end be toward the direction from which youngsters are most likely to approach the pool. Local ordinances require a fence and sometimes a pool cover. Chlorination, heating, filtering, and other maintenance costs may be about \$50.00 per month. Swimming Pools by Sunset gives additional information of this subject.

### Miscellaneous Structures

Overhead trellises, large plant containers, garden seats, planting beds in paved areas, and private area embellishments such as sculptures, lights, and birdbaths are examples of miscellaneous structures. These items are usually found in the private area. Selection must be guided by needs and good taste. These items can add usefulness, individuality, and distinction to landscapes. Recreational structures such as a basketball court, horseshoe pits, and volleyball or badminton standards may also be included in appropriate parts of the private or service area. Service area structures such as clothes line supports, compost bins, tool sheds, and dog houses are additional miscellaneous structures.

The Sunset Book Series - Children's Rooms and Play Yards, Decks for Outdoor Living, Garden Pools, Fountains, and Waterfalls, Garden Work Centers, How to Build Fences and Gates, How to Build Patio Roofs, The Patio Book, Walks, Walls, and Patio Floors, Gardening in Containers, and Garden Art and Decoration - give many useful ideas and directions on construction. (See Reference No. 48)

### Structural Materials

#### Asphalt

Asphalt is used for hard surfacing walks, drives, terraces, small storage platforms, and other areas. It is long lasting, durable, inexpensive, easy to work with, and can be painted. Depressions and cracks may develop unless the asphalt is placed on a good base. Asphalt

will soften in hot weather and may be marked by bicycle stands, lawn furniture, etc. Wood or other edging materials may be needed to prevent the edges of the asphalt from crumbling. Asphalt can be damaged by leaking oil and gasoline. Large asphalt areas may appear drab.

### Concrete

Concrete may be used in the same manner as asphalt. In addition, stairs and walls can be constructed from concrete. Concrete is more durable and more expensive than asphalt. It is easy to apply and may be handled in small amounts. It must be laid on a good foundation. Cracks are difficult to repair. Concrete surfaces may appear to be somewhat "cold" or "harsh" but this can be remedied by a wide variety of attractive finishes and color options. It combines well with brick and wood.

### Brick




Figure 47. Bricks may be laid in many patterns.

Brick is used for walks, stairs, and patio construction. It is "warm" looking, easy to work with, long lasting, may be laid in several patterns, and combines well with other materials. Bricks can be laid on a two-inch cushion of sand supported by a firm base. Joints between bricks on a terrace may be filled with sand or mortar. Brick is subject to cracking and heaving in cold weather. Heaving will not be a problem if the base is well drained. While small, weeds between the joints in brick may be easily removed by hand. The dimensions of common brick are 8 inches by 3 7/8 inches by 2 1/2 inches. Face brick is 8 1/4 inches by 4 inches by 2 1/4 inches. Rough surfaced bricks should be used to avoid a slippery surface.

### Flagstones




Figure 48. Flagstones may be laid on a cushion of sand.

Flagstones are used for walks, patios, stairs, and stepping stones. They may be laid on a cushion of sand which is supported by base material. Joints between the flagstones may be filled with a mortar mix or a soil mixture. Flagstone is durable, but it is also expensive. It is available in different colors and in both geometric and irregular shapes. Cut flagstones may be very slippery when wet.

### Loose Aggregates

Loose aggregates such as crushed stone, limestone chips, or pea gravel are inexpensive and easily applied as surfacing for drives,

walks, and patios. Additional applications of loose aggregates must be made occasionally. Walking is difficult on loose aggregates, and when power equipment is operated, they tend to scatter over lawns and create a hazard. Curbing will help prevent scattering. Loose aggregates are varied in color and texture.



Figure 49. Loose stones fill a space kept dry by the roof overhang.




Figure 50. Crushed rock is an inexpensive paving material for low-traffic paved areas.

### Wood

Wood is used for stairs, deck patios, dividers, and fencing. Most wood must be treated with a preservative; cypress, redwood, and cedar are exceptions. Wood blocks and wood dividers can be used for patios. Railroad ties can be used for soil retention. Many types of wooden fences are available. Wood may be painted or used naturally depending on color and durability of the wood. Wood is reasonable in cost compared to other construction materials.

### Tanbark

Tanbark is a loose, soft, oak-chip by-product of leather tanning. It is useful for natural looking walks. Tanbark is not durable and it requires frequent additions in heavily traveled areas. Wood chips, licorice roots, and other organic materials may be substituted for tanbark.

### Large Stones




Figure 51. Large stones skillfully used give character to the landscape.

Large stones are useful for wall and step construction, especially in naturalized settings. Stones may be laid dry or with mortar. They are available as fieldstone or quarried. Masonry structures are relatively expensive.

### Metal Fencing

Metal fencing is available in a wide range of types and prices. It is useful for regulating traffic and for controlling animals, but has only limited screening value.

### Coping

Coping is steel used as edging along walks, drives, or wherever a strong, long lasting, permanent edging is desired. It is, however, much more costly than wood that has been treated to resist decay.

### Garden Lighting

Lighting of driveways, walks, and steps is essential for safety. Lighting of terraces and play areas makes them usable after dark. Special decorative lighting effects can enhance the beauty of the landscape. For detailed information on this subject see Outdoor Lighting for Your Home, Reference No. 39.





### The Structural Plan

At this point you have done enough exploring of landscape ideas. You have become sufficiently familiar with landscaping structures to make a Structural Plan. Use the drawing equipment assembled earlier and make a Structural Plan. Base it on your earlier plans. Also make several alternate Structural Plans. From these pick out the one that seems best and use it later to develop the Planting Plan. The Finished Landscape Design will then be made from the Planting Plan.

Examples of Structural Plans are shown on the next several pages.

Structural Plan





Plant Hardiness Zone V

88'

Scale: 1/16" = 1'

## The Kinds of Plants

Selecting the most suitable plant materials for a particular location requires great knowledge about plant species and their characteristics. Plant materials should be selected which are well suited to the needs of the site. Tables giving the names and characteristics of recommended plant materials are listed in Appendix A. See the following references: The Art of Home Landscaping, Reference No. 49, pp. 221-246; The Shrub Identification Book, Reference No. 52; The Tree Identification Book, Reference No. 53; Trees for American Gardens, Reference No. 54; Ground Cover Plants, Reference No. 19; Pronouncing Dictionary of Plant Names, Reference No. 43; Shrubs and Vines for American Gardens, Reference No. 46.

When indicating plants in the landscape plan, determine the shape, mass, and size of the plant or plant groupings needed for each area of the site. Decide whether an evergreen or a deciduous plant is appropriate. After the above decisions have been made, one may select the particular species and cultivar to be used. Answering the following questions will help in making the decision: Is the species hardy and adapted to environmental conditions? What are the maintenance requirements of the plant? Does the plant have the flowering, fruiting, foliage, and branching characteristics desired? Is the plant obtainable? Is it too costly to be used in large numbers?

It is important that you know both the technical and common names of plants used for landscape purposes, because wholesale price lists, and nearly all books on landscape plants have plants listed alphabetically according to the technical names. Sugar Maple, for example, is listed as Acer saccharinum. Designers specify plants in a design by technical names to avoid the confusion that could come from the use of common names. For example, Amalanchier canadensis is known as Serviceberry in one part of northeastern United States, as Shadblow in another, and as Juneberry in a third area.

### Habit of Growth

Habit of growth refers to the size, form, and other growth characteristics of a plant. The habit of growth of a plant is an important guide for plant selection. Generally plants have vertical, horizontal, or

rounded growth habits. Horizontal lines may be contrasted by plants with vertical or rounded habits of growth and complemented by plants with horizontal habits of growth. Plants for example may be sheared to establish horizontal lines.

Plant forms are creeping, spreading, pyramidal, columnar, upright, vase-shaped, rounded, and weeping. Low growing plants are frequently placed under windows, along walks, or where a need exists for plant material that will not block vision. They may also be used for ground-covers. Plants with vertical habits of growth may be used for screening, framing, shading, windbreaks, and steep planting.

Some plants have intermediate habits of growth. They are useful for plantings close to the house, for shrub borders, for plant screens and hedges, and for specimen plantings. The habit of growth of a plant may be such that it can be used for several purposes. Some evergreen species are used for windbreaks and for low growing hedges.




Figure 52. Tree and shrub forms.

When selecting a plant, always consider its mature height and shape. It is best to select plants that will mature at the height and shape desired. A landscaper should be able to see how selected plants will look in five, ten, or fifteen years. Plantings under windows or along the edges of drives and walks should have a mature height and width which will not

obstruct vision or passage. Plants selected for framing and screening should have a mature height which is suitable for their planned use.

### Hardiness

Make your selection of plants only from those which are hardy in your area. A map of the Hardiness Zones in the Northeast is given in Appendix A. Since the rainfall and relative humidity are similar throughout the Northeast, the hardiness of a particular species is determined primarily by its reaction to temperature. The degree of resistance to low winter temperature sets the northern limit for a species, while resistance to high summer temperature sets the southern limits.

The table of plant materials in the appendix includes the range of hardiness zones within which each plant will grow well. Several books and nursery catalogs give the hardiness zones for landscape plants. Sometimes a particularly desirable plant, such as a Kaempferi Azalea, may be grown successfully just outside the limits of its zone by planting it on the north side of a building to protect it from winter sunlight and in a position to protect it from strong winter winds. Such protection provides a micro-climate that is favorable for the particular plant. Certain plants require light shade no matter where they are planted. Others are particularly susceptible to drought-injury and must be watered in dry seasons. Resistance to drought and cold injury often increases as the plants become older. Boxwood is a good example of a plant in which this is true.

### Maintenance

Maintenance requirements for a landscape design should be considered at the time of planning. Landscape maintenance includes watering, pruning, fertilizing, staking, spraying, clipping, weeding, and other duties. Maintenance requirements can be reduced by selecting plant materials which require little pruning and which are not highly susceptible to insects, disease, drought, and winter injury. Shrub plantings can be underplanted with groundcovers to simplify mowing. Semi-automatic watering devices can be installed. Low maintenance demands less of the owner's leisure time. You can review the problems of establishing and maintaining a

landscape by reading Landscape Maintenance and Establishment, Department of Agricultural Education, The Pennsylvania State University.

#### Fruit, Flower, Foliage, and Branching Characteristics

The fruit, flower, foliage, and branching characteristics of plant materials in the landscape should blend into a harmonious relationship. It is usually better to plan a landscape with a few repeated colors or other characteristics. Plan to have a selection of plants which give the landscape a succession of color throughout the growing season.

Variety in the landscape may be obtained by varying the color, form, size, and texture. The most pleasing affects are obtained by having one form, color, size, or texture dominate. For example, if only one plant in a large planting is purple-leaved, while the others are mid-green, interest is created without destroying the unifying effect of the green color. But a planting of shrubs with equal proportions of red, blue, green, and yellow foliage would be distracting. Similarly, a few pyramidal plants in a planting dominated by rounded forms creates interest without destroying the rounded forms. Perhaps you can think of similar examples of size and texture. The use of color in landscaping is detailed in Garden Color, Reference No. 48.



Figure 53. Specimen plants should be selected for outstanding form and/or color of flowers, fruit, or foliage.

#### Evergreen and Deciduous Plant Materials

Both evergreen and deciduous plants are used in the landscape. Frequently, either an evergreen or a deciduous plant would be suitable for a specific location in the landscape. Combinations of deciduous and evergreen plants increase interest and adds individuality to the landscape.

When combining these plant types, be especially careful to balance the masses and forms, and visualize the appearance in winter as well as summer.

The foliage of evergreen species can be enjoyed year-round. The colors range from green to gray to blue. The leaves of evergreens may be fine textured needles of hemlocks or somewhat coarse leaves of rhododendrons. Evergreens have many shapes. Those with low spreading forms and those with upright conical forms are frequently used. Evergreens are especially useful for windbreaks or screens in situations requiring nearly opaque material the year round.



Figure 54. A combination of evergreen and deciduous material is pleasing.

Deciduous plants are almost limitless in number of different sizes and shapes. They include a great variety of textures, flowering and fruiting habits, foliage and bark colors, and branching habits. They are often used to add color and interest to plantings. By proper selection, it is possible to achieve a succession of flowering from spring through summer and fall.

### Trees

Trees usually have only one major trunk and grow upright, but multiple-trunked ones, such as birch "clumps" are sometimes used. Trees



are used for framing, shading, screening, windbreaks, and ornamental purposes. Trees may be deciduous or evergreen. Deciduous trees are best suited for framing and shading. Evergreen trees are more effective for windbreaks and screens because they keep their foliage throughout the year.

Tall trees are used to provide a canopy or a background for a house. They should be planted no closer than 20 feet from the building. Small trees can be used for framing a one-story house and should be planted forward and to the side of the house. Most tall trees recommended for framing are also valuable sources of shade. Trees should be selected that grow rapidly, have good growth habits, and are resistant to pests and wind damage.

Selecting tree species for screening depends upon the planting space available, screen height needed, and screen density desired. For narrow dense screens, evergreens are recommended. When space is available, deciduous trees or combinations of both evergreen and deciduous materials can be used.

To be most effective, windbreaks should be at least as tall as the object being protected. When possible, plant more than one row of trees for windbreaks and stagger them.

Many species of trees may be used as specimens; however, smaller trees are usually selected for ornamental use on residential lots. Flowering, fruiting, foliage, branching, and bark characteristics are of primary importance in selecting a tree for a specimen planting. For more information on trees read Trees for American Gardens, Reference No. 54 and The Tree Identification Book, Reference No. 53.

### Shrubs

Shrubs are characterized by having many stems. They may be evergreen or deciduous. Shrubs have a wide variety of growth, flowering, and fruiting habits. Common uses of shrubs include hedging, bed plantings, screening, and specimen plantings. Planting distances between grouped shrubs are usually equal to their mature spread. Planting distances between shrubs used for hedges may be closer. Flowering shrubs should be selected to give a succession of flowering through spring, summer, and fall.



Figure 55. Trees and shrubs should be planted in groups.

Hedges represent an important use of shrubs. They are useful for complementing horizontal building lines, for screening purposes, and for regulating traffic in a landscape. Hedges are usually less expensive to install, require lower maintenance, and present a "softer" appearance than fences. Careful selection of species will reduce pruning and other maintenance to a minimum.

Shrubs for screening also are selected according to the planting space available, and the screen height and density needed. In grouping shrubs for screens, beds, and border plantings, low growing shrubs should be placed near the front and taller shrubs placed near the back. Some trees and large shrubs having particularly desirable features may be substituted for smaller plants if pruned heavily, but the constant maintenance required may become a nuisance.

Shrubs which are selected for specimen plants often have desirable flowering, fruiting, or other qualities that increase their attractiveness.

Specimen plantings add more to the landscape when planted alone where they can attain maximum development.

### Groundcovers

Groundcovers have low maintenance requirements and are often used in problem areas which are not favorable for grasses or shrubs. The term "groundcover" includes any low, spreading, or trailing plants that form dense, spreading mats of vegetation. They may be evergreen or deciduous. Groundcovers may be used: (1) to tie groups of shrubs together, (2) to provide cover under trees or other shady areas where grass cannot be established, and (3) to provide cover on banks and rocky areas where grass maintenance is difficult.

For more reading see Ground Cover Plants, Reference No. 19.



Figure 56. Creeping juniper as a groundcover.



Figure 57. Sweet Woodruff groundcover in dense shade.



Figure 58. Hall's Honeysuckle clothes a large bank.

### Espaliers

Espaliers are trees, shrubs, or vines fastened to walls or fences and usually trained in formal patterns. They create interest, color, and patterns in the landscape. The training of espaliers requires considerable time and effort and should be used only if proper care can be given to the plants.

### Vines

Deciduous and evergreen vines are useful for softening harsh lines of walls and buildings. Some clinging vines will naturally cling to rough surfaces while twining types need open supports. If a trellis appears out of place, use wire and hooks for supports. Vines are especially useful where planting space in front of a wall is narrow.

For more information on shrubs and vines read Shrubs and Vines for American Gardens, Reference No. 46, and The Shrub Identification Book, Reference No. 52.

### Herbaceous Plant Material



Figure 59. Bearded iris in left foreground is an easily grown perennial with attractive foliage.

Beds of flowers provide important sources of long lasting color and brilliance for the landscape. Herbaceous plant materials are non-woody plants which have above ground parts that live only one season.

They may be annuals or perennials. There are three general forms of flowers: (1) spike flowers, (2) round flowers, and (3) intermediates. Round and intermediate forms of flowers should be used for the major portion of the bed. Spiked forms may be used for accent purposes. Red, orange, and yellow are warm colors. Greens, blues, and violets are cool colors. Flower beds usually have sequences of warm or cool colored flowers. Taller growing flowers are placed near the back of the flower bed. There are endless possibilities in the use of herbaceous plants. Unless the homeowner gardens as a hobby, they should be used only in small areas and close to where people pass or stop. For more reading see America's Garden Book, Reference No. 3.

### The Planting Plan


The Planting Plan may be developed from a Structural Plan by determining the appropriate kinds of plants (trees, shrubs, vines, ground-covers, and herbaceous plants) needed to fit the landscape. One has further to decide whether particular masses or individual plants should be deciduous or evergreen, what sizes are needed, and what shapes (forms) are required. An example of a Planting Plan is given on pages 94 and 95.

### Selection of Plant Material

After the Planting Plan has been developed, one is ready to complete the Finished Landscape Plan. This is done by putting labels on the plants in the plan to designate the species and varieties to be planted. The owner may desire some special varieties to be planted. These should be included if at all possible. Five environmental factors should be considered in choosing plants:

1. Soil - drainage, type, acid, alkaline
2. Light - sun, filtered sunlight, shade
3. Moisture - wet, medium, dry
4. Exposure - calm air, breezes, strong winds
5. Hardiness zone - Plants for a particular zone, say Zone V, may be selected from any zone groups, I through V; any from Zone VI and higher should not be used in Zone V.


Color succession in the landscape is also an important consideration. The designer deliberately selects certain plants that have colorful flowers in early spring. He chooses others for flowers in mid-spring, late spring, early summer, mid-summer, and so on throughout the seasons. He may also select certain plants for colorful fruit and brilliant fall color. His objective is to have an interesting, continuously changing, color plan for the landscape. Certain plants, such as Forsythia, may be colorful only in early spring. Others, such as the Blackhaw Viburnum, have attractive flowers in mid-spring, colorful fruit in early fall, and brilliant foliage in the autumn. The plant tables in this handbook are a guide to help you in a selection of plants for a succession of color in the landscape. An example of a Finished Landscape Plan is shown on page 95.



PLANT IDENTIFICATION KEY FOR THE FINISHED LANDSCAPE DESIGN

1. Kalmia latifolia, Mountain Laurel
2. Quercus palustris, Pin Oak
3. Hedera helix baltica, Baltic English Ivy
4. Cornus florida, White Flowering Dogwood
5. Forsythia intermedia, "Lynwood Gold" Forsythia
6. Lonicera fragrantissima, Winter Honeysuckle
7. Crataegus oxycantha, "Paul's Scarlet" English Hawthorn
8. Cotoneaster horisontalis "depressa", Rock Cotoneaster
9. Pachysandra terminalis, Japanese Spurge
10. Acer rubrum, Red Maple
11. Abelia grandiflorum, Abelia
12. Rhododendron mollis, Mollis Azalea
13. Malus arnoldiana, Arnold Crabapple
14. Rhododendron schlippenbachii, Pink Shell Azalea
15. Mahonia aquifolium, Oregon Grapeholly
16. Cornus florida, Pink Flowering Dogwood
17. Pinus strobus, White Pine
18. Quercus coccinea, Scarlet Oak
19. Rhododendron hybrid, Rhododendron
20. Taxus cuspidata 'capitata', Upright Japanese Yew
21. Viburnum carlcephalum, Fragrant Viburnum
22. Rhododendron Kaempferi, Kaempferi Azalea
23. Viburnum opulus hanum, Dwarf Cranberrybush Viburnum





Finished Landscape Design  
(See Plant Identification Key, p. 94)

## PROBLEM AREA 6

### ESTIMATING LANDSCAPE COSTS

#### Student Learning Objectives

1. Develop the ability to estimate the costs of designing and establishing a landscape accurately.
2. Develop the ability to understand family financial problems and to design a landscape plan within the economic limit of the situation.

#### Key Questions

1. What basis is used to determine the design and installation cost for landscaping a site?
2. How can landowners lower the initial cost of establishing a landscape?
3. Before beginning to design a landscape for a client, what is the first thing the designer should do?

#### New Words

Complexity - the degree of difficulty, the relationship of the whole landscape to all its individual parts

Initial - beginning, first

#### Estimating Landscape Costs

Landscaping costs vary from site to site, primarily because of the complexity of the design, the plant materials selected, and the labor costs. A complete landscaping job may cost from 10 to 20 percent of the value of the house and lot. This estimate includes the cost of landscape design and establishment. Landscaping costs should be considered primarily for the value which it adds to the livability of the site. (See Landscaping for Modern Living, Reference No. 34, pp. 184-185.)

Landscape plans are usually drawn and shown to the customer for approval. Customers may be charged a specified fee or an hourly rate. A beginning landscape designer might charge about \$4.00 per hour for his time, while an experienced one might make about \$6.00 per hour. Designers with several years of experience might make a flat charge of \$75 to \$100 for a residential design for an average-size city lot. An agreement regarding

96/97

financial arrangements should be reached in the initial discussions. Firms which design landscape plans, sell landscaping materials, and establish landscapes often have a specific charge for the plan, which may be discounted if the customer buys the plants from the same firm. It may be further discounted if the firm does all the construction work and the planting. Many landscape-nurserymen simply charge the retail price for trees and shrubs installed in the landscape. They estimate that the labor and other costs are covered by the difference between the wholesale price they pay for the plants and the retail price the customer is charged. This is probably a sound practice only if several hundred dollars are involved. For complete landscape construction, charges are usually based on materials, plus labor, equipment depreciation, and overhead.

The cost of construction materials and plant materials can be found in trade catalogs. Some guides to estimating construction costs are given in Ideas for Landscaping Your Home, Reference No. 48, pp. 60-63.

Most state departments of agriculture issue annual lists of licensed nurserymen. Some states also publish bulletins similar to the 1968 Directory of Pennsylvania-Grown Nursery Stock. The Plant Buyer's Guide, published by the Massachusetts Horticultural Society, lists world-wide plant sources. Labor costs vary from one locality to another. Landscape designers and landscape-nurserymen should receive salaries appropriate for their training, skill, and reputation.

Sometimes it may not be economically possible to complete the entire landscape plan in one year. Often a three to five year program can be undertaken to offset the initial cost. The first unit should include all paved areas, steps, pools, walls, fences, trees (because they take the longest to reach maturity), and turf. The second phase could include shrubs. The third phase should include groundcovers, bulbs, and flowers. Possibly garden ornaments, such as statuary and tubbed plants, could be added last.

An example of a cost estimate for the design, specifications, and installation of a landscape plan is given on page 98.

BEETLEBUNG LANDSCAPE SERVICE

Centre, Pennsylvania

Estimated cost for design, specifications, and installation of landscape for Mr. O. B. Joyful, 101 Celestial Terrace, Centre, Pennsylvania.

Landscape Design

Site analysis and sketches, 4 hrs. @ 4.00	\$16.00	
Family needs analysis and sketches, 4 hrs. @ 4.00	16.00	
Soil test	5.00	
Preliminary plan drawing, 6 hrs. @ 4.00	24.00	
Consultation, 2 hrs. @ 4.00	8.00	
Final plan, drawing and specifications, 4 hrs. @ 4.00	16.00	
Consultation on site, 2 hrs. @ 4.00	<u>8.00</u>	
TOTAL		\$ 93.00

Installation

Grading, 4 hrs. @ 8.00	\$ 32.00	
Terrace, 12' x 25', red patio tile on 2" sand base @ 2.00 per sq.ft.	600.00	
Redwood fence, basketweave, 6' high, 70' long, posts set 36" deep in concrete, @ 3.00/linear ft.	210.00	
Turf, seeded 50% Kentucky Bluegrass, 50% Pennlawn Fescue, <u>best</u> quality seed, leveling, fertilizer, seeding, light straw mulch	300.00	
Trees and shrubs*, planted		
2 <u>Quercus palustris</u> , Pin Oaks, 2½" diameter, B & B, @ 100	200.00	
1 <u>Pinus strobus</u> , White Pine, 5-6', B & B @ 18.00	18.00	
3 <u>Cornus florida</u> , Flowering Dogwood, "White Cloud," 5-6', B & B @ 14.00	42.00	
6 <u>Forsythia</u> , "Lynwood Gold," 2-3', @ 1.50	9.00	
6 <u>Lonicera fragrantissima</u> , Winter Honeysuckle, 2-3 @ 1.50	9.00	
25 <u>Viburnum opulus 'nanum'</u> , Dwarf Cranberrybush 8-10" spread @ 1.35	33.75	
2 <u>Taxus cuspidata 'densiformis'</u> , Dense Taxus, 18-24", B & B @ 8.00	16.00	
5 <u>Juniperus virginiana</u> , Red Cedar, "Canart," 4-5', B & B @ 12.00	60.00	
7 <u>Syringa persica</u> , Persian Lilac, 18-24", @ 1.50	10.50	
3 <u>Pieris japonica</u> , Japanese Pieris, 18-24", B & B @ 8.00	24.00	
12 <u>Azalea</u> , "Kaempferi," 15-18", B & B @ 6.75	81.00	
3 <u>Hibiscus syriacus</u> , Rose of Sharon, "Coelstis," 2-3, @ 2.00	6.00	
200 <u>Vinca minor</u> , Periwinkle "Bowles," 2½" pots, @ 35¢	70.00	
200 <u>Hedera helix</u> , English Ivy, "Baltic," 2½" pots, @ 35¢	70.00	
Peat, 6 bales, @ 5.00	<u>30.00</u>	
TOTAL		<u>\$1,821.25</u>

Landscape Design and Installation Total \$1,914.25

\*All plant material must meet the Standard Grades of the American Association of Nurserymen.

An example of a thre-year budget for the cost estimate given on page 99 is shown below:

First Year

Landscape Plan	\$ 93.00
Grading	32.00
Terrace	600.00
Turf	300.00
3 Trees	218.00
1 Bale Peat	5.00

---

TOTAL \$1248.00

Second Year

Redwood Fence	\$210.00
Remaining Shrubs	291.25
3 Bales Peat	15.00

---

TOTAL \$516.25

Third Year

Groundcovers	\$140.00
2 Bales Peat	10.00

---

TOTAL \$150.00

List of References

1. A Guide to Home Landscaping. Bushey, D. J. McGraw-Hill, New York. 1956.
2. American Standards for Nursery Stock. American Association of Nurserymen. 835 Southern Bldg., Washington, D. C. 1957.
3. America's Garden Book. Bush-Brown. Scribner's, New York. 1958.
4. Approved Practices in Landscaping the Home Grounds. Hoover, Norman K., Interstate Printers and Publishers, Inc., Danville, Illinois. 1966.
5. Basic Gardening Illustrated. Sunset Book Series. Lane Book Co., Menlo, California. \$1.95.
6. Budget Landscaping. Lees, Carlton B. Holt, Rinehart and Winston, New York. 1960.
7. Careers as Landscape Architect and Landscape Nurseryman. Research Number 13. The Institute for Research, 537 South Dearborn Street, Chicago, Illinois.
8. Course 131. Landscape Planning for Small Properties. Wilson, Wayne. Correspondence Courses in Agriculture and Home Economics, The Pennsylvania State University, University Park, Pennsylvania.
9. Course 135. Trees for the Home Grounds. Haldeman, W. L. Correspondence Courses in Agriculture and Home Economics, The Pennsylvania State University, University Park, Pennsylvania.
10. Course 137. Shrubs for the Home Grounds. Haldeman, W. L. Correspondence Courses in Agriculture and Home Economics, The Pennsylvania State University, University Park, Pennsylvania.
11. Course 140. Vines, Ground Covers, and Espaliers. Haldeman, W. L. Correspondence Courses in Agriculture and Home Economics, The Pennsylvania State University, University Park, Pennsylvania.
12. Dictionary of Occupational Titles. Volumes I, II, III. U. S. Department of Labor. 1965.
13. Directory of Pennsylvania-Grown Nursery Stock - 1968. Pennsylvania Department of Agriculture, Harrisburg, Pennsylvania.
14. Diseases and Pests of Ornamental Plants. Pironne, Dodge and Rickett. (Third Edition). Ronald Press, New York. 1960.
15. Garden Plans. Sunset Book Series. Lane Book Co., Menlo, Calif.
16. Garden Pools, Fountains, and Waterfalls. Sunset Book Series. Menlo Book Co., Menlo, California. 1965. \$1.95.
17. Gardening in Containers. Sunset Book Series. Menlo Book Co., Menlo California. \$1.95.
18. Gardens are for People. Chruch, T. D. Reinhold, New York. 1955.
19. Ground Cover Plants. Wyman, D. Macmillan, New York. 1956.
20. Grounds Maintenance Handbook. Conover, H. S. F. W. Dodge Corp., New York. 1958.

21. Handbook of Agricultural Occupations. Hoover, Norman K. Interstate Printers and Publishers, Inc., Danville, Illinois. 1963.
22. Handbook of Mulches. Brooklyn Botanic Garden, Brooklyn, New York, 11225. \$1.00.
23. Handbook on Garden Construction. Brooklyn Botanic Garden, Brooklyn, New York, 11225. \$1.00.
24. How to Plan Modern Home Grounds. Aul, Henry B. Sheridan House New York.
25. How to Improve Your Home by Landscaping. A Sunset Book. Lane Book Company, Menlo, California. 1960.
26. Ideas for Entryways and Front Gardens. Sunset Book Series. Lane Book Co., Menlo, California. 1961. \$1.50.
27. Landscape Architecture: The Shaping of Man's Environment. Simmonds, J. O. McGraw-Hill, New York. 1961.
28. Landscape for Living. Eckbo, Garrett. F. W. Dodge Corporation. 1950.
29. Landscape Paving for Home Grounds. Breen, Harold. Misc. Series Circular 1-6. Michigan State University, Cooperative Extension Service, East Lansing, Michigan.
30. Landscape Planning. Better Homes and Gardens. Merideth Press, Des Moines, Iowa. 1963.
31. Landscape Planning for Residential Properties. Circular E-2. Misc. Series. Michigan State University, Cooperative Extension Service, East Lansing, Michigan.
32. Landscape Planning for Rural Homes. (2 vol.) Michigan State University, Cooperative Extension Service, East Lansing, Michigan.
33. Landscape Vocabulary. Marsh, Warner L. Miramar Publishing Company, Los Angeles. 1964.
34. Landscaping for Modern Living. Sunset Book Series. Menlo Book Co., Menlo, California. 1963. \$2.00.
35. Landscaping Your Home. Nelson, William R. University of Illinois, College of Agriculture, Cooperative Extension Service. Circ. 858. \$2.00.
36. Landscaping Your Home. Teacher's Guide. Agdex 271, Vocational Agriculture, Instructional Methods Service, Room 201, 2120 Fyffe Road, Columbus, Ohio. 43210.
37. Nursery Production and Landscape Maintenance. Robinson, William A. and others, Department of Agricultural Education, College of Agriculture, The Pennsylvania State University, University Park, Pennsylvania.
38. Operating a Garden Center. Pinney, John J. American Nurseryman, Chicago, Illinois. 1963.
39. Outdoor Lighting for Your Home. Schuler, S. Van Nostrand, New York. 1962.
40. Planning the Garden. University of California, 934 University Hall, Berkeley 4, California. 1953.

41. Plant Hardiness Zone Map. Misc. Publ. 814, U. S. Department of Agriculture, Washington, D. C.
42. Planting Design. Bracken, John R. Published by John R. Bracken, State College, Pennsylvania. 1957.
43. Pronouncing Dictionary of Plant Names. Florists' Publishing Co., Chicago, Illinois. 1966. \$ .35.
44. Pruning Handbook. The Brooklyn Botanic Garden. Brooklyn, New York, 11225. \$1.00.
45. Roses for Every Garden. Allen R. C. Barrows, New York. 1956.
46. Shrubs and Vines for American Gardens. Wyman, Donald. The Macmillan Company. 1959. \$8.00.
47. Some Shade and Flowering Trees for Pennsylvania Landscapes. Sp. Circ. 57. Agricultural Extension Service, The Pennsylvania State University, University Park, Pennsylvania.
48. Sunset Book Series. Lane Book Co., Menlo, California.
  - a. Basic Gardening Illustrated.
  - b. Building Barbecues.
  - c. Children's Rooms and Play Yards.
  - d. Decks for Outdoor Living.\*
  - e. Entryways and Front Gardens.
  - f. Garden Art and Decoration.
  - g. Garden Color.
  - h. Garden Plans.
  - i. Garden Pools, Fountains, and Waterfalls.
  - j. Garden Work Centers.\*
  - k. Gardening in Containers.
  - l. How to Build Fences and Gates.\*
  - m. How to Build Patio Roofs.
  - n. How to Improve Your Home by Landscaping.
  - o. Ideas for Entries and Front Gardens.
  - p. Ideas for Landscaping Your Home.
  - q. Landscaping for Modern Living.
  - r. Lawns and Groundcovers.
  - s. Planning and Landscaping Hillside Homes.
  - t. Rock Gardens.
  - u. Sunset Patio Book.\*
  - v. Sunset Patio and Building Book. (contains the 5 books marked\*)
  - w. Swimming Pools.
  - x. Vegetable Gardening.
  - y. Walks, Walls, and Patio Floors.
49. The Art of Home Landscaping. Eckbo, Garrett. E. W. Dodge Corp., New York. 1956. \$6.95.
50. The Nursery Business. Small Business Bulletin. Small Business Administration, Washington, D. C.
51. The Plant Buyer's Guide. The Massachusetts Horticultural Society, 300 Massachusetts Avenue, Boston, Mass.



52. The Shrub Identification Book. Symonds, George W. D. M. Barrows and Company, New York. 1963.
53. The Tree Identification Book. Symonds, George W. D. M. Barrows and Company, New York. 1958.
54. Trees for American Gardens. Wyman, Donald. Macmillan, New York. 1957.
55. Trees, Shrubs, and Vines. Bulletin No. 43. College of Forestry, Syracuse University, Syracuse 10, N. Y.
56. Urban Landscape Design. Eckbo, Garrett. McGraw-Hill, New York. 1964.

APPENDIX A

Plant Materials List

Use \_\_\_\_\_ Name \_\_\_\_\_

Form: \_\_\_\_\_

Size - mature height: \_\_\_\_\_

Size - mature spread: \_\_\_\_\_

Texture: very fine \_\_\_\_\_ fine \_\_\_\_\_ medium \_\_\_\_\_ coarse \_\_\_\_\_ very coarse \_\_\_\_\_

Density: compact \_\_\_\_\_ medium \_\_\_\_\_ open \_\_\_\_\_

Foliage: appears early \_\_\_\_\_ late \_\_\_\_\_

          drops early \_\_\_\_\_ late \_\_\_\_\_

          color \_\_\_\_\_ fall color \_\_\_\_\_

Flowers: size \_\_\_\_\_ color \_\_\_\_\_ fragrance \_\_\_\_\_

Fruit: showy \_\_\_\_\_ color \_\_\_\_\_ when appearing \_\_\_\_\_ use \_\_\_\_\_

Bark: color \_\_\_\_\_ texture \_\_\_\_\_ other \_\_\_\_\_

Soil preference: sand \_\_\_\_\_ clay \_\_\_\_\_ loam \_\_\_\_\_

Moisture preference: wet \_\_\_\_\_ dry \_\_\_\_\_ intermediate \_\_\_\_\_

Light preference: sun \_\_\_\_\_ shade \_\_\_\_\_ semi-shade \_\_\_\_\_

pH preference: acid \_\_\_\_\_ alkaline \_\_\_\_\_ neutral \_\_\_\_\_ other \_\_\_\_\_

Rate of growth: slow \_\_\_\_\_ moderate \_\_\_\_\_ fast \_\_\_\_\_

Hardiness: tender \_\_\_\_\_ semi-hardy \_\_\_\_\_ hardy \_\_\_\_\_

Maintenance:

    cleanliness \_\_\_\_\_

    pruning \_\_\_\_\_

    fertilization \_\_\_\_\_


    disease \_\_\_\_\_

    insects \_\_\_\_\_


APPENDIX B

Landscape Symbols


DECIDUOUS PLANT MATERIAL



EVERGREEN PLANT MATERIAL



SITE SYMBOLS



APPENDIX C

Identification and Classification of Plant Materials  
Commonly Used for Landscape Plantings

## IDENTIFICATION AND CLASSIFICATION OF PLANT MATERIALS COMMONLY USED FOR LANDSCAPE PLANTINGS

Everyone involved in landscape design, nursery production, or landscape maintenance and establishment should be able to identify plant materials commonly used for landscaping. Certainly the landscape nurseryman must know the plants which he grows or buys to use in landscape plantings. Garden center workers and salesmen must know plant materials in order to sell effectively. Finally, ground superintendents, park foremen, and landscape workers should know plant materials in order to properly establish and maintain landscape plantings.

There are two methods of identifying plant materials. Each has its merit. The first method is to memorize the appearance of each plant. The second method requires the use of a keyed system of classifying and identifying characteristics of plant materials.

Young people entering landscaping need to acquire rapidly a general knowledge of the trees, shrubs, groundcovers, and vines commonly used in landscape plantings. The visual system is best for the beginner. Later he may want to use the keyed system.

Classifying plant materials according to certain characteristics makes learning easier. These materials can be classified as deciduous (those which drop their leaves in the fall) and evergreen (those which do not drop their leaves). Both may be further classified as broad-leaved or narrow-leaved. Next, they can be classified as trees, shrubs, groundcovers, or vines. Trees may be classified as small or large. Shrubs are usually classified further as small, medium, or large. This classification could be extended as the beginner gains experience.


The beginner should learn a few plant materials in each category. For example, he should learn three broad-leaved evergreen trees and three broad-leaved deciduous trees, etc. From this limited beginning, other materials can be learned as more experience is gained.

A complete display of plant materials commonly used for landscaping is not feasible in this handbook. It is suggested that the student use the tables of recommended plant materials in this appendix to learn 2 to 5 plants in each category. Also refer to Nursery Production - A Student Handbook, pp. 1-44, Reference No. 21. If available, study the slide series C - "Commonly Used Trees, Shrubs, Ground Covers, and Vines." For a more complete


reference, see Wyman's books: Ground Cover Plants, Reference No. 15; Shrubs and Vines for American Gardens, Reference No. 27; and Trees for American Gardens, Reference No. 32.

Tables of recommended trees and shrubs follow. These tables may be used as references for selecting trees and shrubs to fit landscape plans you have prepared or they may be used as a study guide.

Sketches depicting some of the more common shapes of trees and shrubs are shown below. A Hardiness Zone Map also precedes the Tables of Plant Materials. When using the tables, one should know that plants indicated for a particular hardiness zone are also hardy in higher numbered zones, but not in lower numbered zones.



Plant Forms.



Plant Hardiness Zone Map for Certain Northeastern States \*

\* Adapted from Plant Hardiness Zone Map, Agricultural Research Service, United States Department of Agriculture, Miscellaneous Publication No. 814.

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Standard Deciduous Trees (40-160')

Hardi- ness Zones	Form	Height	Width	Leaf Size	Fall Color	Name	Comments
3-8	pyramidal when young, round at maturity	60'	50'	med.	brilliant red	Red Maple <u>Acer rubrum</u>	has red flowers which bloom in early April - grows well in low swampy areas
3-8	densely upright growth, pyramidal at maturity	75'	36'	med.	red and yellow	Column Red Maple <u>Acer rubrum 'columnare'</u>	fast growing upright type, good street tree
3-8	rounded	90'	90'	large	yellow	Norway Maple <u>Acer platanoides</u>	dense head, often used as street tree
3-8	rounded	90'	90'	large	red	Norway Maple <u>Acer platanoides 'Crimson King'</u>	deep red leaves all season
3-8	oval when young, rounded head when mature	110'	93'	med.	yellow and orange	Sugar Maple <u>Acer saccharum</u>	beautiful fall color, sap yields maple syrup
3-8	upright, narrow pyra- midal head	100'	45'	med.	red and yellow	Pyramid Sugar Maple <u>Acer saccharum 'pyramidale'</u>	similar form to Columnar Red Maple
4-8	densely pyramidal	108'	106'	med.	golden bronze	European Beech <u>Fagus sylvatica</u>	intolerant of compact soils, has glossy, dark green leaves, gray trunk
4-8	densely pyramidal	108'	106'	med.	bronze	Purple Beech <u>Fagus sylvatica 'purpurea'</u>	intolerant of compact soils - purple leaves
4-8	wide-spreading, open	130'	130'	med.	yellow	Ginkgo <u>Ginkgo biloba</u>	picturesque fan-like leaves
4-8	narrow pyramidal	130'	40'	med.	yellow	Sentry Ginkgo <u>Ginkgo biloba 'fastigiata'</u>	good street tree
4-8	broad and open	92'	112'	large	- - -	Thornless Honeylocust <u>Gleditsia triacanthos 'inermis'</u>	thornless and densely branched, light shade



SELECTED LANDSCAPE PLANTS, ZONES 2-8

Standard Deciduous Trees (40-160')

Hardiness Zones	Form	Height	Width	Leaf Size	Fall Color	Name	Comments
4-8	wide-spreading	135'	135'	large	- - -	"Sunburst" Honeylocust <u>Gleditsia triacanthos</u> <u>'inermis'</u>	young foliage yellow, some- times turns green in summer
4-8	wide-spreading	135'	135'	large	- - -	Moraine Locust <u>Gleditsia triacanthos</u> <u>'inermis moraine'</u>	withstands city conditions well but has dangerous long thorns
4-8	broadly pyramidal	112'	71'	large	scarlet	Sweet Gum <u>Liquidambar styraciflua</u>	star-shaped leaves - used often along park-ways
4-8	broadly pyramidal, massive branches	160'	80'	med.	yellow	Tuliptree <u>Liriodendron tulipifera</u>	has greenish-yellow, tulip- shaped flowers which bloom in mid-June
4-8	pyramidal with pen- dulous branches	85'	50'	med.	scarlet to	Black Tupelo <u>Nyssa sylvatica</u>	has dense, dark green, lus- trous foliage, excellent fall color
4-8	young trees are pyramidal - old trees are round	130'	107'	large	red	Northern Red Oak <u>Quercus borealis</u>	most rapid growing of all oaks, dense lustrous foliage make a good avenue tree
4-8	open and round- topped	80'	80'	large	scarlet	Scarlet Oak <u>Quercus coccinea</u>	good parkway tree, but diffi- cult to transplant
5-8	young trees are pyramidal - old trees are round, open	96'	85'	med.	yellow to russet	Shingle Oak <u>Quercus imbricaria</u>	leaves without lobes, makes good hedges or screens, foliage lustrous dark green
4-8	pyramidal with droop- ing branches, dense branching	135'	135'	med.	scarlet	Pin Oak <u>Quercus palustris</u>	has picturesque growth habit, is easily transplanted, should not be planted near a street
5-8	open, broad head - short trunk	80'	80'	med.	brown	English Oak <u>Quercus robur</u>	these trees grow in the famous Sherwood Forest, slow growing, dark green leaves

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Standard Deciduous Trees (40-160')

Hardi- ness Zones	Form	Height	Width	Leaf Size	Fall Color	Name	Comments
5-8	upright, columnar	80'	30'	med.	brown	Pyramidal English Oak <u>Quercus robur</u> ' <u>fastigiata</u> '	of the type grown in the famous Sherwood Forest
7-8	wide spreading	60'	120'	med.	- - -	Live Oak <u>Quercus virginiana</u>	evergreen in southern range, very popular, long-lived
4-8	rounded form, long, pendulous branches	40'	60'	med.	- - -	Thurlow Weeping Willow <u>Salix elegantissima</u> ' <u>thurlow</u> '	best variety of several available
3-8	densely pyramidal	100'	50'	small	yellow	Little-leaf Linden <u>Tilia cordata</u>	fragrant flowers, grows well in cities, dense foliage gives perfect shade

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Small Deciduous Trees (8-35')

Hardi- ness Zones	Form	Height	Width	Leaf Size	Fall		Flower Color	Name	Comments
					Leaf Color	mid- summer			
6-7	spreading, flat topped	36'	36'	fine	- - -	pink	mid-summer	Silktree <u>Albizia julibrissima</u> 'rosea'	long flowering period, soil borne wilt disease in Zone 8
2-8	upright but rounded, branching dense	15'	15'	med.	scarlet	- - -	- - -	Amur Maple <u>Acer ginnala</u>	has red fruit in mid-summer, extremely hardy, dense growth
5-8	rounded and often mound-like	20'	25'	med.	scarlet	- - -	- - -	Japanese Maple <u>Acer palmatum</u>	some have red foliage, needs good soil, sun
5-8	rounded and often mound-like	20'	25'	med.	scarlet	- - -	- - -	Bloodleaf Japanese Maple <u>Acer palmatum</u> 'atropurpureum'	hardy, dark red leaves throughout the growing season
4-8	upright, spreading	25'	20'	med.	red	white	white	Shadblow or Service-berry <u>Amelanchier canadensis</u>	flowers in early May, edible blue fruit, shade tolerant, gray trunk
2-7	pyramidal, pendulous branches in older trees	35'	15'	med.	yellow	- - -	- - -	Cutleaf Weeping Birch <u>Betula pendula</u> 'laciniata'	short life - 25-30 yrs., susceptible to borers, very graceful tree
5-8	pyramidal when young, round at maturity	30'	25'	med.	yellow	- - -	- - -	European Hornbeam <u>Carpinus betulus</u>	makes good hedge, very graceful
5-8	upright, becoming vase-shaped	30'	15'	med.	yellow	- - -	- - -	Pyramidal European Hornbeam <u>Carpinus betulus</u> 'fastigiata'	- - -
4-8	flat top, irregular	25'	25'	med.	yellow	purplish-pink	purplish-pink	Eastern Redbud <u>Cercis canadensis</u>	tiny pea-like flowers appear in mid-May before leaves



SELECTED LANDSCAPE PLANTS, ZONES 2-8

Small Deciduous Trees (8-35')

Hardi- ness Zones	Form	Height	Width	Leaf Size	Fall Leaf Color	Flower Color	Name	Comments
4-8	horizontal branch- ing	25'	25'	med.	scarlet	white or pinkish	Flowering Dogwood <u>Cornus florida</u>	red berries in fall, large flowers in mid- May, foliage is dense and lustrous
5-8	horizontal branch- ing	20'	20'	med.	scarlet	white or pinkish	Kousa Dogwood <u>Cornus kousa</u>	raspberry-like red berries, large flowers in mid-June, from China
4-8	rounded, dense, shrub-like	20'	20'	med.	red	yellow	Corneliancherry Dogwood <u>Cornus mas</u>	has bluish-black berries, small flowers appear before leaves, flowers in early April
4-7	branches spreading round-headed, dense	20'	20'	small	- - -	bright- scarlet	Paul's Scarlet English Hawthorn <u>Crataegus oxyacantha</u> 'pauli'	scarlet colored fruit in $\phi$ the fall, flowers are double
4-7	broadly columnar, dense branching, eventually has round head	20'	20'	med.	scarlet to orange	white	Washington Hawthorn <u>Crataegus phaenopyrum</u>	interesting year-round, fruit is bright red and effective all winter
2-8	wide spreading, open	25'	30'	med.	- - -	silvery outside, yellow inside	Russian Olive <u>Elaeagnus angustifolia</u>	interesting foliage and fragrant flowers in early June, crooked trunk
6-8	pyramidal habit	30'	15'	large	orange to red	white	Franklinia <u>Franklinia alatamaha</u>	3" blooms in Sept.-Oct., brilliant fall foliage
5-8	flat-topped	25'	35'	med.	- - -	yellow	Goldraintree <u>Koeleruteria paniculata</u>	has yellow fruit in fall, wide range of soils, flowers in early summer

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Small Deciduous Trees (8-35')

Hardi- ness Zones	Form	Height	Width	Leaf Size	Fall		Name	Comments
					Leaf Color	Flower Color		
5-8	stiffly upright	30'	15'	med.	- - -	yellow - pendulous clusters - May	Laburnum <u>Laburnum vossii</u>	unusual
4-8	pyramidal when young, massive when mature	35'	20'	med.	- - -	white	Kobus Magnolia <u>Magnolia kobus</u>	large white blooms in May, slow growing
5-8	shrub-like with many stems	20'	20'	med.	- - -	white to purple	Saucer Magnolia <u>Magnolia soulangeana</u>	large flowers precede leaves, flowers in April, course textured leaves
5-8	branching dense, mounded to shrub-like	20'	20'	med.	bronze to yellow	white	Star Magnolia <u>Magnolia stellata</u>	large flowers in mid- April, has interesting red fruit, dark green foliage
5-8	grows as a tree in south, as a shrub in north	25'	20'	med.	- - -	cream	Sweetbay Magnolia <u>Magnolia virginiana</u>	flowers over long period, tolerant of wet soils, has red seed pods in fall
4-8	rounded	20'	25'	med.	- - -	red buds, white flowers	Arnold Crabapple <u>Malus arnoldiana</u>	heavy flowering in May, yellow and red fruit, 5/8" in diameter
4-8	mounded, almost shrub-like, dense	20'	20'	med.	- - -	rich carmine	Carmine Crabapple <u>Malus atrosanguinea</u>	flowers in mid-May, dark green, dense foliage
4-8	rounded, densely branched	20'	20'	med.	- - -	crimson	Dorthea Crabapple <u>Malus dorothea</u>	semi-double flowers, blooms every year
4-8	rounded and densely branched	20'	20'	med.	- - -	pink but fades to white	Japanese Flowering Crabapple <u>Malus floribunda</u>	blooms in early May, fruits yellow and red from August to October
5-8	upright, almost vase- shaped, dense	15'	15'	med.	- - -	neuron rose	Hall's Parkman Crabapple <u>Malus halliana 'parkmani'</u>	foliage is dark glossy green, blooms in early May, fruit is dull red

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Small Deciduous Trees (8-35')

Hardi- ness Zones	Form	Height	Width	Leaf Size	Fall		Name	Comments
					Leaf Color	Flower Color		
4-8	upright	21'	12'	med.	- - -	white	Hopa Crabapple <u>Malus hopa</u>	flowers in May, red fruit
2-8	round-headed, open	15'	15'	med.	- - -	pink	Bechtel Crabapple <u>Malus ioensis 'plena'</u>	flowers in late May
4-8	rounded	20'	20'	med.	- - -	red	Eley Purple Crabapple <u>Malus purpurea 'eleyi'</u>	dark flowers in May, fruit deep purple
5-8	mounded, dense branching	8'	12'	med.	- - -	pure white	Sargent Crabapple <u>Malus sargentii</u>	flowers in mid-May, fruit is dark red, smallest Crabapple
4-8	upright	20'	15'	med.	- - -	pale pink	Scheidecker Crabapple <u>Malus scheideckeri</u>	resistant to apple scab, dense foliage
3-7	upright, rounded	25'	25'	med.	purple	pink	'Pink Cloud" Pissard Plum <u>Prunus cerasifera 'rosea'</u>	red-purple leaves all season, bright pink flowers in April
5-7	rounded, dense branching	30'	30'	med.	- - -	light pink	Higan Cherry <u>Prunus subhirtella</u>	flowers in late April
5-7	pendulous branches	20'	20'	med.	- - -	pale pink	Weeping Higan Cherry <u>Prunus subhirtella</u> 'pendula'	most popular of the Higan Cherries
5-7	flat-topped	20'	20'	med.	- - -	pink	Kwazan Cherry <u>Prunus serrulata</u>	double-flowered, blooms last a long time
5-7	flat-topped, bushy	35'	35'	med.	- - -	white to pink	Yoshina Cherry <u>Prunus yedoensis</u>	should be planted 30 - 40 ft. apart, flowers in late April
2-8	erect while young, spreading and open at maturity	20'	20'	med.	reddish	white	European Mountain Ash <u>Sorbus aucuparia</u>	susceptible to borers, fruit bright orange or red clusters, flowers in late May

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Evergreen Trees

Hardiness Zones	Form	Height	Width	Leaf Size	Foliage Color	Soil	Exposure	Name	Comments
4-8	pyramidal, narrow horizontal branching	75'	12'	2"	bluish green	tolerant	sun	White Fir <u>Abies concolor</u>	needle-like leaves, withstands heat and drought better than most firs
5-8	narrow to broadly pyramidal	120'	60'	needle-like	dark green	- - -	sun	Cedar of Lebanon <u>Cedrus libani</u>	very popular where hardy
3-8	slender to broadly pyramidal	150'	40'	scale-like	blue-green	wet	sun	Sawara False-cypress <u>Chamaecyparis pisifera</u>	leaves are scale-like, many horticultural forms
5-8	narrowly pyramidal	150'	30'	needle-like	bluish green	tolerant	sun	<u>Cryptomeria japonica</u>	plume-like branchlets, orange bark, easily grown
5-8	pyramidal	45'	17'	2"	dark green	well drained	sun	American Holly <u>Ilex opaca</u>	spiny leaves, brilliant fruit, sexes separate, outstanding ornamental
2-8	pyramidal, dense	20'-90'	12'	scale-like	green	tolerant	sun	Red Cedar <u>Juniperus virginiana</u>	grows slowly, several excellent forms including 'burki,' 'canaenti,' 'glauca,' 'pyramidalis,' and others
7-8	pyramidal, broad-leaves, large white blooms	90'	40'	5"-6"	glossy, dark green	- - -	sun	Southern Magnolia <u>Magnolia grandiflora</u>	outstanding and popular where hardy
2-8	pyramidal, pendulous branchlets	150'	35'	1"	dark green	- - -	sun	Norway Spruce <u>Picea abies</u>	does not mature gracefully becomes th. top

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Evergreen Trees

Hardi-ness Zones	Form	Height	Width	Leaf Size	Foliage Color	Soil	Exposure	Name	Comments
4-8	densely pyramidal, pendulous branching	90'	20'	needle-like	dark green	- - -	sun	Serbian Spruce <u>Picea omorika</u>	needles flat, white undersurface; the best spruce
2-8	nearly columnar, dense	50'	15'	2"	bluish white	- - -	sun	Koster Blue Spruce <u>Ficea pungens</u> <u>'kosteriana'</u>	very popular, very susceptible to spruce gall aphids, old trees lose lower branches
4-8	densely pyramidal, wide spreading	90'	50'	3"-6"	dark green glossy	- - -	sun	Austrian Pine <u>Pinus nigra</u>	fast growing, makes good specimen plant
2-8	stout spreading branches forming pyramidal head	50'	50'	4"-6"	dark green lustrous	tolerant	sun	Red Pine <u>Pinus resinosa</u>	bark is reddish <sup>1</sup> / <sub>2</sub> "
3-8	rounded or pyramidal	100'	60'	2"-5"	soft green	- - -	sun	White Pine <u>Pinus strobus</u>	has delicate, graceful foliage
2-8	pyramidal when young, rounded-topped, irregular when old	75'	30'	2"-3"	bluish green	- - -	sun	Scotch Pine <u>Pinus sylvestris</u>	reddish trunk, picturesque when old
7-8	broadly pyramidal	60'	30'	4"	dark green	- - -	sun	Yew Podocarpus <u>Podocarpus macrophyllus</u>	similar to Taxus, but larger needles; popular hedge plant
4-8	densely pyramidal, branching, horizontal	75'	20'	needle-like	bluish green	- - -	sun	Douglas Fir <u>Pseudotsuga taxifolia</u>	often used as Christmas trees, soft needles
3-8	long, slender, horizontal or drooping	75'	50'	needle-like	dark green	- - -	light shade	Canada Hemlock <u>Tsuga canadensis</u>	dense foliage, very graceful trees, may be sheared for large hedge



SELECTED LANDSCAPE PLANTS, ZONES 2-8

Large Deciduous Shrubs (8-30')

Hardi-ness Zones	Height	Width	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Form and Comments
4-8	24'	18'	med.	red	yellow	red	- - -	sun or filtered sun	Cornelian Cherry <u>Cornus mas</u>	rounded to upright form, small but very early flowers
5-8	15'	10'	large	yellow to orange	purplish	- - -	- - -	sun	Smoke Tree <u>Cotinus coggyria</u>	upright habit
3-8	20'	10'	med.	reddish	- - -	brilliant pink	- - -	sun or filtered sun	Aldenham Spindle Tree <u>Euonymus europaeus</u> 'aldenhamensis'	upright, interesting fruit
5-8	30'	15'	large	yellow	yellow	- - -	- - -	sun	Chinese Witch-hazel <u>Hamamelis mollis</u>	rounded form
5-8	15'	10'	med.	- - -	white, pink, red, and blue	- - -	normal	sun	Shrub Althea <u>Hibiscus syriacus</u>	upright form, August flowering
4-8	12'	8'	med.	- - -	pink	- - -	tolerant	sun	Beauty Bush <u>Kolkwitzia amabilis</u>	upright, arching branches, profuse flowering
7-8	12-24'	6-12'	med.	- - -	white, pink, red, lavender	- - -	tolerant	sun	Common Crapemyrtle <u>Lagerstroemia indica</u>	upright, open form, August flowering, very popular
3-8	15'	12'	med.	- - -	white	black	tolerant	sun	Amur Privet <u>Ligustrum amurense</u>	hardier than California Privet, upright, dense
4-8	15'	12'	med.	- - -	white	black	tolerant	sun	European Privet <u>Ligustrum vulgare</u>	rounded-loose form, fragrant flowers, often used as hedges
2-8	15'	15'	med.	- - -	white - changing yellowish	red	tolerant	sun	Amur Honeysuckle <u>Lonicera maackii</u>	flowers in late May, fruit and leaves may remain until Thanksgiving, rounded form



SELECTED LANDSCAPE PLANTS, ZONES 2-8

Large Deciduous Shrubs (8-30')

Hardi- ness Zones	Height	Width	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Form and Comments
3-8	15'	15'	med.	- - -	pink to white	red	toler- ant	sun	Tatarian Honey- suckle <u>Lonicera tatarica</u>	rounded form, can be planted at the seashore, very popular
5-8	15-30'	10'	large	- - -	white	dark red	- - -	- - -	Sweetbay Magnolia <u>Magnolia virginiana</u>	fragrant flowers in late May, ever- green in southeast, upright habit, tree in south
5-8	15'	10'	med.	- - -	purple	- - -	toler- ant	sun	Chinese Lilac <u>Syringa chinensis</u>	upright form, flowers in mid-May
3-8	12'	8'	med.	red	white	blue	acid	sun	Highbush Blueberry <u>Vaccinium corymbosum</u>	rounded form
3-8	15'	8'	med.	red	white	red to black	wet toler- ant	sun or fil- tered sun	Wayfaring Tree Viburnum <u>Viburnum lantana</u>	flowers in early June; grows rapidly, upright
2-8	20'	20'	large	purplish red	white	black, purplish red	dry toler- ant	sun	Nannyberry Viburnum <u>Viburnum lentago</u>	rounded form, excellent fall color; good screen or border plant
3-8	15'	15'	med.	shining red	white	blue, black	toler- ant	sun	Blackhaw Viburnum <u>Viburnum pruni- folium</u>	rounded form, excellent as a specimen or for massing
5-8	12'	12'	med.	- - -	white	black	toler- ant	sun	Burkwood Viburnum <u>Viburnum burkwoodi</u>	fragrant flowers, somewhat open plant form
4-8	15'	15'	med.	red	silver	red	toler- ant	sun	Sargent Cranberry- bush Viburnum <u>Viburnum sargentii</u>	rounded form

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Large Deciduous Shrubs (8-30')

Hardiness Zones	Height	Width	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Form and Comments
5-8	12'	12'	large	- - -	white	orange	tolerant	sun	Tea Viburnum <u>Viburnum setigerum</u>	rounded form, flowers in early July
4-8	25'	25'	large	red	white, red	red	tolerant	sun	Siebold Viburnum <u>Viburnum sieboldi</u>	rounded form, flowers in late May, dark green leaves, outstanding as specimen plant
2-8	12'	12'	large	red	white	scarlet	wet	sun	American Cranberry-bush Viburnum <u>Viburnum trilobum</u>	flowers in late May, edible fruit

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Narrowleaf Evergreen Shrubs (to 15")

Hardi- ness Zones	Form	Height	Leaf Size	Color	Name	Comments
3-8	compact pyramidal branches slightly pendulous	10'	scale-like	glossy green	Slender Hinoki Falsecypress <u>Chamaecyparis obtusa 'gracilis'</u>	leaves are scale- like, like cypress
4-8	broad, flat-topped, pyramidal	10'	feather-like	- - -	Pfitzer Juniper <u>Juniperus chinensis 'pfitzeriana'</u>	leaves - light, feathery texture
4-8	low, creeping growth	1½'	needle-like	steel blue	Sargent Juniper <u>Juniperus chinensis 'sargentii'</u>	often grown in seashore areas
2-8	low, spreading growth	2'	feather-like	light green - purple in fall	Andorra Juniper <u>Juniperus horizontalis 'plumosa'</u>	- - -
4-8	wide spreading	6'	needle-like	bright blue	Meyer's Juniper <u>Juniperus squamata 'meyeri'</u>	vigorous
4-8	shape varies with variety - some global others prostrate	6'	needle-like	- - -	Mugho Pine <u>Pinus mugo 'mughus'</u>	susceptible to scale
6-8	varies with variety - most are upright	3'	needle-like	- - -	Spreading English Yew <u>Taxus baccata 'repandens'</u>	over 30 varieties have been listed, has red berries in fall
4-8	varies with variety	10'	needle-like	- - -	Spreading Japanese Yew <u>Taxus cuspidata</u>	one of the best narrowleaf ever- greens, has red berries in fall
4-8	pyramidal form, hori- zontal branches	20'	- - -	- - -	Upright Japanese Yew <u>Taxus cuspidata 'capitata'</u>	- - -
4-8	shrub-like growth, spreading branches	3'	needle-like	dull green	Dwarf Japanese Yew <u>Taxus cuspidata 'nana'</u>	leaves are shorter and more dull than the species
4-8	pyramidal with up- right branches	10'	needle-like	- - -	Hatfield Yew <u>Taxus media 'hatfieldi'</u>	very popular variety



SELECTED LANDSCAPE PLANTS, ZONES 2-8

Narrowleaf Evergreen Shrubs (to 15")

Hardi- ness Zones	Form	Height	Leaf Size	Color	Name	Comments
4-8	columnar	12'	needle-like	- - -	Hick's Yew <u>Taxus media 'hicksi'</u>	excellent for formal accent
2-8	usually conical in shape	15'	scale-like	- - -	Ware's Arborvitae <u>Thuja occidentalis 'wareana'</u>	valued for its fan-like branches rapid growth

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Large Broadleaf Evergreen Shrubs (12-30')

Hardi- ness Zones	Height	Leaf Size	Flower Color	Fruit Color	Soil	Exposure	Name	Form and Comments
7-8	15'	large (7")	- - -	red	- - -	requires shade	Japanese Aucuba <u>Aucuba japonica</u>	rounded form, dark green glossy leaves, variegated type is popular
5-8	15'	small	- - -	- - -	tolerant	- - -	Common Box <u>Buxus sempervirens</u>	rounded, often used as hedge or specimen plant
7-8	20'	large (4")	white to red	- - -	good	shade tolerant	Common Camellia <u>Camellia japonica</u>	pyramidal
7-8	20'	large (4")	white to red	- - -	good	shade tolerant	Sasanqua Camellia <u>Camellia sasanqua</u>	pyramidal, early flowering
8	15'	med.	- - -	red	- - -	- - -	Evergreen Euonymus <u>Euonymus japonicus</u>	upright to rounded form, excellent as hedge
5-8	20'	med.	- - -	red	good, well- drained	- - -	American Holly <u>Ilex opaca</u>	pyramidal with spiny leaves, slow growing, becomes tree in southern range
6-8	20'	large (4")	- - -	black	- - -	sun	Sweetbay Laurel <u>Laurel nobilis</u>	pyramidal, often sheared
6-7	18'	large (4-6")	white	black	- - -	sun	Common Laurel Cherry <u>Prunus laurocerasus</u>	rounded, popular for hedges
3-8	15'	large	rose to purplish- pink	- - -	- - -	requires partial shade	Rose Bay Rhododendron <u>Rhododendron maximum</u>	rounded, irregular form, large dark green leaves
7-8	30'	large (8")	white	red	well- drained	sun	Chinese Photinia <u>Photinia serrulata</u>	vigorous shrub, brilliant red young leaves, leggy unless occasionally pruned
5-8	12'	large (4-6")	white	red to black	- - -	sun	Leatherleaf Viburnum <u>Viburnum rhytidophyllum</u>	upright, evergreen in south

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Medium Deciduous Shrubs (6-10')

Hardi- ness Zones	Height	Width	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Form and Comments
4-8	9'	9'	med.	- - -	- - -	- - -	tolerant	sun or shade	Acanthopanax <u>sieboldianus</u>	very tolerant of shade and polluted air
5-8	7'	7'	small	- - -	yellow	red	tolerant	sun	Mentor Barberry <u>Berberis mentorensis</u>	rounded form, thorny, semi-evergreen
5-8	7'	7'	small	scarlet	yellow	dk. red	tolerant	sun	Japanese Barberry <u>Berberis thunbergii</u> ( <u>B. t. 'purpurea'</u> has red leaves)	rounded or columnar forms, colorful fruit and autumn foliage
4-8	6'	8'	med.	- - -	white to red	green	tolerant	sun	Flowering Quince <u>Chaenomeles lagenaria</u>	rounded form, many varieties
2-8	7'	7'	med.	reddish	white	white	moist	sun	Red Osier Dogwood <u>Cornus stolonifera</u>	loose-rounded, valued for its highly colored red winter twigs; there is a yellow-twigged form
5-8	6'	10'	small	dull red	pink	red	tolerant	sun	Spreading Cotoneaster <u>Cotoneaster divaricata</u>	arching spreading growth, semi-ever- green, bright red berries
4-8	9'	9'	small	- - -	pinkish	black	tolerant	sun	Hedge Cotoneaster <u>Cotoneaster lucida</u>	dense, rounded form, lustrous green foliage, susceptible to fire blight
5-8	8'	8'	med.	- - -	white	- - -	tolerant	sun	Snow-flake Deutzia <u>Deutzia scabra</u> ' <u>candidissima</u> '	arching form, flowers in late June
3-8	10'	10'	med.	scarlet	- - -	scarlet	tolerant	sun	Winged Euonymus <u>Euonymus alata</u>	rounded form, of particular interest because of winged horizontal branches

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Medium Deciduous Shrubs (6-10')

Hardi- ness Zones	Height	Width	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Form and Comments
5-8	9'	9'	med.	- - -	deep yellow	- - -	tolerant	sun	Forsythia, "Lynwood Gold," "Spring Glory," "Beatrix Farrand" <u>Forsythia intermedia</u> 'spectabilis'	upright growth, yellow flowers in mid-April
4-8	10'	10'	large	yellow	yellow	- - -	wet	sun or filtered sun	Vernal Witch-hazel <u>Hamamelis vernalis</u>	open, spreading form, blooms very early-- sometimes January or February
6-8	8'	6'	large	- - -	blue or pink	- - -	good	sun	French Hydrangea <u>Hydrangea macrophylla</u> 'hortensia'	rounded form, 6-10" round flower heads in August
3-8	9'	9'	med.	yellow	- - -	bright red	any good soil	sun or filtered sun	Winterberry Holly <u>Ilex verticillata</u>	berries remain to January
5-8 (3-10')	7' (3-10')	3-10'	small	- - -	bright yellow	- - -	tolerant	sun	Winter Jasmine <u>Jasminum nudiflorum</u>	rounded habit, pendu- lous branches, needs frequent pruning, early April flowering
4-8	5'	5'	med.	- - -	yellow	- - -	tolerant	sun	Kerria <u>Kerria japonica</u> 'pleniflora'	upright branches, ball-shaped flowers in mid-May, has green twigs all winter, much dead wood
4-8	10'	10'	med.	reddish	pink	brown	tolerant	sun	Beauty-bush <u>Kolkwitzia amabilis</u>	ornamental in spring, summer and winter; upright, arching
3-8	6'	6'	med.	russet purplish	white	black	tolerant	sun	Regel Privet <u>Ligustrum obtusifolium</u> 'regelianum'	branches almost hori- zontal, rounded form





SELECTED LANDSCAPE PLANTS, ZONES 2-8

Medium Deciduous Shrubs (6-10')

Hardiness Zones	Height	Width	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Comments
5-8	8'	8'	med.	- - -	white	red	tolerant	sun	Winter Honeysuckle <u>Lonicera fragrantissima</u>	rounded form, stiff leathery, half evergreen leaves, few. Great flowers in clusters
5-8	10'	10'	med.	blue to gray-green	rose	red	tolerant	sun or filtered sun	Blueleaf Honeysuckle <u>Lonicera korolkowii</u>	rounded form, sun. standing clusters in blue to gray. Green foliage in sun
2-8	9'	9'	med.	- - -	- - -	gray	sandy soils	sun or filtered sun	Northern Bayberry <u>Myrica pennsylvanica</u>	upright, dense form. aromatic, semi-evergreen leaves
5-8	6'	6'	med.	- - -	white	- - -	tolerant	sun	Avalanche Nockorange <u>Philadelphus lewisii</u> 'avalanche'	upright habit, upright arching branches. Fragrant flowers
5-8	6'	6'	med.	- - -	white	- - -	tolerant	sun	Albatre Nockorange <u>Philadelphus virginialis</u> 'albatre'	arching branches. Fragrant, double flowers
5-8	9'	9'	med.	- - -	white	- - -	tolerant	sun	Virginal Nockorange <u>Philadelphus virginialis</u> 'virginal'	Tree specimen plant. It is devoid of leaves in branches
5-8	9'	8'	large	yellow	yellow, orange, scarlet	- - -	acid, moist	sun or filtered sun	Flame Azalea <u>Rhododendron salicifolium</u>	upright habit, very colorful flowers in early June
4-8	6'	6'	med.	yellow to crimson	pale rosy-purple	- - -	acid, moist	sun or filtered sun	Korean Rhododendron <u>Rhododendron schimperianum</u>	upright, blooms in mid-April
4-8	10'	10'	large	yellow, orange, crimson	rose, pink	- - -	acid, moist	filtered sun	Royal Azalea <u>Rhododendron schimperianum</u> 'beschi'	rounded habit, large flowers and colorful autumn foliage
5-8	6'	6'	med.	- - -	white	black	tolerant	sun or filtered	Jetbead <u>Rhodotypos scandens</u>	rounded habit, intense coloring because black berries remain in winter

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Medium Deciduous Shrubs (6-10')

Hardi- ness Zones	Height	Width	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Comments
5-8	7'	7'	small	- - -	canary yellow	dark scarlet	tolerant	sun	Father Hugo Rose <u>Rosa hugonis</u>	rounded, arching habit, blooms in late May
2-8	5'	5'	med.	orange	pink to white	brick red	tolerant	sun	Rugosa Rose <u>Rosa rugosa</u>	upright, vigorous growth with an open, shrub, covered with large oval, double
4-8	7'	7'	med.	red to orange	white	- - -	tolerant	sun	Bridalwreath Spirea <u>Spiraea prunifolia</u> 'plena'	arching habit, numerous red, double, blooms, blooms in mid-May
4-8	7'	7'	med.	orange to red	pure white	brown	tolerant	sun	Van Moutte Spirea <u>Spiraea vanhouttei</u>	profuse white flowers clustered, arching habit, foliage with some double
3-8	6'	6'	small	- - -	pink	white	tolerant	sun	Snowberry <u>Symphoricarpos alba</u> 'lanceolata'	upright, arching white berries in fall
5-8	6'	6'	med.	- - -	lilac	- - -	tolerant	sun	Persea Lilac <u>Syringa persea</u>	flourishing, bushy upright, rounded form
5-8	9'	9'	med.	russet red	white	bright red	tolerant	sun	Linden Viburnum <u>Viburnum lindenii</u>	rounded form, flowers are clustered, flowers in early June, dense compact growth
4-8	10'	10'	med.	- - -	white	- - -	tolerant	sun	Japanese Snowball <u>Viburnum plicatum</u> 'sterile'	horizontal, in culture bears flowers in May
4-8	5'	5'	med.	reddish	white or pink	black	tolerant	sun	Koreanspice Viburnum <u>Viburnum spicatum</u>	dense rounded form, flowers in mid-May flowers are clustered suitable for graft diseases

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Medium Broadleaf Evergreen Shrubs (6-12')

Hardiness Zones	Height	Width	Leaf Size	Flower Color & Time	Fruit Color	Soil	Exposure	Name	Comments
7-8	6-10'	6'	7"	- - -	bright red	- - -	shade	Japanese Aucuba <u>Aucuba japonica</u>	rounded form, dense foliage
5-8	6'	6'	3" med.	yellow mid-May	bluish black	- - -	shade tolerant	Wintergreen Barberry <u>Berberis julianae</u>	rounded form, dense foliage, berries bright red
7-8	12'	12'	2-4"	silvery white	red berries	tolerant	sun	Thorny Eleagnus <u>Eleagnus pungens</u>	rounded form, dense foliage, berries bright red
8	12'	- - -	1-3"	- - -	pink to orange	- - -	- - -	Evergreen Euonymus <u>Euonymus japonica</u>	rounded form, upright habit, dense foliage
6-8	8'	8'	2-3" med.	- - -	pinkish to red	- - -	- - -	Spreading Euonymus <u>Euonymus alatus</u>	rounded form, dense foliage, berries bright red
7-8	9'	9'	3"	- - -	bright red	tolerant	sun	Burford Chinese Holly <u>Ilex cornuta</u>	rounded habit, dense foliage, berries bright red
6-8	8'	16'	small	- - -	black	- - -	- - -	Convex Japanese Holly <u>Ilex crenata</u>	after pruning as hedge or high, dense, spreading
5-8	10'	8'	5" large	pink and white mid-June	- - -	requires acid soil	- - -	Mountain laurel <u>Kalmia latifolia</u>	rounded form, dense foliage, berries bright red
7-8	9-18'	6'	4"	white mid-July	black	- - -	- - -	Japanese Privet <u>Ligustrum japonicum</u>	rounded, dense, used as hedge
7-8	8'	8'	- - -	white late July	bright red	tolerant	sun	Nandina <u>Nandina domestica</u>	upright habit, dense foliage, berries bright red
6-8	7'	4'	3 1/2" large	white mid-April	- - -	requires acid soil	full sun to semi-shade	Japanese Pieris <u>Pieris japonica</u>	flowers in spring, dense foliage, berries bright red

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Medium Broadleaf Evergreen Shrubs (6-12')

Hardiness Zones	Height	Width	Leaf Size	Flower Color & Time	Fruit Color	Soil	Exposure	Name	Remarks
5-7	18'	9'	4-6"	white - late May	black	- - -	- - -	Cherry Laurel <u>Prunus laurocerasus</u> <u>'Schubertiana'</u>	rounded, often used as a hedge
6-8	7'	8'	1 1/2"	white	bright red berries	tolerant	sun	Lalena Firethorn <u>Pyracantha coccinea</u> <u>'Lalena'</u>	berries persistent until fall in some areas
5-8	8'	8'	large up to 6"	light pink	red to black	rich - well-drained	semi-shade	Leatherleaf Viburnum <u>Viburnum phillyifolium</u>	rounded form, dense foliage, light heart

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Small Deciduous Shrubs (to 5')

Hardiness Zones	Height	Width	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Comments
5-8	4'	4'	small	scarlet	yellow, reddish outside	bright red	tolerant	sun	Purple Box Berry <i>Berberis thunbergii</i> 'Alage'	inundant in the Pacific Northwest
4-8	3'	4'	med.	- - -	red	green	tolerant	sun	Japanese Quince <i>Chaenomeles japonica</i>	spreading in the West; common in the Pacific Northwest
4-8	3'	5'	small	reddish	pinkish	red	tolerant	sun	Rock Cotoneaster <i>Cotoneaster horizontalis</i>	abundant in the Pacific Northwest; in the structure of the shrub; common in the Pacific Northwest
4-8	4'	4'	med.	- - -	white	- - -	tolerant	sun	Slender Dewberry <i>Doxylis flexilis</i>	in the Pacific Northwest; common in the structure of the shrub; common in the Pacific Northwest
3-8	5'	5'	med.	scarlet	- - -	scarlet	- - -	sun	Dwarf Winged Euonymus <i>Euonymus alatus</i> 'Compactus'	inundant in the Pacific Northwest; common in the structure of the shrub; common in the Pacific Northwest
4-8	3'	3'	large	- - -	white, ball-shaped clusters	- - -	tolerant	sun	Hills of Snow <i>Hydrangea sibirica</i> 'Hills of Snow'	inundant in the Pacific Northwest; common in the structure of the shrub; common in the Pacific Northwest
5-8	5'	5'	very large	reddish	white	- - -	tolerant	sun or filtered sun	Oak-leaved Hydrangea <i>Hydrangea ovata</i>	inundant in the Pacific Northwest; common in the structure of the shrub; common in the Pacific Northwest
4-8	3'	3'	small	- - -	bright yellow	- - -	tolerant	sun	Shrubby St. Johnswort <i>Hypericum pilosum</i>	inundant in the Pacific Northwest; common in the structure of the shrub; common in the Pacific Northwest
5-8	5'	5'	large	- - -	white, yellow, pink, red, lavender	- - -	good - well-drained	sun, no wind	Tree Peony <i>Paeonia moutanensis</i>	inundant in the Pacific Northwest; common in the structure of the shrub; common in the Pacific Northwest

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Small Deciduous Shrubs (to 5')

Hardiness Zones	Height	Width	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Remarks
2-8	4'	4'	small	- - -	yellow	- - -	tolerant	sun	Bush Cinquefoil <u>Potentilla fruticosa</u>	8 rounded fruits, some fruits are green
4-8	4'	4'	med.	- - -	pink, double	- - -	good	sun	Dwarf Flowering Almond <u>Prunus albertiana</u>	8 rounded fruits, fruits green in summer
5	5'	5'	med.	- - -	yellow, orange, red	- - -	acid	filtered sun	Hollis Arales <u>Rhododendron hybrid</u>	very light heart shaped flowers flowers at base
2-8	3'	3'	small	- - -	- - -	- - -	tolerant	sun	Arctic Willow <u>Salix arctica</u>	flowers 8 rounded fruits, fruits green in summer, flowers at base
5-8	2'	2'	med.	- - -	pink	- - -	tolerant	sun	Bonaida Spirea <u>Spiraea bumalda</u> <u>ALBERTA SPIREA</u>	8 rounded fruits flowers 8 rounded fruits at base
3-8	2'	2'	med.	red	- - -	- - -	tolerant	sun or light shade	Dwarf European Cran- berrybush <u>Viburnum corymbosum</u> <u>MAXIMILIAN</u>	8 rounded fruits, fruits green in summer
4-8	5'	5'	med.	- - -	red	- - -	tolerant	sun	Veigela <u>Veigela 'Blancol' RUGEL</u>	8 rounded fruits, fruits green in summer at base

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Small Broadleaf Evergreen Shrubs (to 6')

Hardiness Zones	Height	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Remarks
5-8	3-5'	1½"	- - -	pink	- - -	- - -	- - -	Glossy Abelia <u>ABELIA GLANDULOSA</u>	rounded form. flowers white to cream. great foliage color. flowers at junctions June to August
5-8	6'	3"	- - -	yellow	blue-black	- - -	- - -	Wintergreen Barberry <u>Berberis julianae</u>	dense rounded form
5-8	5'	2"	- - -	white - tinged with red	blue-black	- - -	- - -	Three Spine Barberry <u>Berberis ilicifolia</u> <u>pholia</u>	one of the most hardy barberry and very light green ground
5-8	4'	1"	bronze	golden yellow	violet-black	- - -	- - -	Warty Barberry <u>Berberis verticillata</u>	well rounded growth, attractive leathery foliage rounded form
5-8	4'	1"	- - -	- - -	- - -	- - -	- - -	Green Littleleaf Box <u>Buxus microcarpa</u> <u>microcarpa</u>	small heads of the opposite green form compact dense rounded form
5-8	5'	2"	- - -	yellow	- - -	tolerant	sun	Marshall's Broom <u>Syzygium glaucum</u>	rounded form habit, persistent foliage
4-8	6"	1"	- - -	pink	- - -	alkaline, well- drained	sun	Rose Dogbane <u>Apocynum androsaemifolium</u>	dense, compact form to 24" or 30" diam. best fragment flowers at top
5-8	5'	1"	- - -	pink	- - -	alkaline, well- drained	sun	Sourwood Dogbane <u>Apocynum androsaemifolium</u>	very light habit white abundant pink flowers at top

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Small Broadleaf Evergreen Shrubs (to 6')

Hardiness Zones	Height	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Remarks
5-8	4'	1-2"	- - -	- - -	orange	- - -	- - -	Bigleaf Wintercreeper <i>Euonymus</i> <u>laevis</u>	numbered form. 6-8-81 19-3-84 - excellent - 8-81-86
5-8	12"	1"	- - -	white	- - -	well-drained	sun or light shade	Evergreen Camellia <i>hibida camellifolia</i>	numbered form. excellent form. 6-8-81 at 8-81
6-8	4'	3/4"	- - -	- - -	black	- - -	- - -	Concealed Holly <i>Ilex</i> <u>laevis</u> <u>conspicua</u>	numbered form. 19-3-84 - excellent 19-3-84
4-8	3-6'	7"	bronze	white, drooping	- - -	acid	light shade	Drooping Leucothoe <i>leucothoe</i> <u>laevis</u>	numbered form. excellent form. 6-8-81 best at 8-81 Plantings
7-8	6'	1/2"	- - -	white	blue-purple	tolerant	sun	Box Honeysuckle <i>Lonicera</i> <u>maackii</u>	numbered form. 6-8-81 excellent form. 6-8-81 best at 8-81 Plantings
5-8	4'	- - -	bronze to purplish	bright yellow	bluish-black	- - -	light shade	Oregon Grape Nettle <i>Mahonia</i> <u>repens</u>	numbered form. 6-8-81 excellent form. 6-8-81 best at 8-81 Plantings
4-8	6'	3 1/2"	- - -	white	- - -	tolerant	light shade	Mountain Pieris <i>Pieris</i> <u>floribunda</u>	very light form form. 6-8-81 19-3-84
5-8	5'	3"	- - -	pale rosy purple	- - -	acid	light shade	Carolina Rhododendron <i>Rhododendron</i> <u>carolinianum</u>	very interesting form. 6-8-81 numbered form
4-8	6'	5"	- - -	lilac-purple	- - -	acid	light shade	Columba Rhododendron <i>Rhododendron</i> <u>columbianum</u>	very interesting form excellent at 8-81 19-3-84



SELECTED LANDSCAPE PLANTS, ZONES 2-8

Small Broadleaf Evergreen Shrubs (to 6')

Hardiness Zones	Height	Leaf Size	Fall Leaf Color	Flower Color	Fruit Color	Soil	Exposure	Name	Form and Comments
5-8	6'	- - -	- - -	vary widely	- - -	slightly acid	partial shade	Hybrid Azaleas <u>Rhododendron hybridum</u>	rounded form, brilliant colors vary in degree of hardness
4-8	6'	5"	- - -	white, pink, rose, red, lavender, purple	- - -	acid	light shade	Hybrid Rhododendrons <u>Rhododendron hybridum</u>	rounded form, color grouping - sometimes large shrubs
6-8	3'	- - -	- - -	white	- - -	slightly acid	partial shade	Snow Azaleas <u>Rhododendron hybridum</u>	compact, branching habit, color long lasting
6-8	3'	3/4"	reddish	rich magenta	- - -	slightly acid	partial shade	Azalea <u>Rhododendron hybridum</u>	rounded form, small flowers in form of long slender flowers at end of stem
6-8	4'	3/4"	reddish	salmon to brick-red	- - -	slightly acid	partial shade	Torch Azaleas <u>Rhododendron hybridum</u>	upright habit, brilliant flowers in form, usually erect stems
5-8	4'	- - -	- - -	petunia purple	- - -	slightly acid	partial shade	Korean Yodagans Azaleas <u>Rhododendron hybridum</u>	like the Japanese except more compact rounded form
7-8	3'	3-4"	- - -	- - -	red	- - -	- - -	Fragrant Sarcococca <u>Sarcococca hybridum</u>	upright habit, erect, lustre foliage
7-8	1 1/2'	4"	- - -	white	bright red	tolerant	shade only	Reeves Shrub <u>Skimmia japonica</u>	rounded, compact, some separate species

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Deciduous and Evergreen Vines

Hardiness Zones	Height	Type	Leaf Size	Fall Leaf Color	Flower Color	Soil	Exposure	Name	Comments
(D) 4-8	35'	twining	med.	- - -	purple	tolerant	sun or shade	Five-leaf Akeak <u>Akeak quinquefolia</u>	small - very green leafy growing
(D) 4-8	25'	tendrils	med.	- - -	- - -	tolerant	sun	Porcelain Akeak <u>Akeak quinquefolia</u> <u>peruviana</u> <u>peruviana</u>	small - very green change in color from green to yellow
(E) 6-8	60'	tendrils	large	- - -	orange-red	tolerant	sun	Cross Vine <u>Bignonia capreolata</u>	very low - climbing good climber
(D) 4-8	30'	clinging vine	large	- - -	orange to scarlet	tolerant	sun	Trumpet Creeper <u>Campsis tagliabuana</u> <u>radicans</u>	large - climbing attractive - variable color spectrum
(D) 2-8	20'	twining	med.	yellow	- - -	tolerant	sun	American Bittersweet <u>Celastrus occidentalis</u>	very low - climbing very low - climbing attractive - variable color spectrum
(D) 5-8	20'	tendrils	med.	- - -	various	alkaline	light	Clematis <u>Clematis integrifolia</u>	large - climbing attractive - variable color spectrum
(D) 5-8	30'	tendrils	med.	- - -	white	tolerant	sun	Sweet Autumn Clematis <u>Clematis flammula</u>	attractive - climbing attractive - climbing attractive - climbing
(E) 5-8	25'	clinging vine	med.	- - -	- - -	tolerant	sun or shade	Bigleaf Winter- creeper <u>Lonicera japonica</u> <u>peruviana</u>	one of earliest of <u>Lonicera</u> group attractive - climbing attractive - climbing attractive - climbing

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Deciduous and Evergreen Vines

Hardi- ness	Zones	Height	Type	Leaf Size	Fall Leaf Color	Flower Color	Soil	Exposure	Name	Comments
(E)	7-8	12'	clinging vine	large	- - -	- - -	tolerant	sun or shade	Algerian Ivy <u>Hedera canariensis</u>	"Canary Queen" a popular variegated form
(E)	5-8	90'	clinging vine	large	- - -	- - -	tolerant	sun or shade	English Ivy <u>Hedera helix</u> 'Baltic'	excellent in north and south, there are numerous forms, all less hardy than "Baltic." Old plants have green flowers and black fruits
(D)	4	75'	clinging vine	large	- - -	white	tolerant	light shade	Climbing Hydrangea <u>Hydrangea petiolaris</u>	large flower heads in mid-June, dark shiny leaves, slow growing
(D)	7-8	30'	semi- climbing	med.	- - -	white	tolerant	sun or light shade	Common White Jasmine <u>Jasminum officinale</u>	very fragrant flowers, semi-ever- green
(D)	4-8	20'	twining vine	med.	- - -	yellowish red to purplish red	tolerant	sun	Henry Honeysuckle <u>Lonicera henryi</u>	half evergreen
(E)	3-8	50'	twining vine	- - -	- - -	orange to scarlet	- - -	- - -	Trumpet Honeysuckle <u>Lonicera sempervirens</u>	evergreen, not rampant
(E)	4-8	15'	clinging vine	small	scarlet	- - -	tolerant	sun	Low's Japanese Creeper <u>Parthenocissus</u> <u>tricuspidata</u> 'lowi'	apple green leaves similar to 'veitchi'
(D)	4-8	15'	clinging vine	small	scarlet	- - -	tolerant	sun	Veitch Japanese Creeper <u>Parthenocissus</u> <u>tricuspidata</u> 'veitchi'	leaves purple when young, excellent for "tracery" effect on walls

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Deciduous and Evergreen Vines

Hardi- ness Zones	Height	Type	Leaf Size	Fall Leaf Color	Flower Color	Soil	Exposure	Name	Comments
(D) 8	30'	tendrils	large	- - -	white to blue	good	sun	Passion Flower <u>Passiflora caerulea</u>	very popular, semi- evergreen
(D) 4-8	90'	twining vine	med.	yellow	violet, white, pink	tolerant	sun	Japanese Wisteria <u>Wisteria floribunda</u>	pea-like flowers in pendulous racemes 12-36" long, in late May, needs frequent pruning
(D) 5	90'	twining vine	- - -	- - -	blue- violet	- - -	- - -	Chinese Wisteria <u>Wisteria sinensis</u>	flowers in 12" racemes mid-May, needs frequent pruning

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Deciduous and Evergreen Ground Covers

Hardi- ness Zones	Height	Leaf Size	Soil	Exposure	Name	Comments
(D) 3-8	8"	med.	any	sun or shade	Goutweed <u>Aegopodium podagraria</u> ' <u>variegatum</u> '	cream and green foliage; useful in difficult situations; but invasive
(D) 4-8	8"	med.	any	sun or shade	Carpet Bugle <u>Ajuga reptans</u>	green, bronze, red, and variegated leaf forms available, blue flowers, useful in difficult situations, but invasive
(D) 4-8	8"	fine	good	light to heavy shade	Sweet Woodruff <u>Asperula odorata</u>	spreads rapidly, white flowers, tolerates very dense shade
(E) 4-8	4-24"	fine	acid, moist, low fertility	light shade	Scotch Heather <u>Calluna vulgaris</u>	head back in late winter to hold compact form, colors: white through red, flowers during fall, winter and early spring
(D) 2-8	8"	large	any	light shade to sun	Lily-of-the-Valley <u>Convallaria majalis</u>	spreads rapidly in good soil, white flowers in May, poor foliage color in autumn
(D) 4-8	1½-3'	med.	good	sun	Rock Cotoneaster <u>Cotoneaster horizontalis</u>	mounded form, evergreen in south, red fruit into winter
(E) 5-8	8"	large	good	partial shade	English Ivy <u>Hedera helix</u> 'Baltic'	rapid growing evergreen - also a vine, 'baltica' more cold tolerant than other selections
(E) 4-8	12"	needle-like	any	sun	Sargent Chinese Juniper <u>Juniperus chinensis</u> 'sargentii'	dense mat forming, steel blue color, seaside plant
(E) 2-8	12-18"	needle-like	any	sun	Creeping Juniper <u>Juniperus horizontalis</u>	Waukegan Juniper (J. h. 'dough-lasi') dense, trouble free, steel blue color Andora Juniper (J. h. 'plumosa') dense, trouble free, feathery blue-green in summer purplish in winter

SELECTED LANDSCAPE PLANTS, ZONES 2-8

Deciduous and Evergreen Ground Covers

Hardi-ness Zones	Height	Leaf Size	Soil	Exposure	Name	Comments
(D) 4-8	24"	med.	any	sun	Henry Honeysuckle <u>Lonicera henryi</u>	half evergreen climbing vine with yellowish red to purplish flowers, excellent on banks clear of shrubs and trees which it will climb
(E) 5-8	12"	needle-like	acid	sun or shade	Canby Pachistema <u>Pachistema canbyi</u>	dense growth, flat 1" needle leaves, requires acid soil, good drainage
(E) 4-8	6"	large	any	shade	Japanese Spurge <u>Pachysandra terminalis</u>	dense, trouble free, popular, it grows best in light to heavy shade, the color becomes an attractive yellowish-green in <sup>3</sup> / <sub>4</sub> full sun
(E) 7-8	18"	med.	tolerant	sun	Chilean Pernettya <u>Pernettya mucronata</u>	popular in mid-south, becomes straggly in shade, white, pink, red, violet, <sup>1</sup> / <sub>2</sub> " persistent fruit of particular interest
(D) 5-8	12"	med.	tolerant	sun	Memorial Rose <u>Rosa wichuriana</u>	semi-evergreen, vigorous, effective white flowers, especially good for erosion control on banks
(D) 2-8	8"	med.	acid	sun	Smoothleaf Lowbush Blueberry <u>Vaccinium augustifolium</u> <u>'laevifolium'</u>	especially good for acid, rocky, low-fertility soils
(E) 4-8	6"	med.	any	sun or shade	Myrtle, Periwinkle <u>Vinca minor</u>	persistent, trouble free, attractive blue, white, or purple flowers, often used for erosion control on banks, very popular

SELECTED LANDSCAPE PLANTS

Garden Flowers, Herbaceous Perennials

Height	Months in Bloom	Flower Color	Soil	Exposure	Spacing	Name	Comments
med.	September	pink	medium	filtered sun, no wind	12"	Grapeleaf Anemone <u>Anemone vitifolia</u>	good companion for lilies, self-sows, but not rampant
med.	July	orange	well-drained	sun	18"	Butterfly Weed <u>Asclepias tuberosa</u>	permanent, difficult to transplant
med.	June	white, pink, red	wet	filtered sun	18"	Astilbe <u>Astilbe hybrids</u>	plume-shaped flower spikes, sensitive to drying, tolerant of wet soil
med.	June to July	white	medium	sun	18"	Shasta Daisy <u>Chrysanthemum maxi-mum</u>	must be reset every 2 years or dies out
med.	August to October	many, but no blue	medium	sun	18"	Florists Chrysanthemum <u>Chrysanthemum morifolium</u>	tall kinds require staking, pinch to July 1 for compact habit, reset every year
tall	July to September	white, blue, violet	well-drained	sun, no wind	18"	Delphinium <u>Delphinium hybrid</u> esp. <u>D. belladonna</u> h.	usually requires staking
tall	May	rose	medium	filtered sun	24"	Common Bleedingheart <u>Dicentra spectabilis</u>	permanent, resents disturbance, foliage gone after July
med	June	pink, white	medium	sun	24"	Gas Plant Dittany <u>Dictamnus fraxinella</u>	permanent, resents disturbance, blooms give off ignitable gas
tall	June to October	blue	medium	sun	24"	Small Globethistle <u>Echinops ritro</u> esp. <u>'Taplow Blue'</u>	spherical blooms, reset every 2-3 years

SELECTED LANDSCAPE PLANTS

Garden Flowers, Herbaceous Perennials

Height	Months in Bloom	Flower Color	Soil	Exposure	Spacing	Name	Comments
tall or med.	May to October	yellow, orange, pink, mahogany	tolerant	sun	24"	Daylily <u>Hemerocallis hybrids</u>	hundreds of named cultivars, flowering period varies with cultivar and age, some are night-flowering, reset every 3-4 years
med.	June to October	red	medium	sun or filtered sun	12"	Coral Bells <u>Heuchera sanguinea</u>	foliage only 6" high, good cut flower, reset every 2-3 years
tall	August to September	white, rose, red	wet	sun	36"	Rosemallow <u>Hibiscus moscheutos</u>	late and slow spring growth, large blooms, tolerates very wet soil
short	May	white	medium	sun	12"	Evergreen Candytuft <u>Iberis sempervirens</u>	permanent, old plants may require reshaping
med.	July	orange	well-drained	sun	18"	Sword Torchlily <u>Kniphofia foliosa</u>	permanent
short	June to August	lavender	medium	sun	12"	True Lavender <u>Lavandula vera</u> esp. 'Munstead'	permanent, may be sheared for dwarf
tall	August to September	red	wet	filtered sun	18"	Cardinal Flower <u>Lobelia cardinalis</u>	permanent, brilliant flowers, thrives in wet soil
tall	July to September	pink	wet	sun	18"	Loose Strife <u>Lythrum superbum</u>	named cultivars are better than species, may be grown in shallow water



SELECTED LANDSCAPE PLANTS

Garden Flowers, Herbaceous Perennials

Height	Months in Bloom	Flower Color	Soil	Exposure	Spacing	Name	Comments
med.	June	white, pink, red	medium	sun	36"	Peony <u>Paeonia hybrids</u>	resents disturbance, brown foliage in fall should be removed and burned to prevent bud blight
med.	June to July	white, orange, red	tolerant	sun	24"	Oriental Poppy <u>Papaver orientale</u>	permanent, very large blooms, foliage dies after July, can be reset <u>only</u> in August
med.	July to August	white, pink	medium	sun	12"	Summer Phlox <u>Phlox paniculata</u>	remove old flower heads of inferior seedlings will replace cultivar, reset every 2 years
med.	June	yellow, gold	medium	sun	18"	Globeflower <u>Trollius europaeus</u>	permanent, blooms resemble giant buttercup

SELECTED LANDSCAPE PLANTS

Garden Flowers, Herbaceous Annuals

Height	Months in Bloom	Flower Color	Soil	Exposure	Spacing	Name	Comments
tall, med., or short	July to October	all except blue	medium	sun	9-12"	Common Snapdragon <u>Antirrhinum majus</u>	height depends on cultivar, good cut flower
med.	July to October	foliage, all except blue and lavender	medium	filtered sun	9"	Common Coleus <u>Coleus blumei</u>	grown for interesting foliage colors
short	July to October	all except blue	medium	filtered sun or sun	9"	Sultan Snapweed <u>Impatiens sultani</u>	outstanding for shade, will flower well as a house plant
med.	June to October	white, pink, red	medium	sun	9"	Fish Pelargonium <u>Pelargonium hortorum</u>	very popular
short	June to October	all colors	tolerant	filtered sun or sun	9"	Petunia <u>Petunia hybrid</u>	most popular annual; cut to 6" and fertilize in August for good fall flowering
tall, med., or short	June to October	red	tolerant	filtered sun or sun	12-24"	Scarlet Sage <u>Salvia splendens</u>	height depends on cultivar, brilliant color
tall, med., or short	July to October	yellow, orange, and mahogany	tolerant	sun	9-12"	Aztec Marigold <u>Tagetes erecta</u>	height depends on cultivar, very popular

SELECTED LANDSCAPE PLANTS

Garden Flowers, Bulbs

Height	Months in Bloom	Flower Color	Soil	Exposure	Spacing	Planting Depth	Name	Comments
short	September	lavender	tolerant	sun	12"	6"	"Autumn Crocus" <u>Colchicum autumnale</u>	permanent not a true crocus
short	April	white, blue, lavender and yellow	well- drained	sun, fil- tered sun	4"	4"	Crocus <u>Crocus species</u>	foliage must ripen for flowers after first year, corms eaten by rodents
tall	July	white	well- drained	sun	18"	6"	Madonna Lily <u>Lilium candidum</u>	very fragrant, spray with captan in spring to prevent Botrytis
tall	September	pink	well- drained	sun	12"	9"	Rubrum Lily <u>Lilium speciosum</u> ' <u>rubrum</u> '	requires staking
short	May	blue	tolerant	sun, fil- tered sun	4"	4"	Armenian Grape Hya- cinth <u>Muscari armeniacum</u>	permanent, foliage remains all year
med.	April to May	yellow, white	tolerant	filtered	6"	6-9"	Daffodil <u>Narcissus pseudo-</u> <u>narcissus</u>	foliage must ripen for good flowering next season, may be used in woodlands
short	April to May	blue	tolerant	sun, fil- tered sun	4"	4"	Siberian Squill <u>Scilla siberica</u>	cultivar "Spring Beauty" is best, per- manent, may be planted close to deciduous shrubs
med.	May	all	well- drained	filtered sun	6"	6-9"	Tulip <u>Tulipa hybrid</u>	foliage must ripen for good flowering next season, lift only once in 3 years, per- manence depends on cultivar

APPENDIX D

Addresses for Agricultural Extension Publication Services

MAILING ROOM  
Agricultural Extension Service  
Agricultural and Home Economics  
Experiment Station and Cooperative  
Extension Service  
Iowa State University of Science and  
Technology  
Ames, Iowa 50010

Agricultural Extension Service  
MSU Bulletin Office  
P. O. Box 231  
East Lansing, Michigan 48823

Extension Director  
College of Agriculture  
University of Connecticut  
Storrs, Connecticut 06268

MAILING ROOM  
Agricultural Extension Service  
Agricultural Hall  
University of Delaware  
Newark, Delaware 19711

Cooperative Extension Director  
Agricultural Extension Service  
University of Maine  
Orono, Maine 04473

Extension Director  
Agricultural Extension Service  
University of Maryland  
College Park, Maryland 20740

Extension Director  
Agricultural Extension Service  
University of Massachusetts  
Amherst, Massachusetts 01002

Cooperative Extension Director  
Agricultural Extension Service  
Thompson Hall  
University of New Hampshire  
Durham, New Hampshire 08324

Associate Director  
Agricultural Extension Service  
College of Agriculture  
Rutgers University  
New Brunswick, New Jersey 08900

MAILING ROOM  
Agricultural Extension Service  
Stone Hall  
Cornell University  
Ithaca, New York 14850

Extension Director  
102 Armsby Building  
The Pennsylvania State University  
University Park, Pa. 16802

Ag. Editor's Office  
16 Woodward Hall  
University of Rhode Island  
Kingston, Rhode Island 02836

Extension Service Director  
Agricultural Extension Service  
Morrill Hall  
University of Vermont  
Burlington, Vermont 05401

Office of Information  
U. S. Department of Agriculture  
Washington, D. C. 20250