

DOCUMENT RESUME

ED 164 359

SE 026 545

AUTHOR Ackerman, Allan D.; And Others
 TITLE In the Bank...Or Up the Chimney? A Dollars and Cents Guide to Energy-Saving Home Improvements. 2nd Edition.
 INSTITUTION Abt Associates, Inc. Cambridge, Mass.
 SPONS AGENCY Department of Housing and Urban Development, Washington, D.C. Office of Policy Development and Research.
 REPORT NO HUD-PDR-89(4)
 PUB DATE Aug 77
 CONTRACT H-2681
 NOTE ~~Not available~~; Not available in hard copy due to numerous colored print, shaded charts and graphs; For related document, see ED 146 042
 AVAILABLE FROM Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402 (Stock Number 023-000-00411-9; No price quoted)
 EDRS PRICE MF-\$0.83 Plus Postage. HC Not Available from EDRS.
 DESCRIPTORS Air Conditioning; *Building Improvement; Climate Control; *Cost Effectiveness; Energy; *Energy Conservation; Fuels; *Guides; Heating; *Home Management; Ventilation
 IDENTIFIERS *Weatherization

ABSTRACT


This publication is a homeowner's guide to energy conserving home improvements. This second edition is the same as the earlier version except that the energy conservation cost and saving estimates are based on more current fuel prices. The reader is led through steps to assess the energy conservation needs of a home and then through how to effect the improvements. The major emphasis in this guide is on insulation and other weatherization measures that are simple and effective. (MR)

 * Reproductions supplied by EDRS are the best that can be made *
 * from the original document. *

IN THE BANK... OR UP THE CHIMNEY?

A Dollars and Cents Guide to Energy-Saving Home Improvements

ED164359



U.S. DEPARTMENT OF HEALTH,
EDUCATION & WELFARE
NATIONAL INSTITUTE OF
EDUCATION

THIS DOCUMENT HAS BEEN REPRODUCED EXACTLY AS RECEIVED FROM THE PERSON OR ORGANIZATION ORIGINATING IT. POINTS OF VIEW OR OPINIONS STATED DO NOT NECESSARILY REPRESENT OFFICIAL NATIONAL INSTITUTE OF EDUCATION POSITION OR POLICY.



SE 026 545



Preface

To the American Homeowner:

I am sure you are aware that heating and cooling your home is costing more money than ever before. This does not have to be true. There is clear and reliable information to help you put dollars in the bank instead of up the chimney.

The results of HUD-sponsored research on the many ways to save energy and money while heating and cooling your house are described in this booklet.

It doesn't matter whether your house is built of brick, wood or other material. HUD has included energy-saving techniques applicable to all types of housing, and from the explanations in this booklet, you will be able to choose the best methods for your house. This booklet will also help you choose between those energy-saving steps you can do for yourself and those you will want to hire a contractor to undertake. Tables are provided to enable you to compute the cost-savings of each method.

We at HUD believe this booklet is very useful. We hope that you will use it to save money and energy for your family and the Nation.



Patricia Roberts Harris
Secretary

IN THE BANK... OR UP THE CHIMNEY?

A Dollars and Cents Guide to Energy-Saving Home Improvements

2nd EDITION

Prepared for the

Office of Policy Development and Research,

Division of Energy, Building Technology and Standards,

U.S. Department of Housing and Urban Development

Under Contract H-2179R by

Abt Associates, Inc.
Cambridge, Massachusetts
April 1975

Revised under Contract H-2681 by

Technology + Economics, Inc.
Cambridge, Massachusetts

August 1977



For sale by the Superintendent of Documents
U.S. Government Printing Office
Washington, D.C. 20402

Stock No. 023-000-00411-9

Financing Energy-Saving Home Improvements

HUD/FHA-insured "Title I" home improvement loans can be used to finance energy saving home improvements (see page 66). Contact your bank or local HUD Office for information on terms and amounts.

Tax Credits

At the time of this publication, federal tax credits to benefit homeowners who make energy-saving investments had not yet been enacted. However, in the near future this situation is almost certain to change, making the improvements described here even more financially attractive. There will be a limit to those credits; we hope this manual will serve as a tool to help you make the most of them, both in terms of fuel dollars you save, and in terms of energy saved for the nation. Be sure to check with the local office of the Internal Revenue Service before applying for a tax credit for energy saving improvements.

More Information

A more detailed, technical presentation of the material in this manual is available, and is recommended for use by contractors, architects, and engineers. Enclose \$7.50 for paperbound, \$3.00 for microfiche, and write for "Cost-Effective Methods to Reduce the Heating and Cooling Energy Requirements of Single-Family Dwellings," Stock Number PB241919:

National Technical Information Service
5285 Port Royal Road
Springfield, Virginia 22151

More Copies of this Manual

If you think your company, organization, or department would be interested in obtaining quantities of "IN THE BANK...OR UP THE CHIMNEY?", information on getting discounts for orders in quantity is available. In addition, information on using this manual as a promotional device, or in energy education programs is also available. Write:

Office of Policy Development and Research
Division of Product Dissemination and Transfer
U.S. Department of Housing and Urban Development
451 7th Street, S.W., Room 8126
Washington, D.C. 20410

CONTENTS

PART 1: A QUICK LOOK AT YOUR HOME

Page 1

PART 2: A CLOSER LOOK AT YOUR HOME

Page 5

| | |
|--|----|
| Caulk and Weatherstrip Your Doors and Windows | 8 |
| Install Storm Windows | 10 |
| Insulating Your Attic | 11 |
| Insulate Your Unfinished Attic | 12 |
| Insulate Your Unfinished Floored Attic | 14 |
| Insulate Your Finished Attic | 16 |
| Insulate Your Walls | 19 |
| Insulating Your Crawl Space Walls, Floor or Basement Walls | 21 |
| Insulate Your Crawl Space Walls | 22 |
| Insulate Your Floor | 23 |
| Insulate Your Basement Walls | 24 |
| Thermostat, Furnace and Air Conditioner | 25 |
| Your Heating and Cooling Factors | 28 |

PART 3: HOW TO DO IT

Page 31

| | |
|--|----|
| WINDOWS AND DOORS | |
| Caulk the Openings in Your Home | 34 |
| Weatherstrip Your Windows | 36 |
| Weatherstrip Your Doors | 38 |
| Install Plastic Storm Windows | 40 |
| Install Single Pane Storm Windows | 41 |
| Install Combination Storm Windows | 42 |
| Install Combination Storm Doors | 43 |
| INSULATION | |
| Buying Insulation | 44 |
| Insulate Your Unfinished Attic | 47 |
| Insulate Your Unfinished Floored Attic | 50 |
| Insulate Your Finished Attic | 53 |
| Do You Need a Vapor Barrier or More Ventilation in Your Attic? | 54 |
| Insulate Your Wood Frame Walls | 55 |
| Insulate Your Crawl Space Walls | 56 |
| Insulate Your Floor | 58 |
| Insulate Your Basement Walls | 60 |
| SAVING ENERGY WITH YOUR HEATING, AIR CONDITIONING, AND WATER | |
| HEATING | 62 |
| CHOOSING A CONTRACTOR | 66 |
| GETTING FINANCING | 66 |

PART 4: MORE...on how to save heating & cooling energy

Page 67

| | |
|------------------------------------|----|
| Index | 74 |
| Acknowledgements and Authors | 75 |
| THE ENERGY CHECKLIST | 76 |

HOW TO USE THIS MANUAL

TWO WAYS TO BEGIN

Whether you begin with Part 1 or Part 2, you won't have to read all of it — just what applies to your home.

1. Take a Quick Look at Your Home

Start on page 2...




... to look at your home from your armchair — you don't have to measure or count a thing. Depending on where you live and whether or not you have air conditioning, Part 1 will tell you what your best energy-saving steps are. You'll get a rough idea of what they'll cost, and how much they'll save you each year.

OR

2. Take a Closer Look


Start on page 7...

... if you're willing to count your windows, make some quick measurements, and do a little arithmetic. Part 2 will tell you much more than Part 1. It's tailored to your home — and it'll give you a pretty good idea of your costs and savings for each energy-saving home improvement.



THEN ... DO IT!

Go on to page 33...



... each energy-saving home improvement you've chosen is spelled out in detail. You'll find out how to do-it-yourself, or, how to hire a contractor and see that he does the job right.

There's More, too...

Page 69...

Part 4 has lots more ways to save energy — and some new ways to come in the future.

PART 1: A QUICK LOOK AT YOUR HOME

PART 1: A QUICK LOOK AT YOUR HOME

There are ranges of costs and savings given for the energy-savings improvements on these two pages. For comparison with your home, a single-story, 1250 square-foot house in Washington, D.C. paying \$.45 per gal. of oil, \$.16 per hundred cubic feet of gas, or \$.03 per kilowatt of electricity will fall at about the middle of the range given.

YOUR HEATING SAVINGS



You can save significantly on heating if you live practically anywhere in the U.S.A.

Look at the map above.


If you live in the part of the country that's shaded, here are two packages of energy-saving measures for you:

Package 1 is cheap and easy, and it pays for itself every year.

Package 2 saves even more, year after year. It can cut your heating bills by as much as one-half. It will pay for itself within 5 years.


Package 1

1. Turn down thermostat 6° in winter from your usual setting.



Package 2

1. Turn down thermostat 6° in winter from your usual setting.



2. Put on plastic storm windows.



YOUR AIR-CONDITIONING SAVINGS




Package 3


Look at the map to the left.

Package 3 can save you money on your air-conditioning bills, if you live in the part of the country that's shaded.

2. Put on plastic storm windows.



3. Service your oil furnace



Here's an idea of what Package 1 costs and saves in a typical home.


| | Yearly Cost | Yearly Savings |
|--------------------------|----------------|-----------------|
| 1. Turn down thermostat | \$0 | \$27-87 |
| 2. Put on plastic storms | \$7-9 | \$27-73 |
| 3. Service oil furnace | \$25 | \$33-87 |
| TOTAL | \$32-34 | \$87-247 |

If you already have storm windows, or if you don't have an oil furnace -- then take a look at package 2.

3. Service your oil furnace.



4. Caulk and weatherstrip your doors and windows.



5. Insulate your attic.



Here's an idea of what Package 2 costs and saves in a typical home (Items 4 and 5 reduce the heating bill to which the effects of Items 1, 2, and 3 are applied, so 1, 2, and 3 save less here than in Package 1):

| | 1st Year Cost | Yearly Savings |
|---------------------------|------------------|------------------|
| 1. Turn down thermostat | \$0 | \$13-53 |
| 2. Put on plastic storms | \$7-9 | \$20-60 |
| 3. Service oil furnace | \$25 | \$20-53 |
| 4. Caulk and weatherstrip | \$75-105* | \$40-100 |
| 5. Insulate your attic | \$300-450* | \$50-75 |
| TOTAL | \$407-589 | \$143-341 |


* These are do-it-yourself costs. If you called a contractor, these items could cost twice as much.

You might or might not need to do all of these things. Turn the page to find out which items apply to your home.


1. Turn up thermostat 6° in summer from your usual setting.



2. Insulate your attic.



3. Caulk and weatherstrip your doors and windows.



Here's an idea of what Package 3 costs and saves in a typical home:

| | 1st Year Cost | Yearly Savings |
|---------------------------|------------------|-----------------|
| 1. Turn up thermostat | \$0 | \$7-20 |
| 2. Insulate your attic | \$300-450* | \$33-67 |
| 3. Caulk and weatherstrip | \$75-105* | \$27-67 |
| TOTAL | \$375-555 | \$67-154 |

* These are do-it-yourself costs. If you called a contractor, these items could cost twice as much.

You might or might not need to do all of these things. Turn the page to find out which items apply to your home.

And if you live in the part of the country that's shaded on both maps, these cooling savings are *in addition* to what you save on heating -- turn the page to see what your total savings will be.

HEATING AND AIR-CONDITIONING SAVINGS TOGETHER

If you have whole-house air conditioning and if you live in the part of the country that's shaded on both of the maps on the previous page, some of the energy-saving steps save on both heating and cooling — but you only have to pay for them once.

LOOK AT THESE TWO TABLES FOR AN ESTIMATE OF THE COMBINED COSTS AND SAVINGS FOR A TYPICAL HOME:

Table 1

Package 1 plus turning up the thermostat in summer:

| | Yearly Cost | Yearly Savings |
|--------------------------------|----------------|-----------------|
| Turn down thermostat in winter | \$0 | \$27-87 |
| Turn up thermostat in summer | \$0 | \$7-20 |
| Put on plastic storms | \$7-9 | \$27-73 |
| Service oil furnace | \$25 | \$33-87 |
| TOTAL | \$32-34 | \$94-267 |

Table 2

Package 2 and Package 3 together:

| | 1st Year Cost | Yearly Savings |
|--------------------------------|------------------|------------------|
| Turn down thermostat in winter | \$0 | \$27-87 |
| Turn up thermostat in summer | \$0 | \$7-20 |
| Put on plastic storms | \$7-9 | \$20-73 |
| Service oil furnace | \$25 | \$20-53 |
| Caulk and weatherstrip | \$75-105* | \$67-167 |
| Insulate attic | \$300-450* | \$80-227 |
| TOTAL | \$407-589 | \$221-626 |

* These are do-it-yourself costs. If you have a contractor do it, these items could cost about twice as much.

Which items do you need to do?


Do you need to adjust your thermostat?

Everyone can profit from turning their thermostat down in winter and up in summer.

Do you need to put on storm windows or service your oil furnace?


You do if you live in the part of the country that's shaded on the upper map on the last page. Put on storm windows if you don't have them already. Plastic ones are cheapest. See page 40. Service your oil furnace each year if you have one. See page 63. If you have a gas furnace, service it every three years and save, too.

Do you need to add caulk or putty?



Look around the edges of a typical window, where the picture shows. Check the edges of your doors, too. There should be some filler in all these cracks. That's either *caulking* or *putty*. If it's old, brittle, and broken up, or if it's missing altogether, you need to put some in. Go to page 34 to find out how to do it.

Do you need to weatherstrip?



Look for the strips of vinyl, metal, or foam-rubber around the edges of your windows and doors. That's *weatherstripping*. If it's missing or deteriorated, you need to put some in. Go to pages 36-39 to find out how to do it.

Do you need to insulate your attic?


Go up into your attic and see how much insulation is there. Usually, there's a door or hatchway to the attic. If not, get a contractor to check it for you. Look at the table on page 44 to see how much more insulation you need.

Keep Going

... there are lots more energy-saving ideas in Parts 3 and 4, starting on page 33. If you want more accurate cost and savings figures, look at Part 2, starting on the next page.

IN THE BANK ... OR UP THE CHIMNEY

PART 2: A CLOSER LOOK AT YOUR HOME



This part of your manual takes a closer look at your home, where it is in the country, and the best, cheapest way to fix up your house to save energy. In Part 2 there are 12 valuable energy-saving steps. You'll find out which ones apply to your home and:

1. How much they'll cost; of those steps that do apply, which you can afford.
2. Which to do first; of those steps you can afford, which ones get you your money back the fastest.
3. How much you'll save by taking an energy-saving step.

You Can Skip Some of Part 2



Each energy-saving step has a page or two in this part. Go through these one at a time. You'll see immediately that you can skip some of them.

There's a section at the beginning of the pages on each energy-saving step. Reading this section and checking some items around your home, you'll find some more measures you can skip.



Some of Part 2 is Just What You Need



There are sure to be several energy-saving steps here that *do* apply to your home. Every time you find a step that does, follow the pages through until you get the two important numbers for each step: **COST**, and **SAVINGS FACTOR**, then copy them onto the Energy Checklist at the end of the book. The Energy Checklist lets you see all the numbers for your energy-saving steps in one place. Once you've copied your **COST** and **SAVINGS FACTOR** onto the Checklist, there's a little arithmetic – the directions are all right there. Then you're ready to go – you'll know what to do first, how much you'll save the first year, and whether you can afford it.

TABLE OF CONTENTS

| | | | |
|---|----|--|----|
| Caulk and Weatherstrip Your Doors and Windows | 8 | Insulate Your Walls | 19 |
| Install Storm Windows | 10 | Insulating Your Crawl Space Walls, Floor or Basement Walls | 21 |
| Insulating Your Attic | 11 | Insulate Your Crawl Space Walls | 22 |
| Insulate Your Unfinished Attic | 12 | Insulate Your Floor | 23 |
| Insulate Your Unfinished Floored Attic | 14 | Insulate Your Basement Walls | 24 |
| Insulate Your Finished Attic | 16 | Thermostat, Furnace and Air Conditioner | 25 |
| | | Your Heating and Cooling Factors | 28 |


CAULK AND WEATHERSTRIP YOUR DOORS AND WINDOWS



Caulking and weatherstripping are good cheap ways to save energy. It's worth your while to check to see if you need caulking, putty, or weatherstripping on your windows and doors.

DO THEY NEED CAULKING OR PUTTY?

Look at a typical window and a typical door. Look at the parts shown in the pictures. Check the box next to the description that best fits what you see:




- OK... All the cracks are completely filled with caulking. The putty around the window panes is solid and unbroken; no drafts.
- FAIR... The caulking and putty are old and cracked, or missing in places; minor drafts.
- POOR... There's no caulking at all. The putty is in poor condition; noticeable drafts.

If you checked either "FAIR" or "POOR", then you probably need caulking.

DO THEY NEED WEATHERSTRIPPING?

A. YOUR WINDOWS

Look at the parts shown in the pictures of one or two of your typical windows. Check one:




- OK... Good, unbroken weatherstripping in all the indicated places; no drafts.
- FAIR... Weatherstripping damaged or missing in places; minor drafts.
- POOR... No weatherstripping at all; noticeable drafts.

If you checked either "FAIR" or "POOR", then your windows probably need weatherstripping.

Be careful, they may be in such poor condition that weatherstripping can't be installed. See p. 36.

B. YOUR DOORS

Look at the parts of your doors shown in the picture. Check one:



- OK... Good, unbroken weatherstripping in all the indicated places; no drafts.
- FAIR... Weatherstripping damaged or missing in places; minor drafts.
- POOR... No weatherstripping at all; noticeable drafts.

If you checked either "FAIR" or "POOR", then your doors probably need weatherstripping.

IF YOU CHECKED "OK" FOR ALL ITEMS, THEN YOU DON'T NEED CAULKING, PUTTY, OR WEATHERSTRIPPING. GO ON TO PAGE 10

IF YOU CHECKED "FAIR" OR "POOR" FOR ANY ITEM, COMPLETE THE NEXT PAGE:

IN THE BANK... OR UP THE CHIMNEY

Find Your Cost

1. Multiply the number of windows that need *caulking and putty* times the cost per window: _____ X \$0.90 =
number of windows
2. Multiply the number of windows that need *weatherstripping* times the cost per window: _____ X \$4.00 =
number of windows
3. Multiply the number of doors that need *caulking* times the cost per door: _____ X \$0.85 =
number of doors
4. Multiply the number of doors that need *weatherstripping* times the cost per door: _____ X \$6.75 = +
number of doors
5. Add up these numbers to get the total: _____ TOTAL COST \$

This cost is your estimated *do-it-yourself* cost. (It's easy to do yourself — look at page 34.) If you get a contractor to do it, your costs will be greater — at least 2

to 4 times as much. Prices vary from area to area and from job to job, so check with local contractors for an estimate (see page 66).

Find Your Savings Factor

Fill out only the lines that apply to your house:

A. YOUR WINDOWS

caulking and putty:

in FAIR condition: _____ X 0.3 =
number of windows

in POOR condition: _____ X 1.0 =
number of windows

weatherstripping:

in FAIR condition: _____ X 1.0 =
number of windows

in POOR condition: _____ X 8.4 =
number of windows

B. YOUR DOORS

caulking:

in FAIR condition: _____ X 0.3 =
number of doors

in POOR condition: _____ X 0.9 =
number of doors

weatherstripping:

in FAIR condition: _____ X 2.0 =
number of doors

in POOR condition: _____ X 16.8 = +
number of doors

C. Add up all the numbers you've written in the boxes to the right and write the total here: This number is your savings factor. _____ SAVINGS FACTOR


GO TO THE ENERGY CHECKLIST AT THE END OF THE BOOK

Write the *total cost* you found above in the orange box on line 1 of the Checklist.

Write the *savings factor* you found above in the grey box on line 1 of the Checklist.



INSTALL STORM WINDOWS



There are five kinds of storm windows:
PLASTIC (POLYETHYLENE SHEET). These come in rolls and cost only 65¢ each. You may have to put up replacements each year.

SINGLE PANE GLASS OR RIGID PLASTIC. These cost \$25.00 for glass and \$8.00 for acrylic panes. You put them up and take them down each year.

TRIPLE-TRACK GLASS (COMBINATION). These have screens and you can open and close them. They are for double hung or sliding windows (see the illustration). They cost about \$33.00 each installed. They are available for less without screens.

All five kinds are about equally effective. The more expensive ones are more durable, attractive, and convenient.

FILL OUT ONE OR MORE OF LINES A, B, AND C -- WHICHEVER ONES YOU'RE INTERESTED IN.

A. PUT ON PLASTIC STORM WINDOWS WITHOUT WEATHERSTRIPPING

Your cost: Count the number of windows you have and multiply times \$0.65:

_____ X \$0.65 = \$ _____
 number of windows total cost

Your Savings: In step A on page 8 you checked either "OK," "fair," or "poor" as the condition of the weatherstripping on your windows.

- If you checked "OK", circle this number 7.9
- If you checked "FAIR" circle this number 8.2
- If you checked "POOR" circle this number 10.8

Multiply the number you circled times the number of windows you have:

_____ X _____ = _____
 number you circled number of windows savings factor

C. PUT ON GLASS OR RIGID PLASTIC STORM WINDOWS (see Note)

Your Cost: Choose which kind of glass or rigid plastic storm windows you want, and multiply the number of windows you have times the cost given below:

| | |
|---|---------|
| Single-pane, rigid plastic | \$ 8.00 |
| Single-pane glass | \$25.00 |
| Triple-track glass (combination), double hung or slider | \$33.00 |

_____ X \$ _____ = \$ _____
 number of windows total cost

Your savings: Multiply your number of windows times 7.9:

_____ X 7.9 = _____
 number of windows savings factor

B. PUT ON PLASTIC STORM WINDOWS AT THE SAME TIME YOU WEATHERSTRIP (see Note)

Your cost: Multiply your number of windows times \$0.65:

_____ X \$0.65 = \$ _____
 number of windows total cost

Your savings: Multiply your number of windows times 7.9:

_____ X 7.9 = _____
 number of windows savings factor

SEE THE ENERGY CHECKLIST AT THE END OF THE BOOK

NOTE: These cost and savings factors are for storm windows only. They are in addition to the costs and savings for caulking and weatherstripping that you found on the last page.

If you filled out Part A here, fill out line 2a of the Checklist.

If you filled out Part B here, fill out line 2b of the Checklist.

If you filled out Part C here, fill out line 2c of the Checklist.

In each case, write the total cost into the orange box on that line and the savings factor into the grey box.



INSULATING YOUR ATTIC

Attic insulation is one of the most important energy-saving home improvements you can make. This section talks about insulating 3 kinds of attics.

IF YOUR HOME HAS ONE OF THE 3 KINDS SHOWN BELOW,

go straight to the page in this section that applies, work it through, and fill out one of the lines in the attic portion of the Energy Checklist at the end of the book.

Unfinished Attics

Unfinished Attic without a floor. Attic isn't used at all. (This includes Attics with roof trusses in them.)



Page 12

Unfinished Attic with a floor. (Attic can be used for storage.)



Page 14

Finished Attics

Finished Attic that can be used for living or storage.



Page 16

IF YOUR HOME IS A COMBINATION OF TWO KINDS OF ATTICS



(part of your attic may be finished and heated, part may be unused except as storage, as in these sample houses):

If this is your situation, treat each of your attics separately. Go to both of the pages in this section that apply, and fill out both lines in the attic portion of the Energy Checklist at the end of the book.




Flat roof? Mansard roof?

If your home has a flat roof, or a mansard roof, it will be harder and more expensive to insulate than the others — talk to a contractor — see Part 3 on how to pick a contractor.




INSULATE YOUR UNFINISHED ATTIC



This is the kind of attic you have if it has no floor — at most some loose boards to walk on, and you don't ever plan to finish it.

Should you insulate it ?

It depends on how much insulation is already there. To find out, go up into your attic and measure the depth of the insulation.



No

If you already have 8" or more, you may have enough, and you can skip the rest of this page. Check the table on page 44 to be sure.

Yes

If you have less than 9", you may need more, and you should keep going on this page. Start by writing down the approximate thickness you have:

_____ inches

You'll need this number in a minute.

Go on to the next column.

NOTE: If you can't get up into your attic to measure the depth of your insulation, you will need a contractor to do the work. Call him for a cost estimate. Ask the contractor to tell you how much insulation is already there. Then ask him for an estimate to add the R-value recommended on these pages.

LESS THAN NINE INCHES?

Go through the steps marked 1, 2 and 3, on this and the next page. Then read the directions in the lower right-hand corner of the next page to interpret the chart.

1. How much should you add

Given below are recommended amounts of insulation to add. For electrically heated homes, or extremely cold climates, these may still not be enough. For more precise advice on how much to add, see the table on page 44. If the table on page 44 recommends a greater thickness for your home than is given below, you can still use the tables on these pages to estimate insulation costs, but not fuel savings.

2. Should you do-it-yourself or hire a contractor?

You can do-it-yourself if there's a way for you to get up into the attic. If you aren't sure whether you want to do-it-yourself, look at page 47 to help you decide. Then, check "Do-it-yourself" or "Contractor" in one of the boxes below.

IF YOU HAVE THIS MUCH INSULATION

YOU NEED THIS MUCH MORE INSULATION •

NONE AT ALL

Do-it-yourself

Hire a contractor

R-38(10"-18")

R-38(10"-18")

UNDER 2 INCHES

Do-it-yourself

Hire a contractor

R-22(6"-10")

R-22(6"-10")

2 TO 4 INCHES

Do-it-yourself

Hire a contractor

R-11(3"-5")

R-11(3"-5")

4 TO 6 INCHES

Do-it-yourself

Hire a contractor

R-11(3"-5")

R-11(3"-5")

6 TO 8 INCHES

See page 44.


IN THE BANK ... OR UP THE CHIMNEY

3. How big is your attic?

To get your attic area, you don't even have to go up into the attic. Find out the area of the first floor of your home, not counting the garage, porch, and other unheated areas, and it will be the same as the area of your attic.


If it's a rectangle:

Measure its length and width in feet to the nearest foot and multiply them together.



If it's a combination:

Break it down into rectangles, find the area of each one, then add the areas to get the total.



length X width = area

_____ X _____ = _____

length X width = area

1 _____ X _____ = _____

2 _____ X _____ = _____

3 _____ X _____ = _____

total area _____

Check the number of square feet below that's closest to your total attic area

| | 600 Sq. Ft. | 900 Sq. Ft. | 1200 Sq. Ft. | 1600 Sq. Ft. | 2000 Sq. Ft. |
|----------------|----------------|----------------|-----------------|-----------------|-----------------|
| Cost | \$282 | \$423 | \$564 | \$752 | \$ 940 |
| Savings Factor | 246 | 369 | 492 | 656 | 820 |
| Cost | \$350 | \$525 | \$699 | \$932 | \$1166 |
| Savings Factor | 246 | 369 | 492 | 656 | 820 |

| | 600 Sq. Ft. | 900 Sq. Ft. | 1200 Sq. Ft. | 1600 Sq. Ft. | 2000 Sq. Ft. |
|----------------|----------------|----------------|-----------------|-----------------|-----------------|
| Cost | \$168 | \$252 | \$336 | \$448 | \$ 560 |
| Savings Factor | 56 | 86 | 115 | 154 | 206 |
| Cost | \$198 | \$297 | \$396 | \$529 | \$ 661 |
| Savings Factor | 56 | 86 | 115 | 154 | 206 |

| | 600 Sq. Ft. | 900 Sq. Ft. | 1200 Sq. Ft. | 1600 Sq. Ft. | 2000 Sq. Ft. |
|----------------|----------------|----------------|-----------------|-----------------|-----------------|
| Cost | \$ 78 | \$117 | \$156 | \$208 | \$ 260 |
| Savings Factor | 22 | 33 | 44 | 59 | 74 |
| Cost | \$ 86 | \$129 | \$172 | \$229 | \$ 286 |
| Savings Factor | 22 | 33 | 44 | 59 | 74 |

| | 600 Sq. Ft. | 900 Sq. Ft. | 1200 Sq. Ft. | 1600 Sq. Ft. | 2000 Sq. Ft. |
|----------------|----------------|----------------|-----------------|-----------------|-----------------|
| Cost | \$ 78 | \$117 | \$156 | \$208 | \$ 260 |
| Savings Factor | 12 | 18 | 24 | 32 | 40 |
| Cost | \$ 86 | \$129 | \$172 | \$229 | \$ 286 |
| Savings Factor | 12 | 18 | 24 | 32 | 40 |

Read across and down the chart from the boxes you've checked to find which square in the chart applies to you, like this:

| | 600 Sq. Ft. | 900 Sq. Ft. | 1200 Sq. Ft. |
|----------------|----------------|----------------|-----------------|
| Cost | \$282 | \$423 | \$564 |
| Savings Factor | 246 | 369 | 492 |

Copy these two numbers onto line 3 of the Energy Checklist at the end of the book. The orange number, your cost, goes in the orange box, the grey number, your savings factor, goes in the grey box.

*Different insulating materials require different thicknesses to achieve the same R-Value. See Page 46.

INSULATE YOUR UNFINISHED FLOORED ATTIC



This is your kind of attic if it's unfinished and unheated but has a floor.

Should you insulate it?

It depends on how much insulation is already there. To find out, go up there and check.

The insulation, if there is any, will be in either of two places:

Between the rafters. The first place to look is up between the rafters and in the walls at the ends of the attic.

Under the floor. If it's not up between the rafters, it might be down under the floorboards. If so, it won't be easy to see. You'll have to look around the edges of the attic, or through any large cracks in the floor. A flashlight may be handy, and also a ruler or stick that you can poke through the cracks with. If there's any soft, fluffy material in there, that's insulation.

Wherever the insulation is, if it's there at all, estimate how thick it is.

No

If it's thicker than 4 inches, it's not economical to add more — skip the rest of this page.

Yes

If it's 4 inches thick or less, you might need more — fill out these two pages to help you decide.

NOTE: If you can't tell whether you have enough insulation up there, get a contractor to find out for you. You're likely to be calling one anyway to do the work, and you'll want a cost estimate from him. Ask the contractor to tell you how much insulation is already there, and use the figures he gives you to complete this page and fill out the Energy Checklist.

Your cost and savings

To get a quick estimate of your costs and savings, follow steps 1 and 2 below and on the next page.

1. Which method?

There are two basic ways to insulate this type of attic.

a. Insulate the rafters, end walls, and collar beams.

This is the best way if you're doing it yourself, or if you think you might ever finish the attic.

b. The other way is to blow loose insulation in under the attic floor. This is a contractor job — you can't do it yourself. Also, don't do this if you think you might ever finish the attic. But if you're going to call a contractor, this is the cheapest and most effective way.

To see what's involved in a do-it-yourself job of insulating the rafters, end walls, and collar beams, look at page 51. What's involved when a contractor does the work is on page 50.

There are three different methods listed below. Pick the one that you think you might want to do. For the method you've chosen, check one of the three boxes — the *top* one if there's no existing insulation, the *middle* one if there's up to 2 inches of existing insulation, or the *bottom* one if there's from 2 to 4 inches of existing insulation.

Then go to step 2 on the next page.

DO-IT-YOURSELF: RAFTERS, END WALLS, COLLAR BEAMS

No existing insulation

0-2 inches

2-4 inches

CONTRACTOR INSTALLATION: RAFTERS, END WALLS, COLLAR BEAMS

No existing insulation

0-2 inches

2-4 inches

CONTRACTOR INSTALLATION: UNDER ATTIC FLOOR

No existing insulation

0-2 inches


2-4 inches

2. How big is your attic ?

Your unfinished, floored attic area will be either shaped like a rectangle or a combination of rectangles.


If it's a rectangle:

Measure its length and width in feet to the nearest foot and multiply them together.



If it's a combination:

Break it down into rectangles, find the area of each one, then add the areas to get the total.



length X width = area

_____ X _____ = _____

length X width = area

1 _____ X _____ = _____


2 _____ X _____ = _____

3 _____ X _____ = _____

total area _____

Check the number of square feet below that's closest to your attic floor area:

600 Sq. Ft. 900 Sq. Ft. 1200 Sq. Ft. 1600 Sq. Ft. 2000 Sq. Ft.



| | | | | | |
|----------------|-------|-------|-------|-------|--------|
| Cost | \$190 | \$274 | \$359 | \$487 | \$ 595 |
| Savings Factor | 83 | 121 | 165 | 224 | 284 |
| Cost | \$110 | \$187 | \$236 | \$366 | \$ 444 |
| Savings Factor | 27 | 41 | 57 | 74 | 92 |
| Cost | \$ 93 | \$164 | \$219 | \$310 | \$ 388 |
| Savings Factor | 11 | 18 | 25 | 34 | 43 |

How to read the chart

Read down and across from the boxes you've checked to find which square in the chart applies to you, like this:

| | | | | |
|-------------------------------------|----------------|-------------|-------------|--------------|
| | | 600 Sq. Ft. | 900 Sq. Ft. | 1200 Sq. Ft. |
| <input type="checkbox"/> | Cost | \$190 | \$274 | \$359 |
| <input type="checkbox"/> | Savings Factor | 83 | 121 | 165 |
| <input checked="" type="checkbox"/> | Cost | \$110 | \$187 | \$236 |
| <input type="checkbox"/> | Savings Factor | 27 | 41 | 57 |
| <input type="checkbox"/> | Cost | \$ 93 | \$164 | \$219 |
| <input type="checkbox"/> | Savings Factor | 11 | 18 | 25 |

| | | | | | |
|----------------|-------|-------|-------|-------|--------|
| Cost | \$346 | \$500 | \$657 | \$885 | \$1082 |
| Savings Factor | 83 | 121 | 165 | 224 | 284 |
| Cost | \$187 | \$314 | \$409 | \$644 | \$ 781 |
| Savings Factor | 27 | 41 | 55 | 72 | 88 |
| Cost | \$158 | \$285 | \$380 | \$549 | \$ 686 |
| Savings Factor | 9 | 15 | 22 | 30 | 38 |

| | | | | | |
|----------------|-------|-------|-------|-------|--------|
| Cost | \$296 | \$445 | \$593 | \$790 | \$ 988 |
| Savings Factor | 170 | 256 | 341 | 454 | 568 |
| Cost | \$246 | \$369 | \$492 | \$656 | \$ 820 |
| Savings Factor | 49 | 73 | 97 | 130 | 162 |
| Cost | \$210 | \$315 | \$420 | \$560 | \$ 700 |
| Savings Factor | 18 | 27 | 36 | 48 | 60 |

Copy these two numbers onto line 3 of the Energy Checklist at the back of the book. The orange number, your cost, goes in the orange box, the grey number, your savings factor, goes in the grey box.

INSULATE YOUR FINISHED ATTIC



This attic is a little harder to insulate than an unfinished attic because some parts are hard to reach. A contractor can do a complete job, but if you do-it-yourself, there will probably be parts that you can't reach.

Should you insulate it?

You need to find out if there's enough insulation there already.



Depending on what your house is like, you may or may not be able to measure your insulation by getting into the unfinished spaces in your attic through a door or hatchway.

1. **IF YOU CAN GET IN**, measure the depth of insulation. If you have 9 inches or more of insulation everywhere, you have enough and you can skip the rest of this page.
2. **IF YOU CAN'T GET INTO THE UNFINISHED PARTS OF YOUR ATTIC AT ALL**, have a contractor measure the insulation for you. Ask him how much is there, and use these figures to complete page 17 and fill out the Energy Checklist.

When you go to take a look at these places, make a note of the depth of insulation that's already there; you'll want this information in a minute.

1. Which method?

You may have already found out that you can't do-it-yourself because you can't get into the unfinished part of your attic. If you can get in, there are some good things you can do yourself to insulate it.

Depending on your particular attic you may be able to do one or more of these:

A. INSULATE ATTIC CEILING


You can insulate your attic ceiling if there's a door to the space above the finished area. You should consider insulating it if there's less than 9 inches already there.

B. INSULATE OUTER ATTIC RAFTERS

"Outer attic rafters" are the parts of the roof shown in the picture below:


You should consider insulating them if:

- there's no insulation between the rafters; and
- there's room for more insulation in the outer attic floor and in the "knee walls" that separate the finished and unfinished parts of the attic.



C. INSULATE OUTER ATTIC GABLES

"Outer attic gables" are the little triangular walls shown in the picture. You should insulate them if you insulate the outer attic rafters.



To get a better idea of what's involved in doing-it-yourself, read page 53. See page 44 to see how thick the insulation should be.

If you want to find costs and savings for a do-it-yourself insulation job, use the next page.

If you want to estimate costs and savings for contractor installation, go on to page 18.

Costs and savings for do-it-yourself insulation

1. How big are the areas you want to insulate?

Multiply the length times the width (in feet) of each area that you can insulate.

a. ATTIC CEILING

length X width = area

_____ X _____ = _____

b. OUTER ATTIC RAFTERS (there may be several areas you'll need to add together here)

length X width = area

_____ X _____ = _____

_____ X _____ = _____

_____ X _____ = _____


TOTAL

c. OUTER ATTIC GABLES (the area of these triangles is only half the length times the height.)

length X height ÷ 2 = area

_____ X _____ ÷ 2 = _____

Multiply by the number of gable ends to get the total area.



2. Your Savings Factor

For each part of your attic that you've measured, check below about how much insulation is already there. For each row you've checked, multiply your area times the number written to the right:

ATTIC CEILING

none _____ X .38 = _____

0-2 inches _____ X .09 = _____

2-4 inches _____ X .04 = _____

OUTER ATTIC RAFTERS (existing insulation will be in the floor and knee walls)

none _____ X .23 = _____

0-2 inches _____ X .09 = _____

2-4 inches _____ X .05 = _____

OUTER ATTIC GABLES (existing insulation will be in the floor and knee walls)

none _____ X .16 = _____

0-2 inches _____ X .06 = _____

2-4 inches _____ X .03 = _____

TOTAL

Add the results from each row you've filled out to get your Savings Factor.

3. Your Cost

ATTIC CEILING:

If there's no existing insulation:

_____ X \$0.37 = _____

If there's up to 2 inches of existing insulation:

_____ X \$0.24 = _____

If there's 2 to 4 inches of existing insulation:

_____ X \$0.13 = _____

OUTER ATTIC RAFTERS:

If there's up to 2 inches of existing insulation:

_____ X \$0.24 = _____

If there's from 2 to 4 inches of existing insulation:

_____ X \$0.13 = _____

OUTER ATTIC GABLES:

_____ X \$0.13 = _____

GO TO THE ENERGY CHECKLIST

at the end of the book. On line 3, "Insulate Your Attic", write your total cost in the orange box and your savings factor in the grey box.


Costs and savings for contractor installation

Finished attics differ a lot in how much they cost for a contractor to insulate them. Therefore, this page gives you only a rough estimate of how much it would cost you. If you want a better figure, get a contractor to give you an estimate. To see what's involved, see page 53. To see how much insulation should be installed, see page-44.

Your cost and savings

To get a quick estimate of your cost and savings, follow steps 1, 2, and 3 on this page.


1. How much insulation do you have already?



Go up and measure the depth of existing insulation, if you haven't already.

Check the box below that's closest to the depth you find. Usually, there's the same thickness in all parts of the attic. If there are different thicknesses, figure the average depth and check it below:

2. How big is your attic?



Measure the length and width of the *finished part* of your attic. Round them off to the nearest foot and multiply them together:

length X width = area

_____ X _____ = _____

Check the number of square feet below that's closest to your finished attic area.

| | | | | | | |
|----------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------|
| | 300 | 550 | 800 | 1100 | 1400 | |
| | <input type="checkbox"/> | |
| none | <input type="checkbox"/> | \$321 208 | \$469 316 | \$587 429 | \$641 572 | \$745 721 |
| under 2" | <input type="checkbox"/> | \$233 68 | \$343 97 | \$418 126 | \$469 167 | \$555 205 |
| 2"-4" | <input type="checkbox"/> | \$130 31 | \$214 44 | \$285 56 | \$322 74 | \$410 90 |


How to read the chart

Read down and across from the boxes you've checked to find which square in the chart applies to you, like this:

| | | |
|------|-------------------------------------|-------------------------------------|
| | 300 | 550 |
| | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| none | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| | \$321 208 | \$469 316 |
| | \$233 | \$343 |

Copy the orange number into the orange box on line 3 of the Energy Checklist, "Insulate Your Attic", at the end of the book. Copy the grey number into the grey box on the same line.

INSULATE YOUR WALLS



Should you insulate them?

It depends on two things: the size of your energy bills and what your walls are like. To find out if you should insulate them, answer these two questions:

1. How big are your energy bills?

If you have just heating — NO whole-house air conditioning, look up the Heating Factor for your city on page 28 or 29. The Heating Factor is a number that reflects the climate in your area, and how much you pay for fuel. Look at the Heating Factor for the type of heating you have — gas, oil, electricity, or coal. It's one of the numbers in the first four columns.

If your Heating Factor is 0.37 or more, keep on going. If it's less than 0.37, skip these two pages.

If you have heating AND whole-house air conditioning, look up both your Heating Factor and your Cooling Factor. They're listed on page 28 or 29. Look up the Heating Factor for your city for the type of heating you have — gas, oil, electricity, or coal. It's one of the numbers in the first four columns.

Then look up your Cooling Factor. It's the number in the fifth column.

Add together your Heating and Cooling Factors. If the sum is 0.37 or more, keep going. If it's less than 0.37, skip these two pages.

2. What are your walls like?

Most houses have *frame* walls. They have a wood structure — usually 2 by 4's — even though they may have brick or stone on the outside.

Some houses have brick or block *masonry* walls that form the structure of the house, without a wooden backup.

If you have *frame* walls, you should consider insulating them if there's no insulation at all in them already. A contractor can fill them with insulation and cut energy waste through them by 2/3.

You may already know whether or not your walls have insulation in them. If you don't know, here's how to find out: Take the cover off a light switch on an outside wall. (*Turn off the power first.*) Shine a flashlight into the space between the switchbox and the wall material and see if you can see any insulation.

If there's *no* insulation there now, you may need more, so fill out these two pages.

If there is some there already, you don't need more, so skip the rest of these pages.

If you have *masonry* walls, it may be worthwhile to insulate them if they're uninsulated now, even though it's more complicated than insulating frame walls; call a contractor to find out what's involved.

Condensation in Walls

None of the insulating materials contractors blow into frame walls serves as a barrier to moisture vapor; condensation in insulated walls may be a problem:

Look at the map on page 54. If you live in Zone I, and plan to insulate your walls, you need to take steps to ensure that too much moisture from the air in your house won't get into your walls. (In Zone II the problem is much smaller.) If it does, it is likely to condense there in the winter, and you will run two risks: first, that your insulation will become wet and won't insulate; and second, that enough moisture will collect to cause rot in the structure. Here's how to help avoid these dangers:

1. Seal any opening in the inside walls that could afford a path to moisture, especially around the window and door frames.
2. Paint interior walls with a low-permeability paint; this can be a high-gloss enamel or other finish — ask your paint dealer.

TURN TO THE NEXT PAGE FOR YOUR COST AND SAVINGS FACTORS

COSTS AND SAVINGS FOR WALL INSULATION

1. What kind of insulation?

Some kinds of wall insulation cost more than others, and some kinds work better than others. Generally, you get what you pay for – if you spend more, you get better insulation.

The least expensive is *mineral fiber* insulation. There are two kinds; rock wool and glass fiber. Either kind can be blown into the wall by means of a special machine.

A slightly more expensive but more effective insulation is *cellulosic fiber*. This is another loose insulation that's blown in like mineral fiber.

The most expensive and perhaps the most effective insulation is ureaformaldehyde-based foam (*not* urethane foam – urethane foam is not good in walls). Quality control problems with ureaformaldehyde-based foam require that you choose a qualified installer.

2. How big is your house?

Measure the *perimeter* – the total distance around the outside – of each story of your house that has frame walls.

Measure around the heated parts only. Measure in feet to the nearest ten feet.

Write the perimeters for each story over here:

If you have a finished, heated attic, measure the widths of the end walls of the attic *only*. Add up the width of all these walls and write the total to the right:

Add up all the numbers you've written and write the total number of feet of walls here:

First story perimeter _____ feet

Second story perimeter _____ feet

Third story perimeter _____ feet

Finished attic end walls + _____ feet

TOTAL feet

LINEAR FEET OF WALLS

Check the number of feet at the right that's closest to the number of feet of the walls you found above.

100 LF.

150 LF.

200 LF.

250 LF.

300 LF.

400 LF.

Mineral Fiber

Cellulosic Fiber

Ureaformaldehyde-Based Foam

| | 100 LF. | 150 LF. | 200 LF. | 250 LF. | 300 LF. | 400 LF. |
|--|---------|---------|---------|---------|---------|---------|
| Mineral Fiber Cost | \$397 | \$596 | \$ 794 | \$ 993 | \$1191 | \$1588 |
| Mineral Fiber Savings Factor | 100 | 155 | 205 | 255 | 310 | 410 |
| Cellulosic Fiber Cost | \$447 | \$671 | \$ 894 | \$1118 | \$1341 | \$1788 |
| Cellulosic Fiber Savings Factor | 110 | 170 | 225 | 280 | 335 | 450 |
| Ureaformaldehyde-Based Foam Cost | \$596 | \$894 | \$1192 | \$1490 | \$1788 | \$2384 |
| Ureaformaldehyde-Based Foam Savings Factor | 115 | 175 | 230 | 290 | 350 | 460 |

How to read the chart

The chart shows the cost and savings factors for different kinds of insulation applied to different sizes of houses.

To use the chart, look at the column under the box you've checked.

Look at the orange numbers in that column – the estimated costs for installing each type of material. See which you can afford; remember that if the cost is higher, your savings will also be higher.

When you've figured out which cost you're willing to pay, copy that cost into the orange box on line 5 of the Energy Checklist at the end of the book, and the savings factor into the grey box on the same line.

| | 100 LF. | 150 LF. | 200 LF. | 250 LF. |
|---------------------------------|---------|---------|---------|---------|
| Mineral Fiber Cost | \$397 | \$596 | \$ 794 | \$ 993 |
| Mineral Fiber Savings Factor | 100 | 155 | 205 | 255 |
| Cellulosic Fiber Cost | \$447 | \$671 | \$ 894 | \$1118 |
| Cellulosic Fiber Savings Factor | 110 | 170 | 225 | 280 |


INSULATING YOUR CRAWL SPACE WALLS, FLOOR, OR BASEMENT WALLS

If you live in a climate where your heating bill is big enough to be a worry, it's a good idea to insulate the underside of your house. It won't save much on air conditioning, but it will save on heating.

The underside of your house looks like one of these. Choose which of these pictures and descriptions looks like your house, and go to the page indicated.


A. A flat concrete slab sitting on the ground:

There's not much that you can easily do to insulate this type of foundation, and since it's hard to tell how much insulation is already there, it's hard to tell what your savings would be. Therefore, no cost and savings figures are given here for slab insulation. Go on to the next section on page 25.




B. A crawl space with walls around it:

If you have a crawl space that you can seal tightly in winter, you can insulate its walls and the ground around its outer edges. See page 22.




C. A floor over a garage, porch or open crawl space:

If there's an open space under your floor that you can't seal off tightly from the outside air, the place to insulate is in the floor, between the joists. See page 23.



D. Walls of a heated basement that stick out of the ground:

If you have a basement that is heated and used as a living area, it may be worth your while to insulate the basement walls down to a depth of two feet below the ground. See page 24.



E. A combination of the above types:


Your house may be part heated basement and part crawl space, or some other combination. To estimate your costs and savings, treat each of the parts separately and go to the pages dealing with each part. There are three separate lines on the Energy Checklist:


1 Insulate Crawl Space Walls

2 Insulate Floor

3 Insulate Basement Walls

You can fill out as many of these as apply to you, and see which are most important for you to do.





If your house (or part of it) sits on top of a crawl space that can be tightly sealed off from the outside air in the winter the cheapest and best place to insulate it is around the outside walls and on the adjacent ground inside the space:

Should you insulate it?

Answer these two questions:

1. Is there *no* insulation at all around the crawl space walls or under the floor?
2. Is your crawl space high enough to get in there to do the work?


If the answer to either of these questions is "No" don't insulate here. Skip the rest of this page. If your answer to both questions is "Yes", fill out this page.

Your cost and savings

To get a quick estimate of your cost and savings, follow steps 1, 2, and 3 on this page.

1. Measure your crawl space

Measure the distance around the outside of the heated part of your crawl space (don't include areas underneath porches, and other unheated areas).



Write that distance down here, in feet (you'll need it in a minute):

_____ feet

2. How much will it cost?

It makes a difference whether you want to do the work yourself or call a contractor. Doing it yourself is hard work, but you'll save a lot of money once you're through. If you're not sure which route you want to take — do-it-yourself or contractor — turn to page 56 to see what doing-it-yourself involves.

TO ESTIMATE THE COST IF YOU'RE DOING-IT-YOURSELF:

Multiply the total distance around your crawl space (the number you wrote in at the bottom of the last column) times \$0.80, the cost per running foot:

| |
|------------------------------|
| _____ FEET (fill in) |
| X \$ 0.80 PER RUNNING FOOT |
| \$ _____ DO-IT-YOURSELF COST |

TO ESTIMATE THE COST IF A CONTRACTOR'S DOING THE WORK:

Multiply the distance around your crawl space that you wrote in at the bottom of the last column by \$1.10, the cost per running foot.

| |
|-----------------------------|
| _____ FEET (fill in) |
| X \$ 1.10 PER RUNNING FOOT. |
| \$ _____ CONTRACTOR COST |


3. How much will you save?

To get your savings factor, multiply the distance around your crawl space times .54:

| |
|-----------------------------|
| _____ FEET (fill in) |
| X 0.54 RUNNING FOOT SAVINGS |
| _____ SAVINGS FACTOR |

Turn to the Energy Checklist at the end of the book. Go to line 4a, called "Insulate Crawl Space Walls". Write your cost in the orange box on that line, and write your savings factor in the grey box next to it.

INSULATE YOUR FLOOR



There are two cases where it's good to insulate your floor:

1. You have a crawl space that you can't seal off in winter — for example, your house stands on piers:



2. You have a garage, porch, or other cold unheated space with heated rooms above it:



Should you insulate it?

1. Is your floor uninsulated?
2. Is the floor accessible?
If it's above a crawl space, is the crawl space high enough for a person to work in it?

No

If your answer to any of these questions is "No" don't insulate the floor. Skip the rest of this page.

Yes

If your answer to both questions is "Yes", fill out this page.

Your cost and savings

To get a quick estimate of your cost and savings, follow steps 1, 2, and 3 on this page.

1. Which method?

Decide whether you want to do it yourself or call a contractor. Look at page 58 to help you decide.

2. How big is your floor?

Measure the area of the floor that you plan to insulate.

If It's a Rectangle:

Measure the length and width of the floor in feet and multiply them together.

$$\text{length} \times \text{width} = \text{area}$$

$$\underline{\hspace{2cm}} \times \underline{\hspace{2cm}} = \underline{\hspace{2cm}}$$

If It's a Combination of Rectangles:

Break it down into rectangles. For each rectangle, measure its length and its width and multiply them together. Add these numbers to get the total area.

$$\text{length} \times \text{width} = \text{area}$$

$$1 \underline{\hspace{2cm}} \times \underline{\hspace{2cm}} = \underline{\hspace{2cm}}$$

$$2 \underline{\hspace{2cm}} \times \underline{\hspace{2cm}} = \underline{\hspace{2cm}}$$

$$3 \underline{\hspace{2cm}} \times \underline{\hspace{2cm}} = \underline{\hspace{2cm}}$$

total area

3. How to read the chart


Check the number of square feet below that's closest to the floor area to be insulated that you found above.

Choose either the "do-it-yourself" or "contractor" column in the chart (see 1 above). Read down that column until you come to the row next to the number of square feet you've checked. Circle that box.

| SQUARE FEET | Do-it-Yourself Contractor | | Cost Savings Factor |
|-------------------------------|---------------------------|--------------|---------------------|
| | Do-it-Yourself | Contractor | |
| 200 <input type="checkbox"/> | \$ 24 58 | \$ 56 58 | |
| 400 <input type="checkbox"/> | \$ 48 116 | \$112 116 | |
| 600 <input type="checkbox"/> | \$ 76 173 | \$167 173 | |
| 900 <input type="checkbox"/> | \$106 260 | \$250 260 | |
| 1200 <input type="checkbox"/> | \$152 347 | \$334 347 | |
| 1600 <input type="checkbox"/> | \$189 462 | \$445 462 | |

Turn to the Energy Checklist at the end of the book. Go to line 4b, called "Insulate Floor". Write the orange number from the box you've circled into the orange box on that line, and the grey number into the grey box next to it.

INSULATE YOUR BASEMENT WALLS



If you have a basement that you use as a living or work space and that has air outlets, radiators, or baseboard units to heat it, you may find that it will pay to add a layer of insulation to the inside of the wall. The cost figures given below do not allow for the cost of refinishing as well as insulating.

Should you insulate them?

If your basement walls aren't insulated and if your basement's average height above ground is two feet or more, then it pays to insulate them in almost any climate if you do the work yourself. If your basement's average height above ground is less than two feet, then it pays to insulate these walls yourself if your Heating Factor is more than 0.7.

If you want to have a contractor do it, your Heating Factor should be 0.5 or more if your basement's average height above ground is two feet or more. If the height is less than two feet, you should not have the work done.

Your cost and savings


To get a quick estimate of your cost and savings, follow steps 1 and 2 on this page.

1. Make some measurements

Measure the length of each wall that sticks 2 or more feet above ground and add the lengths together.

Write the total number of feet here: _____ feet.
length of wall

Estimate to the nearest foot how far on the average these walls stick up above ground. For example, suppose your house is on a slope like this:



The average height above ground for this house is three feet. Write your average height above ground here: _____ feet.

2. How to use the chart

At the top of the chart, check the height of your basement walls above ground that's closest to the amount you wrote above in Step 1.

At the side of the chart, check either "do-it-yourself" or "contractor".

Read across the row you checked until you come to the column you checked. Circle the square where the row and the column meet.

AVERAGE HEIGHT ABOVE THE GROUND

0 Feet 2 Feet 4 Feet 6 Feet 8 Feet

| | | | | | | | |
|----------------|--------------------------|---------------|---------------|---------------|---------------|---------------|---------------------|
| Do-It-Yourself | <input type="checkbox"/> | \$1.84 0.2 | \$1.84 1.1 | \$1.84 2.0 | \$1.84 2.8 | \$1.84 3.4 | Cost Savings Factor |
| Contractor | <input type="checkbox"/> | \$4.84 0.2 | \$4.84 1.1 | \$4.84 2.0 | \$4.84 2.8 | \$4.84 3.4 | Cost Savings Factor |

Multiply the top number in the square you circled times the total length of the walls that you wrote down in Step 1. The result is your estimated total cost.

$$\text{\$ } \underline{\hspace{2cm}} \times \underline{\hspace{2cm}} = \text{\$ } \underline{\hspace{2cm}}$$

top number length of wall Cost

Multiply the bottom number in the square that you circled times the total length of the walls to get your savings factor.


$$\underline{\hspace{2cm}} \times \underline{\hspace{2cm}} = \underline{\hspace{2cm}}$$

bottom number length of wall savings factor


Turn to the Energy Checklist at the end of the book. Go to Line 4c, called "Insulate Basement Walls". Copy the total cost you've found into the orange box on that line and the savings factor into the grey box on the same line.

IN THE BANK ... OR UP THE CHIMNEY

THERMOSTAT, FURNACE AND AIR CONDITIONER



YOUR THERMOSTAT



The table below tells you what percent of your heating bill you'll save by turning down your thermostat. Look at the map above to see which zone you live in. Read the column in the table for that zone. Circle either the top or bottom number in that column - you'll need it after you figure out your heating bill.

Circle the top number if you want to see what you'll save with a 5-degree turn-down from your usual setting.

Circle the bottom number if you want to see what you'll save with an 8-degree turn-down from your usual setting.

| | ZONE 1 | ZONE 2 | ZONE 3 |
|--------------|--------|--------|--------|
| 5° turn-down | 14% | 17% | 25% |
| 8° turn-down | 19% | 24% | 35% |

Table 1

If you have whole-house air conditioning, you can save about 3 per cent of your air conditioning bill for each degree you turn up your thermostat. Usually, about a 4 degree turn-up will still be comfortable; above that the air conditioning system will have trouble keeping the house cool during the hot part of the day. Figure out how many degrees you can turn up your thermostat, then multiply the number of degrees by 3 to get your percent savings:

$$\frac{\text{degree turn-up}}{\text{degree turn-up}} \times 3 = \frac{\% \text{savings}}{\% \text{savings}}$$

YOUR HEATING BILL

The method for figuring out your heating bill depends on what kind of fuel you use. Pick the method below that applies to you:

NOTE: You may heat with two fuels; for example, most of your house may be heated with oil or gas, while some newer rooms may have electric heat. In this case, do this section once for each fuel, and add the results together.

A. Oil or coal heat

If you have an oil or coal furnace that heats your house but *not* your hot water, then all of your oil or coal bill goes to heating. Simply add up your fuel bills for last year. Write the total here:

\$ _____

If your furnace heats your hot water too, add up your fuel bills for last year and multiply the total by 8:

\$ _____ X .8 \$ _____
total fuel bill your heating bill

B. Gas or electric heat

If you have gas heat

OR

If you have electric heat **WITHOUT** whole-house electric air conditioning:

1. Write your *January* electric or gas bill (whichever kind of heat you have) on line 1 at the top of the next page.
2. Find the city nearest you from the table on page 27. There's a month written beside the name of that city. Write your electric or gas bill for that month on line 2.
3. Subtract line 2 from line 1 and write the difference on line 3.
4. Write the number from column A of the table for the city nearest you on line 4.

5. Multiply line 3 by line 4; write the result on line 5. That number's your estimated heating bill.

If you have electric heat AND whole-house air conditioning:

Follow steps 1-5 above, except for one thing: in step 4, use the number from column B of the table (instead of column A) for your city, and write it on line 4.

\$ _____ Line 1

SUBTRACT — \$ _____ Line 2

\$ _____ Line 3

MULTIPLY X _____ Line 4

YOUR HEAT BILL \$ _____ Line 5

YOUR AIR CONDITIONING BILL

If you have whole-house air conditioning, estimate how much it's costing you each year — Use this method: Look up the city nearest you in the table on the next page. If there's an asterisk (*) after the name of the city, your air conditioning savings will be insignificant; skip steps 1-5. If there's no asterisk, keep on going.

- Write your *July* electric bill on line 1 below.
- Find the city nearest you from the table on the next page. There's a month written beside the name of that city. Write your electric bill for that month on line 2.
- Subtract line 2 from line 1 and write the difference on line 3.
- If you have electric heat as well as air conditioning, write the number from column D of the table for the city nearest you on line 4. If you have gas, oil, or coal heat, write the number from column C of the table for the city nearest you on line 4.
- Multiply line 3 by line 4; write the result on line 5. That number's your estimated air conditioning bill.

\$ _____ Line 1

SUBTRACT — \$ _____ Line 2

\$ _____ Line 3

MULTIPLY X _____ Line 4

YOUR AIR CONDITIONING \$ _____ Line 5
BILL

YOUR DOLLAR SAVINGS

NOW THAT YOU'VE FOUND YOUR HEATING AND AIR CONDITIONING BILLS, YOU'RE READY TO FIND OUT HOW MUCH YOU CAN SAVE EACH YEAR ON THESE MEASURES.

1. YOUR THERMOSTAT

Multiply your heating bill by the percent you circled in table 1 on the previous page and divide by 100:

$$\begin{array}{r} \$ \text{ _____ } \times \text{ _____ } \div 100 = \text{ _____ } \\ \text{heating bill} \quad \quad \quad \% \text{ savings} \quad \quad \quad \text{dollar savings} \end{array}$$

If you have whole-house air conditioning, multiply your air conditioning bill by the percent you figured on the previous page and divide by 100:

$$\begin{array}{r} \$ \text{ _____ } \times \text{ _____ } \div 100 = \$ \text{ _____ } \\ \text{air cond. bill} \quad \quad \quad \% \text{ savings} \quad \quad \quad \text{dollar savings} \end{array}$$

Add up your thermostat savings for heating and air conditioning;

$$\begin{array}{r} \$ \text{ _____ } + \$ \text{ _____ } = \$ \text{ _____ } \\ \text{heat savings} \quad \quad \quad \text{air cond. savings} \quad \quad \quad \text{total savings} \end{array}$$

Write your total savings into the grey box on line 6 of the Energy Checklist at the end of the book.

2. YOUR OIL OR COAL FURNACE

If you have an oil or coal furnace that hasn't been serviced recently, multiply your heating bill by .1 if you have the furnace serviced.

$$\begin{array}{r} \$ \text{ _____ } \times 0.1 = \$ \text{ _____ } \\ \text{heating bill} \quad \quad \quad \text{dollar savings} \end{array}$$

Write the result in the grey box on line 7 of the Energy Checklist at the end of the book.*

3. YOUR GAS FURNACE

If you have a gas furnace that hasn't been serviced recently, you can save too — see page 63.

4. YOUR AIR CONDITIONER

If you have a central air conditioner that hasn't been serviced recently, multiply your air conditioning bill by 0.1 if you have the unit serviced.*

$$\begin{array}{r} \$ \text{ _____ } \times 0.1 = \$ \text{ _____ } \\ \text{air cond. bill} \quad \quad \quad \text{dollar savings} \end{array}$$

Write the result in the grey box on line 8 of the Energy Checklist at the end of the book.

* An estimate of cost has been entered for you on the Energy Checklist. For greater accuracy, use an estimate from your own heating or cooling specialist.

IN THE BANK... OR UP THE CHIMNEY

| | | Gas Electric Heat Alone | Electric Heat With Electric A/C | Electric A/C Alone | Electric A/C With Electric Heat | | | Gas Or Electric Heat Alone | Electric Heat With Electric A/C | Electric A/C Alone | Electric A/C With Electric Heat |
|----------------------|-------|----------------------------------|---|--------------------------|---|---------------------|-------|-------------------------------------|---|--------------------------|---|
| Location | Month | A | B | C | D | Location | Month | A | B | C | D |
| Alabama | | | | | | Nevada | | | | | |
| Montgomery | May | 4.2 | 5.2 | 7.3 | 7.3 | Elko | Sept. | 6.8 | 6.8 | 2.2 | . |
| Alaska | | | | | | Las Vegas | April | 4.7 | 4.9 | 4.1 | 5.7 |
| Anchorage | July | 7.8 | 7.8 | . | . | New Hampshire | | | | | |
| Arizona | | | | | | Concord | July | 5.5 | 5.9 | . | . |
| Flagstaff | July | 6.4 | 6.6 | . | . | New Jersey | | | | | |
| Phoenix | April | 4.4 | 5.1 | 5.1 | 6.3 | Atlantic City | Sept. | 5.4 | 5.7 | 5.1 | 8.2 |
| Arkansas | | | | | | New Mexico | | | | | |
| Little Rock | May | 4.3 | 4.7 | 5.6 | 5.9 | Raton | Sept. | 6.3 | 6.5 | 3.7 | . |
| California | | | | | | Silver City | Sept. | 4.7 | 5.3 | 5.7 | 5.9 |
| Bishop | Sept. | 5.2 | 7.5 | 3.5 | 5.1 | New York | | | | | |
| Eureka | July | 17.0 | 17.0 | . | . | New York City | Sept. | 5.7 | 5.6 | 5.9 | 8.0 |
| Los Angeles | Oct. | 6.0 | 7.1 | 10.5 | ... | Rochester | Sept. | 6.1 | 6.4 | 5.0 | . |
| Bakersfield | April | 4.8 | 5.3 | 4.9 | 8.0 | North Carolina | | | | | |
| San Francisco | Sept. | 6.7 | 7.0 | . | . | Raleigh | May | 4.9 | 5.2 | 5.3 | 6.9 |
| Colorado | | | | | | Wilmington | May | 4.3 | 4.8 | 7.0 | 5.9 |
| Alamosa | July | 6.0 | 6.0 | . | . | North Dakota | | | | | |
| Denver | Sept. | 6.2 | 6.3 | 3.5 | . | Bismarck | July | 5.3 | 5.5 | . | . |
| Connecticut | | | | | | Ohio | | | | | |
| New Haven | Sept. | 5.8 | 6.1 | 4.7 | .. | Youngstown | Sept. | 6.1 | 4.8 | 5.2 | . |
| Delaware | | | | | | Cincinnati | May | 5.4 | 5.4 | 4.0 | 10.0 |
| Dover | May | 5.7 | 5.8 | 3.8 | 9.6 | Oklahoma | | | | | |
| District of Columbia | | | | | | Oklahoma City | May | 4.5 | 4.8 | 4.9 | 6.1 |
| Washington | May | 5.3 | 5.5 | 4.3 | 6.7 | Oregon | | | | | |
| Florida | | | | | | Salem | July | 6.1 | 6.5 | . | . |
| Miami | Feb. | 1 | 1 | 9.6 | 9.6 | Medford | May | 7.4 | 6.3 | 3.3 | 11.3 |
| Tallahassee | April | 4.4 | 4.9 | 5.6 | 6.5 | Pennsylvania | | | | | |
| Georgia | | | | | | Philadelphia | May | 5.7 | 5.8 | 3.8 | 10.5 |
| Atlanta | May | 4.8 | 5.2 | 4.7 | 5.4 | Pittsburgh | Sept. | 5.9 | 6.2 | 5.4 | . |
| Savannah | April | 4.6 | 5.1 | 5.3 | 6.5 | Rhode Island | | | | | |
| Idaho | | | | | | Providence | Sept. | 5.9 | 6.1 | 4.7 | . |
| Boise | Sept. | 5.9 | 6.0 | 3.1 | .. | South Carolina | | | | | |
| Illinois | | | | | | Charleston | April | 4.7 | 4.9 | 4.9 | 6.2 |
| Chicago | Sept. | 5.5 | 5.8 | 5.2 | .. | Greenville-Spartan- | | | | | |
| Springfield | May | 5.4 | 5.5 | 3.6 | .. | burg | May | 4.6 | 5.0 | 4.8 | 5.4 |
| Cairo | May | 4.7 | 4.9 | 4.2 | 5.3 | South Dakota | | | | | |
| Indiana | | | | | | Rapid City | Sept. | 6.3 | 6.3 | 3.2 | . |
| Indianapolis | Sept. | 5.6 | 6.1 | 6.5 | .. | Tennessee | | | | | |
| Iowa | | | | | | Knoxville | May | 5.1 | 5.3 | 4.7 | 6.5 |
| Des Moines | Sept. | 5.1 | 5.4 | 11.8 | .. | Memphis | May | 4.3 | 4.8 | 5.2 | 5.6 |
| Dubuque | Sept. | 5.8 | 6.0 | 4.1 | . | Texas | | | | | |
| Kansas | | | | | | Austin | April | 4.1 | 4.5 | 5.5 | 7.0 |
| Wichita | May | 4.9 | 5.0 | 3.5 | 5.8 | Dallas | April | 4.6 | 5.0 | 5.0 | 7.7 |
| Goodland | Sept. | 5.7 | 5.8 | 3.4 | 9.8 | Houston | April | 4.0 | 4.8 | 5.9 | 7.0 |
| Kentucky | | | | | | Lubbock | May | 4.7 | 5.2 | 6.8 | 9.3 |
| Lexington | May | 5.6 | 5.6 | 4.0 | 11.4 | Utah | | | | | |
| Louisiana | | | | | | Salt Lake City | Sept. | 5.6 | 5.7 | 3.2 | 6.4 |
| Baton Rouge | April | 4.1 | 4.8 | 5.9 | 6.5 | Milford | Sept. | 5.5 | 5.7 | 2.7 | . |
| Shreveport | April | 4.6 | 5.0 | 4.9 | 7.7 | Vermont | | | | | |
| Maine | | | | | | Burlington | July | 5.6 | 5.9 | . | . |
| Portland | July | 5.7 | 5.7 | . | . | Virginia | | | | | |
| Maryland | | | | | | Richmond | May | 5.1 | 5.4 | 5.2 | 8.0 |
| Baltimore | May | 5.5 | 5.6 | 3.9 | 9.0 | Washington | | | | | |
| Massachusetts | | | | | | Olympia | July | 6.8 | 7.0 | . | . |
| Worcester | Sept. | 6.2 | 6.4 | 4.4 | . | Walla Walla | Sept. | 5.3 | 5.6 | 3.3 | 8.0 |
| Michigan | | | | | | West Virginia | | | | | |
| Lansing | July | 5.5 | 5.5 | . | . | Charleston | May | 5.7 | 5.7 | 4.2 | 9.6 |
| Minnesota | | | | | | Elkins | Sept. | 6.5 | 6.2 | 4.0 | . |
| Duluth | July | 6.0 | 6.1 | . | . | Wisconsin | | | | | |
| Minneapolis | May | 6.2 | 6.3 | 2.8 | . | Milwaukee | July | 5.9 | 6.2 | . | . |
| Mississippi | | | | | | Wyoming | | | | | |
| Jackson | April | 4.9 | 5.3 | 5.0 | 7.7 | Casper | Sept. | 6.7 | 6.8 | 2.8 | . |
| Missouri | | | | | | | | | | | |
| St. Louis | May | 4.8 | 4.8 | 3.4 | 5.9 | | | | | | |
| Springfield | May | 5.6 | 5.7 | 3.7 | 9.1 | | | | | | |
| Montana | | | | | | | | | | | |
| Helena | July | 5.8 | 6.0 | . | . | | | | | | |
| Nebraska | | | | | | | | | | | |
| Omaha | Sept. | 5.3 | 5.5 | 4.3 | . | | | | | | |
| Scottsbluff | Sept. | 6.1 | 6.2 | 3.1 | . | | | | | | |

* Air conditioning savings not significant.
 ** Your air conditioning bill is about 1/10 of your electric heating bill.
 *** Your air conditioning bill is about 1/4 of your electric heating bill.
 † Heating savings not significant.

YOUR HEATING AND COOLING FACTORS

You already have all the Savings Factors for the energy-saving home improvements you're considering. Combine them with your Heating Factor and (if you have whole-house air conditioning) your Cooling Factor, and you'll get dollar savings. There's *one* Heating Factor, and *one* Cooling Factor for your house, and they are

based on where you live, and how much you pay for the fuel you use for heating (and cooling). The Table on this page and the next has your Heating and Cooling Factors in it. There are two ways to use the Table: a quick approximate way, and a slower but more accurate way that uses your own fuel bill to get your own Factors.

1. The quick way

Find the row on the chart below that's for the city nearest you. Look at the first four columns in that row (A,B,C,D). Circle the number for your fuel. It's your Heating Factor.

If you have whole-house air conditioning, also circle the number in column E of the same row. That's your Cooling Factor.

Important: Check the fuel prices given in columns F through I. They were collected in mid-1977 and were

used to figure the Heating and Cooling Factors given in Columns A through E. Compare them with the price you pay for fuel (see "How Much Do You Really Pay for Fuel" below). If you find a significant difference, figure your Heating and Cooling Factors in "2. Using Your Own Bill" below.

Instructions for using these Factors are on the Energy Checklist at the end of the book.

2. Using your own bill

You can calculate your Heating Factor (and your Cooling Factor, if you have whole-house air conditioning), using the figures from your own utility bills.

it by the price you pay for electricity in cents per kilowatt hour, (see "How Much Do You Really Pay for Fuel"):

To figure your exact Heating Factor, find the Heating Multiplier for your city and your fuel (Columns J-M), and multiply it by the price you pay for heating fuel. Make sure you use the right units: gas - $\$/100$ Cu.Ft., oil - $\$/gal.$, electricity - $\$/Kwh$, coal - $\$/lb.$ (see "How Much Do You Really Pay for Fuel"):

$$\frac{\text{electricity price } (\$/Kwh)}{\text{your Cooling Multiplier}} = \text{Cooling Factor}$$

Enter on the Energy Checklist

$$\frac{\text{your fuel price}}{\text{your Heating Multiplier}} = \text{Heating Factor}$$

Enter on the Energy Checklist

To figure out your exact Cooling Factor, find the Cooling Multiplier in Column N for your city, and multiply

How Much Do You Really Pay for Fuel?


Your true cost for 100 cu. ft. of gas, a kilowatt of electricity, etc., is sometimes pretty well hidden in your bill. Call your utility company and ask them for the true cost (including all "fuel adjustment" factors and taxes) of the *last* unit of fuel that you buy every month. Use this cost to figure your Heating and Cooling Factor.

| | | Heating Factors | | | | Cooling Factor | Fuel costs | | | | Heating Multipliers | | | | Cooling Multiplier |
|------------|---------------|-----------------|-----|------|------|----------------|------------|-------|------|------|---------------------|-------|-------|-------|--------------------|
| | | Gas | Oil | Elec | Coal | | Gas | Oil | Elec | Coal | Gas | Oil | Elec | Coal | |
| | | A | B | C | D | | E | F | G | H | I | J | K | L | |
| ALABAMA | Montgomery | .13 | .28 | .34 | - | .13 | 12.00 | 38.88 | 1.50 | - | .0105 | .0071 | .2260 | .0987 | .0859 |
| ALASKA | Anchorage | .33 | .86 | 1.21 | - | .00 | 12.00 | 53.82 | 2.03 | - | .0275 | .0160 | .5956 | - | .0001 |
| ARIZONA | Flagstaff | .48 | .61 | .72 | - | .01 | 20.71 | 37.78 | 1.43 | - | .0233 | .0162 | .5040 | - | .0056 |
| | Phoenix | .07 | .23 | .23 | - | .20 | 8.20 | 37.78 | 1.43 | - | .0081 | .0062 | .1741 | - | .1430 |
| ARKANSAS | Little Rock | .10 | .40 | .45 | - | .11 | 8.40 | 39.22 | 1.40 | - | .0147 | .0102 | .3176 | - | .0769 |
| CALIFORNIA | Bishop | .29 | - | .59 | - | .67 | 17.69 | - | 1.69 | - | .0163 | - | .3515 | - | .0414 |
| | Eureka | .35 | - | .84 | - | .00 | 16.51 | - | 1.84 | - | .0212 | - | .4580 | - | .0001 |
| | Los Angeles | .09 | - | .28 | - | .06 | 12.17 | - | 1.69 | - | .0078 | - | .1682 | - | .0367 |
| | Bakersfield | .12 | - | .39 | - | .17 | 12.17 | - | 1.84 | - | .0097 | - | .2093 | - | .0941 |
| | San Francisco | .22 | - | .55 | - | .01 | 15.70 | - | 1.84 | - | .0137 | - | .2967 | - | .0059 |
| COLORADO | Alamosa | .28 | .58 | 1.18 | - | .01 | 10.15 | 38.26 | 1.96 | - | .0278 | .0153 | .6010 | - | .0023 |
| | Denver | .19 | .56 | .71 | - | .05 | 11.03 | 39.90 | 1.96 | - | .0168 | .0140 | .3640 | - | .0231 |

| | | Heating Factors | | | | Cooling Factor | Fuel costs | | | | Heating Multipliers | | | | Cooling Multiplier |
|----------------|------------------------|-----------------|-----|------|------|----------------|------------|-------|------|------|---------------------|-------|-------|-------|--------------------|
| | | Gas | Oil | Elec | Coal | | Gas | Oil | Elec | Coal | Gas | Oil | Elec | Coal | |
| | | A | B | C | D | | E | F | G | H | I | J | K | L | |
| CONNECTICUT | New Haven | .58 | .67 | 1.77 | - | .13 | 30.09 | 46.87 | 4.28 | - | .0192 | .0143 | .4155 | - | .0312 |
| DELAWARE | Dover | .28 | .84 | .85 | - | .07 | 15.30 | 45.55 | 1.80 | - | .0188 | .0140 | .4054 | 1.770 | .0447 |
| D.C. | Washington | .41 | .55 | 1.12 | .69 | .18 | 25.26 | 45.92 | 3.22 | 4.55 | .0161 | .0120 | .3473 | 1.517 | .0559 |
| FLORIDA | Miami | .10 | .04 | .07 | - | .49 | 10.00 | 52.96 | 3.07 | - | .0010 | .0007 | .0211 | - | .1589 |
| | Tallahassee | .09 | .25 | .37 | - | .23 | 13.90 | 48.78 | 2.49 | - | .0068 | .0051 | .1465 | - | .0941 |
| GEORGIA | Atlanta | .14 | .40 | - | .49 | - | 12.50 | 43.50 | - | 4.63 | .0113 | .0092 | .2435 | 1.063 | .0812 |
| | Savannah | .10 | .23 | - | - | - | 12.50 | 37.81 | - | - | .0083 | .0062 | .1794 | - | .0892 |
| IDAHO | Boise | .39 | .52 | .36 | - | .03 | 23.62 | 42.06 | 1.01 | - | .0166 | .0124 | .3582 | - | .0330 |
| ILLINOIS | Chicago | .36 | .60 | .54 | .54 | .05 | 19.25 | 44.19 | 1.38 | 3.12 | .0182 | .0136 | .3944 | 1.722 | .0373 |
| | Springfield | .26 | .44 | .77 | .33 | .12 | 19.16 | 42.79 | 2.59 | 2.52 | .0138 | .0103 | .2976 | 1.300 | .0453 |
| | Cairo | .22 | .40 | .82 | .24 | .20 | 17.85 | 42.79 | 3.04 | 2.00 | .0125 | .0093 | .2692 | 1.176 | .0663 |
| INDIANA | Indianapolis | .30 | .50 | .48 | .50 | .05 | 18.27 | 41.60 | 1.33 | 3.25 | .0168 | .0124 | .3514 | 1.534 | .0398 |
| IOWA | Des Moines | .28 | .58 | - | - | - | 14.92 | 41.32 | - | - | .0188 | .0140 | .4062 | - | .0406 |
| | Dubuque | .24 | .65 | - | - | - | 11.24 | 41.32 | - | - | .0210 | .0151 | .4548 | - | .0257 |
| KANSAS | Wichita | .15 | .41 | .49 | - | .09 | 9.70 | 36.42 | 1.49 | - | .0151 | .0112 | .3255 | - | .0603 |
| | Goodland | .14 | .48 | .38 | - | .03 | 8.18 | 36.42 | 1.00 | - | .0175 | .0133 | .3780 | - | .0337 |
| KENTUCKY | Lexington | .26 | .50 | .63 | - | .08 | 17.26 | 43.75 | 1.90 | - | .0153 | .0114 | .3300 | 1.441 | .0423 |
| LOUISIANA | Baton Rouge | .06 | - | .28 | - | .19 | 7.10 | - | 1.82 | - | .0071 | - | .1539 | - | .1046 |
| | Shreveport | .08 | - | .38 | - | .16 | 7.50 | - | 1.77 | - | .0100 | - | .2155 | - | .0914 |
| MAINE | Portland | .65 | .72 | 1.04 | - | .03 | 26.00 | 44.70 | 2.25 | - | .0231 | .0161 | .4631 | - | .0138 |
| MARYLAND | Baltimore | .46 | .58 | .98 | .51 | .42 | 27.12 | 46.74 | 2.71 | 3.25 | .0167 | .0124 | .3603 | 1.573 | .0461 |
| MASSACHUSETTS | Worcester | .73 | .77 | 1.09 | - | .06 | 32.14 | 45.78 | 3.02 | - | .0227 | .0169 | .4911 | - | .0185 |
| MICHIGAN | Lansing | .56 | .65 | 1.10 | .70 | .05 | 28.47 | 43.86 | 2.60 | 3.75 | .0197 | .0147 | .4260 | 1.860 | .0200 |
| MINNESOTA | Duluth | .60 | .76 | - | - | - | 23.80 | 43.09 | - | - | .0254 | .0177 | .5482 | - | .0073 |
| | Minneapolis | .33 | .72 | - | - | - | 15.59 | 46.18 | - | - | .0213 | .0156 | .4595 | - | .0288 |
| MISSISSIPPI | Jackson | .11 | - | .57 | - | .24 | 10.50 | - | 2.58 | - | .0102 | - | .2209 | .0904 | .0918 |
| MISSOURI | St. Louis | .21 | .76 | .39 | - | .06 | 14.12 | 45.63 | 1.18 | - | .0153 | .0167 | .3306 | - | .0540 |
| | Springfield | .17 | .49 | .45 | - | .07 | 10.50 | 41.37 | 1.30 | - | .0160 | .0119 | .3453 | - | .0578 |
| MONTANA | Helena | .26 | - | .69 | - | .01 | 12.45 | - | 1.55 | - | .0206 | - | .4456 | - | .0093 |
| NEBRASKA | Omaha | .33 | .58 | .73 | - | .08 | 17.65 | 40.90 | 1.80 | - | .0189 | .0141 | .4077 | - | .0446 |
| | Scottsbluff | .25 | .52 | .68 | - | .04 | 14.00 | 41.35 | 1.87 | - | .0169 | .0126 | .3658 | - | .0232 |
| NEVADA | Elko | .33 | .63 | .71 | - | .02 | 17.75 | 44.34 | 1.75 | - | .0188 | .0141 | .4075 | - | .0128 |
| | Las Vegas | .14 | .34 | .46 | - | .23 | 13.90 | 44.34 | 2.08 | - | .0103 | .0077 | .2228 | - | .1114 |
| NEW HAMPSHIRE | Concord | .70 | .73 | 1.05 | - | .04 | 33.29 | 46.38 | 2.30 | - | .0211 | .0157 | .4552 | - | .0170 |
| NEW JERSEY | Atlantic City | .62 | .62 | 1.20 | .56 | .09 | 33.84 | 45.32 | 3.02 | 3.25 | .0183 | .0137 | .3957 | 1.728 | .0312 |
| NEW MEXICO | Raton | .17 | - | 1.03 | - | .09 | 8.60 | - | 2.35 | - | .0203 | - | .4388 | - | .0391 |
| | Silver City | .09 | - | .69 | - | .10 | 7.05 | - | 2.63 | - | .0121 | - | .2611 | - | .0391 |
| NEW YORK | New York City | .65 | .68 | 1.72 | .76 | .19 | 35.28 | 49.46 | 4.34 | 4.40 | .0183 | .0137 | .3959 | 1.729 | .0434 |
| | Rochester | .53 | .76 | 1.36 | .82 | .07 | 24.05 | 46.53 | 2.85 | 3.95 | .0220 | .0164 | .4755 | 2.076 | .0259 |
| NORTH CAROLINA | Raleigh | .30 | .52 | .95 | .64 | .12 | 19.41 | 45.10 | 2.35 | 4.40 | .0155 | .0115 | .3347 | 1.462 | .0500 |
| | Wilmington | .17 | .35 | .54 | .70 | .17 | 16.46 | 43.43 | 2.35 | 4.76 | .0107 | .0080 | .2315 | 1.011 | .0730 |
| NORTH DAKOTA | Bismarck | .59 | - | 1.21 | - | .04 | 26.50 | - | 2.49 | - | .0224 | - | .4852 | - | .0171 |
| OHIO | Youngstown | .19 | .69 | 1.18 | .36 | .05 | 8.88 | 43.95 | 2.62 | 1.80 | .0209 | .0156 | .4522 | 1.974 | .0204 |
| | Cincinnati | .18 | .47 | .52 | .53 | .07 | 12.79 | 43.95 | 1.68 | 3.90 | .0144 | .0107 | .3107 | 1.357 | .0439 |
| OKLAHOMA | Oklahoma City | .21 | - | .74 | - | .20 | 17.45 | - | 2.80 | - | .0121 | - | .2625 | - | .0705 |
| OREGON | Salem | .57 | .72 | 1.02 | - | .02 | 26.41 | 44.20 | 2.17 | - | .0217 | .0162 | .4690 | - | .0101 |
| | Medford | .58 | .75 | 1.05 | - | .06 | 25.11 | 44.20 | 2.13 | - | .0229 | .0170 | .4440 | - | .0283 |
| PENNSYLVANIA | Philadelphia | .49 | .63 | 1.08 | .61 | .12 | 26.87 | 46.10 | 2.73 | 3.55 | .0183 | .0137 | .3959 | 1.729 | .0448 |
| | Pittsburgh | .35 | .60 | 1.04 | .44 | .03 | 19.25 | 44.75 | 2.68 | 2.60 | .0180 | .0134 | .3890 | 1.698 | .0120 |
| RHODE ISLAND | Providence | .45 | .68 | 1.37 | - | .09 | 23.03 | 47.20 | 3.26 | - | .0194 | .0145 | .4195 | - | .0285 |
| SOUTH CAROLINA | Charleston | .19 | .27 | .44 | - | .20 | 21.58 | 42.17 | 2.34 | - | .0087 | .0065 | .1888 | - | .0669 |
| | Greenville-Spartanburg | .18 | .36 | .56 | - | .13 | 16.23 | 42.17 | 2.28 | - | .0113 | .0085 | .2450 | - | .0561 |
| SOUTH DAKOTA | Rapid City | .22 | .58 | .79 | - | .04 | 11.88 | 41.76 | 1.95 | - | .0186 | .0139 | .4027 | - | .0209 |
| TENNESSEE | Knoxville | .19 | .44 | .61 | .31 | .12 | 14.20 | 44.20 | 2.13 | 2.50 | .0133 | .0099 | .2873 | 1.255 | .0557 |
| | Memphis | .11 | .38 | .55 | .31 | .17 | 9.25 | 42.36 | 2.13 | 2.80 | .0119 | .0089 | .2569 | 1.122 | .0780 |
| TEXAS | Austin | .07 | - | .51 | - | .32 | 8.60 | - | 3.00 | - | .0078 | - | .1688 | - | .1071 |
| | Dallas | .07 | - | .29 | - | .16 | 7.90 | - | 1.49 | - | .0090 | - | .1943 | - | .1049 |
| | Houston | .05 | - | .21 | - | .16 | 9.00 | - | 1.62 | - | .0061 | - | .1319 | - | .1000 |
| | Lubbock | .15 | - | .53 | - | .13 | 12.46 | - | 2.11 | - | .0117 | - | .2529 | - | .0617 |
| UTAH | Salt Lake City | .23 | .58 | .87 | - | .08 | 11.56 | 39.60 | 2.05 | - | .0197 | .0147 | .4264 | - | .0371 |
| | Midford | .28 | - | .90 | - | .05 | 13.39 | - | 1.97 | - | .0212 | - | .4578 | - | .0267 |
| VERMONT | Burlington | .63 | .84 | 1.20 | - | .04 | 27.81 | 47.58 | 2.36 | - | .0222 | .0176 | .5098 | - | .0178 |
| VIRGINIA | Richmond | .24 | .50 | .72 | .61 | .12 | 16.64 | 45.58 | 2.25 | 4.40 | .0147 | .0110 | .3178 | 1.388 | .0537 |
| WASHINGTON | Olympia | .75 | .80 | .79 | - | .01 | 32.19 | 44.72 | 1.52 | - | .0239 | .0178 | .5165 | - | .0035 |
| | Walla Walla | .21 | .46 | .45 | - | .05 | 15.40 | 44.72 | 1.51 | - | .0137 | .0102 | .2963 | - | .0357 |
| WEST VIRGINIA | Charleston | .32 | .50 | .79 | .13 | .10 | 21.92 | 45.73 | 2.50 | .96 | .0146 | .0109 | .3154 | 1.377 | .0388 |
| | Elkins | .44 | .63 | 1.10 | .78 | .06 | 23.82 | 45.73 | 2.76 | 1.05 | .0185 | .0138 | .3999 | 1.746 | .0208 |
| WISCONSIN | Milwaukee | .44 | .75 | - | .79 | - | 20.29 | 46.10 | - | 3.85 | .0218 | .0162 | .4707 | 2.055 | .0216 |
| WYOMING | Casper | .32 | - | .81 | - | .03 | 16.90 | - | 2.00 | - | .0188 | - | .4062 | - | .0151 |

PART 3: HOW TO DO IT

This part is divided into sections, each one treating an energy-saving step—13 in all. A section works like this:



First, how hard is it?



Should you do it yourself? – a quick rundown to help you decide whether you can handle it yourself or if you need the services of a professional.

Then, how to get it done



If you're doing it yourself:
 Tools you'll need
 Safety items to include
 What kind of materials


How much material
 Getting it done, step by step

OR if you want to hire a contractor to do it, how to make sure he does the job right.

What kind of materials
 How much material
 R-Value

Signing a contract
 What to check

Last, more information you may need



Some general information that could be helpful:

Buying Insulating Materials
 Choosing a Contractor
 Getting Financing

TABLE OF CONTENTS

WINDOWS AND DOORS

| | |
|---|----|
| Caulk the Openings in Your Home | 34 |
| Weatherstrip Your Windows | 36 |
| Weatherstrip Your Doors | 38 |
| Install Plastic Storm Windows | 40 |
| Install Single Pane Storm Windows | 41 |
| Install Combination Storm Windows | 42 |
| Install Combination Storm Doors | 43 |

INSULATION

| | |
|--|----|
| Buying Insulation | 44 |
| Insulate Your Unfinished Attic | 47 |
| Insulate Your Unfinished Floored Attic | 50 |

| | |
|---|----|
| Insulate Your Finished Attic | 53 |
| Do You Need a Vapor Barrier or More Ventilation in Your Attic | 54 |
| Insulate Your Wood Frame Walls | 55 |
| Insulate Your Crawl Space Walls | 56 |
| Insulate Your Floors | 58 |
| Insulate Your Basement Walls | 60 |
| SAVING ENERGY WITH YOUR HEATING, AIR CONDITIONING, AND WATER | |
| HEATING | 62 |
| CHOOSING A CONTRACTOR | 66 |
| GETTING FINANCING | 66 |

CAULK THE OPENINGS IN YOUR HOME




AN EASY DO-IT-YOURSELF PROJECT

Caulking should be applied wherever two different materials or parts of the house meet. It takes no specialized skill to apply and a minimum of tools.

Tools

1. Ladder
2. Caulking gun
3. Caulking cartridges
4. Oakum, glass fiber strips, caulking cotton, or sponge rubber
5. Putty knife or large screwdriver



Where a house needs to be caulked

1. Between window drip caps (tops of windows) and siding.
2. Between door drip caps and siding.
3. At joints between window frames and siding.
4. At joints between door frames and siding.
5. Between window sills and siding.
6. At corners formed by siding.
7. At sills where wood structure meets the foundation.
8. Outside water faucets, or other special breaks in the outside house surface.
9. Where pipes and wires penetrate the ceiling below an unheated attic.
10. Between porches and main body of the house.
11. Where chimney or masonry meets siding.
12. Where storm windows meet the window frame, except for drain holes at window sill.
13. And if you have a heated attic; where the wall meets the eave at the gable ends.

Safety

You'll need to use a ladder to reach some of the areas which need to be caulked. Be sure you use it safely.

Level and block the ladder in place. Have a helper hold it if possible.

Don't try to reach that extra little bit — get down and move the ladder.

Carry your caulking gun with a sling so that you can use both hands climbing the ladder.

Materials

What you'll need

Caulking compound is available in these basic types:

1. Oil or resin base caulk; readily available and will bond to most surfaces — wood, masonry and metal; not very durable but lowest in first cost for this type of application.
2. Latex, butyl or polyvinyl based caulk; all readily available and will bond to most surfaces, more durable, but more expensive than oil or resin based caulk.
3. Elastomeric caulks; most durable and most expensive; includes silicones, polysulfides and polyurethanes; the instructions provided on the labels should be followed.
4. Filler; includes oakum, caulking cotton, sponge rubber, and glass fiber types; used to fill extra wide cracks or as a backup for elastomeric caulks.

CAUTION: Lead base caulk is not recommended because it is toxic. Many states prohibit its use.

How much

Estimating the number of cartridges of caulking compound required is difficult since the number needed will vary greatly with the size of cracks to be filled. Rough estimates are:

1/2 cartridge per window or door


4 cartridges for the foundation sill

2 cartridges for a two story chimney


If possible, it's best to start the job with a half-dozen cartridges and then purchase more as the job continues and you need them.

IN THE BANK... OR UP THE CHIMNEY


Installation



1 Before applying caulking compound, clean area of paint build-up, dirt, or deteriorated caulk with solvent and putty knife or large screwdriver.




2 Drawing a good bead of caulk will take a little practice. First attempts may be a bit messy. Make sure the bead overlaps both sides for a tight seal.




3 A wide bead may be necessary to make sure caulk adheres to both sides.



4 Fill extra wide cracks like those at the sills (where the house meets the foundation) with oakum, glass fiber insulation strips, etc.)




5 In places where you can't quite fill the gaps, finish the job with caulk.



6 Caulking compound also comes in rope form. Unwind it and force it into cracks with your fingers. You can fill extra long cracks easily this way.

WEATHERSTRIP YOUR WINDOWS




AN EASY DO-IT-YOURSELF PROJECT

Weatherstripping windows can be accomplished by even the inexperienced handyman. A minimum of tools and skills is required.

But before starting, make sure that both the moving parts of your windows (the sash), and the channels that the sash slide in aren't so rotted that they won't hold the small nails used for weatherstripping. If they are badly rotted, don't weatherstrip, but consider replacing the entire window unit first. Call your lumberyard or window dealer for an evaluation or cost estimate.

Tools

1. Hammer and nails
2. Screwdriver
3. Tin snips
4. Tape measure



Safety

Upper story windows may be a problem. You should be able to do all work from inside, but avoid awkward leaning out of windows when tacking weatherstripping into place. If you find you need to use a ladder observe the precautions on page 34.



Materials

What you'll need




Thin spring metal

Installed in the channel of window so it is virtually invisible. Somewhat difficult to install. Very durable.



Rolled vinyl

With or without metal backing. Visible when installed. Easy to install. Durable.



Foam rubber with adhesive backing

Easy to install. Breaks down and wears rather quickly. Not as effective a sealer as metal strips or rolled vinyl.

Never use where friction occurs.

How much

Weatherstripping is purchased either by the running foot or in kit form for each window. In either case you'll have to make a list of your windows, and measure them to find the total length of weatherstripping you'll need. Measure the total distance around the edges of the moving parts of each window type you have, and complete the list below:


| Type | Size | Quantity | X length req'd | = Total |
|--|------|----------|----------------|---------|
| 1. Double-hung  | 1 | () | X () | = |
| | 2 | () | X () | = |
| | 3 | () | X () | = |
| 2. Casement  | 1 | () | X () | = |
| | 2 | () | X () | = |
| | 3 | () | X () | = |
| 3. Tilting  | 1 | () | X () | = |
| | 2 | () | X () | = |
| | 3 | () | X () | = |
| 4. Sliding pane  | 1 | () | X () | = |
| | 2 | () | X () | = |
| | 3 | () | X () | = |

Total length of weatherstripping required _____

Be sure to allow for waste. If you buy in kit form, be sure the kit is intended for your window type and size.


Installation

Thin spring metal




1

Install by moving sash to the open position and sliding strip in between the sash and the channel. Tack in place into the casing. Do not cover the pulleys in the upper channels.



2


Install strips the full width of the sash on the bottom of the lower sash bottom rail and the top of the upper sash top rail.



3


Then attach a strip the full width of the window to the upper sash bottom rail. Countersink the nails slightly so they won't catch on the lower sash top rail.

Rolled vinyl



1


Nail on vinyl strips on double-hung windows as shown. A sliding window is much the same and can be treated as a double-hung window turned on its side. Casement and



2

tilting windows should be weatherstripped with the vinyl nailed to the window casing so that, as the window shuts, it compresses the roll.

Adhesive-backed foam strip



Install adhesive backed foam, on all types of windows, only where there is no friction. On double-hung windows, this is only on the bottom (as shown) and top rails. Other types of windows can use foam strips in many more places.

WEATHERSTRIP YOUR DOORS



AN EASY DO-IT-YOURSELF PROJECT

You can weatherstrip your doors even if you're not an experienced handyman. There are several types of weatherstripping for doors, each with its own level of effectiveness, durability and degree of installation difficulty. Select among the options given the one you feel is best for you. The installations are the same for the two sides and top of a door, with a different, more durable one for the threshold.

The Alternative Methods and Materials

1. Adhesive backed foam:


Tools

Knife or shears,
Tape measure



Evaluation — extremely easy to install, invisible when installed, not very durable, more effective on doors than windows.


Installation — stick foam to inside face of jamb.



2. Rolled vinyl with aluminum channel backing:

Tools

Hammer, nails,
Tin snips
Tape measure



Evaluation — easy to install, visible when installed, durable.


Installation — nail strip snugly against door on the casing



3. Foam rubber with wood backing:


Tools

Hammer, nails,
Hand saw,
Tape measure



Evaluation — easy to install, visible when installed, not very durable.

Installation — nail strip snugly against the closed door. Space nails 8 to 12 inches apart.



4. Spring metal:


Tools

Tin snips
Hammer, nails,
Tape measure



Evaluation — easy to install, invisible when installed, extremely durable.

Installation — cut to length and tack in place. Lift outer edge of strip with screwdriver after tacking, for better seal.



Note: These methods are harder than 1 through 4.

5. Interlocking metal channels:

Tools

Hack saw,
Hammer, nails,
Tape measure

Evaluation — difficult to install (alignment is critical), visible when installed, durable but subject to damage, because they're exposed, excellent seal.

Installation — cut and fit strips to head of door first: male strip on door, female on head; then hinge side of door: male strip on jamb, female on door; finally lock side on door, female on jamb.





8. Door Shoes:

Tools

Screwdriver,
Hack saw,
Plane,
Tape measure

Evaluation — useful with wooden threshold that is not worn, very durable, difficult to install (must remove door).

Installation — remove door and trim required amount off bottom. Cut to door width. Install by sliding vinyl out and fasten with screws.



6. Fitted interlocking metal channels: (J-Strips)

TOP VIEW



Evaluation — very difficult to install, exceptionally good weather seal, invisible when installed, not exposed to possible damage.

Installation — should be installed by a carpenter. Not appropriate for do-it-yourself installation unless done by an accomplished handyman.


9. Vinyl bulb threshold:

Tools

Screwdriver,
Hack saw,
Plane,
Tape measure

Evaluation — useful where there is no threshold or wooden one is worn out, difficult to install, vinyl will wear but replacements are available.

Installation — remove door and trim required amount off bottom. Bottom should have about 1/8" bevel to seal against vinyl. Be sure bevel is cut in right direction for opening.



7. Sweeps:


Tools

Screwdriver,
Hack saw,
Tape measure

Evaluation — useful for flat thresholds, may drag on carpet or rug.


Models that flip up when the door is opened are available (not illustrated).

Installation — cut sweep to fit 1/16 inch in from the edges of the door. Some sweeps are installed on the inside and some outside. Check instructions for your particular type.



10. Interlocking threshold:

INSIDE ←




Evaluation — very difficult to install, exceptionally good weather seal.

Installation — should be installed by a skilled carpenter.

INSTALL PLASTIC STORM WINDOWS


AN EASY DO-IT-YOURSELF PROJECT



Tack the plastic sheets over the outside of your windows or tape sheets over the inside instead of installing permanent type storm windows.

Tools & Materials

1. Six-mil thick polyethylene plastic in rolls or kits
 2. Shears to cut and trim plastic
 3. 2" wide masking tape
- OR
3. Hammer and tacks
 4. 1/4" X 1-1/4" wood slats



therefore how many rolls or the kit size you need to buy.

Attach to the inside or outside of the frame so that the plastic will block airflow that leaks around the moveable parts of the window. If you attach the plastic to the outside use the slats and tacks. If you attach it to the inside masking tape will work.


Inside installation is easier and will provide greater protection to the plastic. Outside installation is more difficult, especially on a 2 story house, and the plastic is more likely to be damaged by the elements.

Installation

Measure the width of your larger windows to determine the width of the plastic rolls to buy. Measure the length of your windows to see how many linear feet and

Be sure to install tightly and securely, and remove all excess — besides looking better, this will make the plastic less susceptible to deterioration during the course of the winter.

INSTALL SINGLE PANE STORM WINDOWS



CONTRACTOR ASSEMBLY DO-IT-YOURSELF INSTALLATION

Rigid Plastic: These are available in do-it-yourself kits.

Glass: Storm window suppliers will build single pane glass storm windows to your measurements that you then install yourself. Another method is to make your own with do-it-yourself materials available at some hardware stores.

Installation

Rigid Plastic: These are always installed on the inside. Follow the instructions on the do-it-yourself kit.

Glass: These can be installed either inside, if the way the window is built will permit it, or on the outside. If you install them on the inside, then you won't be able to open the existing window. If you install them on the outside, then they only cover the moving part of the window and you'll save less energy, but they will be permanently installed. With metal casement windows, exterior installation of single-pane storm windows is a job for a contractor.

Determine how you want the windows to sit in the frame. Your measurements will be the outside measurements of the storm window. Be as accurate as possible, then allow 1/8" along each edge for clearance. You'll be responsible for any errors in measurement, so do a good job.

When your windows are delivered, check the actual measurements carefully against your order.

Install the windows and fix in place with moveable clips so you can take them down for cleaning.

Advantages and Disadvantages

Single pane storm windows aren't as expensive as the double-track or triple-track combination windows (see page 42). The major disadvantage of the single pane windows is that you can't open them easily after they're installed.

Selection: Judging Quality

Frame finish (glass windows): A mill finish (plain aluminum) will oxidize quickly and degrade appearance. Windows with an anodized or baked enamel finish look better.

Weatherstripping: The side of the storm window frame which touches the existing window frame should have a permanently installed weatherstrip or gasket to make the joint as airtight as possible.

INSTALL COMBINATION STORM WINDOWS



NORMALLY CONTRACTOR INSTALLED

Triple track combination (windows and screen) storm windows are designed for installation over double-hung and sliding windows. They are permanently installed and can be opened at any time for ventilation.

Double-track combination units are also available and they cost less. Both kinds are sold almost everywhere, and can be bought with or without the cost of installation.

Installation

You can save a few dollars (10% to 15% of the purchase price) by installing the windows yourself. But you'll need some tools: caulking gun, drill, and screw driver. In most cases it will be easier to have the supplier install your windows for you, although it will cost more.

The supplier will first measure all the windows where you want storm windows installed. It will take anywhere from several days to a few weeks to make up your order before the supplier returns to install them.

Installation should take less than one day, depending on how many windows are involved. Two very important items should be checked to make sure the installation is properly done.

Make sure that both the window sashes and screen sash move smoothly and seal tightly when closed after installation. Poor installation can cause misalignment.

Be sure there is a *tightly* caulked seal around the edge of the storm windows. Leaks can hurt the performance of storm windows a lot.

NOTE: Most combination units will come with two or three 1/4" dia. holes (or other types of vents) drilled through the frame where it meets the window sill. This is to keep winter condensation from collecting on the sill and causing rot. Keep these holes clear, and drill them yourself if your combination units don't already have them.

Selection: Judging Quality

Frame finish: A mill finish (plain aluminum) will oxidize, reducing ease of operation and degrading appearance. An anodized or baked enamel finish is better.

Corner joints: Quality of construction affects the strength and performance of storm windows. Corners are a good place to check construction. They should be strong and air tight. Normally overlapped corner joints are better than mitered. If you can see through the joints, they will leak air.

Sash tracks and weatherstripping: Storm windows are supposed to reduce air leakage around windows. The depth of the metal grooves (sash tracks) at the sides of the window and the weatherstripping quality makes a big difference in how well storm windows can do this. Compare several types before deciding.

Hardware quality: The quality of locks and catches has a direct effect on durability and is a good indicator of overall construction quality.

INSTALL COMBINATION STORM DOORS



NORMALLY CONTRACTOR INSTALLED

Combination (windows and screen) storm doors are designed for installation over exterior doors. They are sold almost everywhere, with or without the cost of installation.

Installation

You can save a few dollars (10% to 15% of the purchase price) by installing doors yourself. But you'll need some tools: hammer, drill, screw driver, and weatherstripping. In most cases, it will be easier to have the supplier install your doors himself.

The supplier will first measure all the doors where you want storm doors installed. It will take anywhere from several days to a few weeks to make up your order before the supplier returns to install them. Installation should take less than one-half day.

Before the installer leaves, be sure the doors operate smoothly and close tightly. Check for cracks around the jamb and make sure the seal is as air-tight as possible. Also, remove and replace the exchangeable panels (window and screen) to make sure they fit properly and with a weather tight seal.

Selection: Judging Quality

Door finish: A mill finish (plain aluminum) will oxidize, reducing ease of operation and degrading appearance. An anodized or baked enamel finish is better.

Corner joints: Quality of construction affects the strength and effectiveness of storm doors. Corners are a good place to check construction. They should be strong and air tight. If you can see through the joints, they will leak air.

Weatherstripping: Storm doors are supposed to reduce air leakage around your doors. Weatherstripping quality makes a big difference in how well storm doors can do this. Compare several types before deciding.

Hardware quality: The quality of locks, hinges and catches should be evaluated since it can have a direct effect on durability and is a good indicator of overall construction quality.

Construction material: Storm doors of wood or steel can also be purchased within the same price range as the aluminum variety. They have the same quality differences and should be similarly evaluated. The choice between doors of similar quality but different material is primarily up to your own personal taste.

BUYING INSULATION

From the pages in Part 3 that deal with insulating your house you can get a good idea of what your choice of insulating materials is (see "Materials" at the beginning of each how-to section), how many square feet you need, and whether you need a vapor barrier with your insulation. There are three more things you need to know before you buy:

1. **What the R-Value of the insulation should be** — your money's worth in insulation is measured in R-Value. R-Value is a number that tells you how much resistance the insulation presents to heat flowing through it. The bigger the R-Value, the better the insulation. This page lists recommended R-Values for the different parts of the house.

2. **What kind of insulation to buy** — pages 45 and 46 will help you choose the right kind of insulation for the job you want to do.

3. **How thick your insulation should be** — For the R-Value and type of insulation you're going to buy, look at the table at the bottom of page 46 — it'll tell you how many inches of each type of insulation it takes to achieve the R-Value you need.

NOTE: If you have a choice of insulating materials, and all your choices are available in your area, simply price the same R-Value for both, and get the better buy. Pay more only for more R-Value.

1. What the R-Value of the insulation should be:

UNFINISHED ATTIC, NO FLOOR

Batts, -blankets or loose fill in the floor between the joists:

| THICKNESS OF EXISTING INSULATION | HOW MUCH TO ADD | HOW MUCH TO ADD IF YOU HAVE ELECTRIC HEAT OR IF YOU HAVE OIL HEAT AND LIVE IN A COLD CLIMATE** | HOW MUCH TO ADD IF YOU HAVE ELECTRIC HEAT AND LIVE IN A COLD CLIMATE** |
|----------------------------------|-----------------|--|--|
| 0" | R-38 | R-38 | R-38 |
| 0"-2" | R-22 | R-30 | R-38 |
| 2"-4" | R-11 | R-11 | R-30 |
| 4"-6" | R-11 | R-11 | R-19 |
| 6"-8" | None | None | R-11 |


*Add this much if:

- A. You're doing it yourself and your Heating and Cooling Factors add up to more than 0.4, or
- B. You're hiring a contractor and your Heating and Cooling Factors add up to more than 0.6.

**Add this much if:

- A. You're doing it yourself and your Heating and Cooling Factors add up to more than 0.7, or
- B. You're hiring a contractor and your Heating and Cooling Factors add up to more than 1.0.

FINISHED ATTIC



1. Attic Ceiling — see the table at the left under Unfinished Attic, No Floor.
2. Rafters — contractor fills completely with blow-in insulation.
3. Knee Walls — Insulate (5), Outer Attic Rafters instead.
4. Outer Attic Floors — Insulate (5), Outer Attic Rafters instead.
5. Outer Attic Rafters — Add batts or blankets: If there is existing insulation in (3) and (4), add R-11. If there is no existing insulation in (3) and (4), add R-19.
6. End Walls — Add batts or blankets, R-11.

UNFINISHED ATTIC WITH FLOOR

A. Do-it-yourself or Contractor Installed:

Between the collar beams — follow the guidelines above in Unfinished Attic, No Floor.

Rafters and end walls — buy insulation thick enough to fill the space available (usually R-19 for the rafters and R-11 for the end walls).


B. Contractor Installed

Contractor blows loose-fill insulation under the floor. Fill this space completely — see page 44 for the R-Value you should get.

FRAME WALLS — contractor blows in insulation to fill the space inside the walls. See page 44 for the R-Value you should get.

2. What kind of insulation to buy:

BATTS— glass fiber, rock wool



Where they're used to insulate:

unfinished attic floor
unfinished attic rafters
underside of floors

best suited for standard joist or rafter spacing of 16" or 24", and space between joists relatively free of obstructions

cut in sections 15" or 23" wide, 1" to 7" thick, 4' or 8' long


with or without a vapor barrier backing — if you need one and can't get it, buy polyethylene except that to be used to insulate the underside of floors

easy to handle because of relatively small size

use will result in more waste from trimming sections than use of blankets

fire resistant, moisture resistant

FOAMED IN PLACE— urea formaldehyde-based



Where it's used to insulate:

finished frame walls

moisture resistant, fire resistant

may have higher insulating value than blown-in materials

more expensive than blown-in materials

quality of application to date has been very inconsistent — choose a qualified contractor who will guarantee his work.

CRAWL SPACE — R-11 batts or blankets against the wall and the edge of the floor.

FLOORS — R-11 batts or blankets between the floor joists, foil-faced.

BASEMENT WALLS — R-11 batts or blankets between wall studs.

BLANKETS— glass fiber, rock wool



Where they're used to insulate:

unfinished attic floor
unfinished attic rafters
underside of floors

best suited for standard joist or rafter spacing of 16" or 24", and space between joists relatively free of obstructions

cut in sections 15" or 23" wide, 1" to 7" thick in rolls to be cut to length by the installer


with or without a vapor barrier backing

a little more difficult to handle than batts because of size

fire resistant, moisture resistant

RIGID BOARD—

extruded polystyrene bead board (expanded polystyrene) urethane board, glass fiber



Where it's used to insulate:

basement wall

NOTE: Polystyrene and urethane rigid board insulation should only be installed by a contractor. They must be covered with 1/2" gypsum wall-board to assure fire safety.


extruded polystyrene and urethane are their own vapor barriers, bead board and glass fiber are not.

high insulating value for relatively small thicknesses, particularly urethane.

comes in 24" or 48" widths

variety of thicknesses from 3/4" to 4"

LOOSE FILL (poured-in)— glass fiber, rock wool, cellulosic fiber, vermiculite, perlite



Where it's used to insulate:
unfinished attic floor

vapor barrier bought and applied separately

best suited for non-standard or irregular joist spacing or when space between joists has many obstructions

glass fiber and rock wool are fire resistant and moisture resistant

cellulosic fiber, chemically treated to be fire resistant and moisture resistant; treatment not yet proven to be heat resistant, may break down in a hot attic; check to be sure that bags indicate material meets Federal Specifications. If they do, they'll be clearly labelled.

cellulosic fiber has about 30% more insulation value than rock wool for the same installed thickness (this can be important in walls or under attic floors).

vermiculite is significantly more expensive but can be poured into smaller areas.

vermiculite and perlite have about the same insulating value.

all are easy to install.

LOOSE FILL (blown-in)— glass fiber, rock wool, cellulosic fiber



Where it's used to insulate:
unfinished attic floor
finished attic floor
finished frame walls
underside of floors

vapor barrier bought separately

same physical properties as poured-in loose fill.

Because it consists of smaller tufts, cellulosic fiber gets into small nooks and corners more consistently than rock wool or glass fiber when blown into closed spaces such as walls or joist spaces.

When any of these materials are blown into a closed space enough must be blown in to fill the whole space.

3. How thick your insulation should be:

Get the R-Value you need from page 44, and the type of insulation you need from this page and the one before. Use the table below to find out how thick the insulation you buy should be:

TYPE OF INSULATION

| | BATTS OR BLANKETS | | LOOSE FILL (POURED-IN) | | | |
|------|-------------------|-----------|------------------------|-----------|------------------|------|
| | glass fiber | rock wool | glass fiber | rock wool | cellulosic fiber | |
| R-11 | 3½"-4" | 3" | 5" | 4" | 3" | R-11 |
| R-19 | 6"-6½" | 5¼" | 8"-9" | 6"-7" | 5" | R-19 |
| R-22 | 6½" | 6" | 10" | 7"-8" | 6" | R-22 |
| R-30 | 9½"-10½"* | 9"* | 13"-14" | 10"-11" | 8" | R-30 |
| R-38 | 12"-13"* | 10½"* | 17"-18" | 13"-14" | 10"-11" | R-38 |

* two batts or blankets required.

INSULATE YOUR UNFINISHED ATTIC



AN EASY DO-IT-YOURSELF PROJECT

Install batts or blankets between the joists or trusses in your attic

OR


Pour in loose fill between the joists or trusses

OR

Lay in batts or pour in loose fill over existing insulation if you've decided you don't have enough already. *Don't* add a vapor barrier if you're installing additional insulation.

NOTE: If your attic has trusses in it, this section still applies — the insulation goes in the same place, but job is more difficult.

Tools

1. Temporary lighting 
2. Temporary flooring 
3. Duct or masking tape (2" wide) 
4. Heavy duty staple gun and staples, or hammer and tacks 
5. Heavy duty shears or linoleum knife to cut batts or blankets and plastic for vapor barrier 

Safety

1. Provide good lighting
2. Lay boards or plywood sheets down over the tops of the joists or trusses to form a walkway (the ceiling below won't support your weight).
3. Be careful of roofing nails protruding through roof sheathing.
4. If you use glass fiber or mineral wool, wear gloves and breathing mask, and keep the material wrapped until you're ready to put it in place.

Materials

What you'll need

Batts, glass fiber or rock wool 

Blankets, glass fiber or rock wool 

Loose fill, rock wool, cellulosic fiber, or vermiculite 

Vapor barriers 

How much

1. Accurately determine your attic area.
If necessary, divide it into rectangles and sum the areas.


| | | | | |
|-------|---|--------------|---|-------|
| _____ | X | _____ | = | _____ |
| _____ | X | _____ | = | _____ |
| _____ | X | _____ | = | _____ |
| | | Total | = | _____ |

2. Insulation area = (.9) X (total) = _____
3. Vapor barrier area (see if you need one - page 54).
 1. Batts or blankets with vapor barrier backing — use insulation area.
 2. Polyethylene (for use with loose fill, or if backed batts or blankets are not available) — use insulation area, but plan on waste since the polyethylene will be installed in strips between the joists or trusses, and you may not be able to cut an even number of strips out of a roll.
4. Insulation thickness — see page 44. If page 44 calls for R-30 or more, you may be adding two layers of insulation. Lay the first layer between the joists or trusses, and the second layer across them. *Only* the first layer should have a vapor barrier underneath it. The second layer should be an unfaced batt or blanket, loose fill, or a faced batt or blanket with the vapor barrier slashed freely.


Installation

Preparation


Put in temporary lighting and flooring, check for leaks and check need for ventilation and vapor barrier (see page 54). Seal all places where pipes or wires penetrate the attic floor. **NOTE:** Some manufacturers may recommend using polyethylene in a continuous sheet across the joists or trusses. If you aren't adding insulation that covers the tops of these framing members with at least 3½" of insulation, laying a continuous sheet may cause condensation along them; lay strips as shown instead.




1
Install temporary flooring and lights. Keep insulation in wrappers until you are ready to install. It comes wrapped in a compressed state and expands when the wrappers are removed.



3
Install separate vapor barrier if needed (see page 54). Lay in polyethylene strips between joists or trusses. Staple or tack in place. Seal seams and holes with tape. (Instead of taping, seams may be overlapped 6").




2
Check for roof leaks, looking for water stains or marks. If you find leakage, make repairs before you insulate. Wet insulation is ineffective and can damage the structure of your home.



4
If you're using loose fill, install baffles at the inside of the eave vents so that the insulation won't block the flow of air from the vents into the attic. Be sure that insulation extends out far enough to cover the top plate.

Installing the insulation

Either lay in batts or blankets between the joists or pour in loose fill. If you're using batts or blankets with a vapor barrier, place the barrier on the side toward the living area.



Lay in blankets or batts between joists or trusses. (Note: batts and blankets are slightly wider than joist spacing so they'll fit snugly). If blankets are used, cut long runs first to conserve material, using leftovers for shorter spaces. Slide insulation under wiring wherever possible.


OR



Pour in loose fill insulation to the depth required. If you are covering the tops of the joists, a good way to get uniform depth is to stretch two or three strings the length of the attic at the desired height, and level the insulation to the strings. Use a board or garden rake. Fill all the nooks and crannies, but don't cover recessed light fixtures, exhaust fans, or attic ventilation.




The space between the chimney and the wood framing should be filled with *non-combustible* material, preferably unfaced batts or blankets. Also, the National Electric Code requires that insulation be kept 3" away from light fixtures.



Cut ends of batts or blankets to fit snugly around cross bracing. Cut the next batt in a similar way to allow the ends to butt tightly together. If page 44 calls for an R-Value that requires a second layer, place it at right angles to the joists.

INSULATE YOUR UNFINISHED FLOORED ATTIC



TWO OPTIONS AVAILABLE

1. **CONTRACTOR INSTALLED:** blow-in insulation under the flooring and between the joists.
2. **DO IT YOURSELF OR CONTRACTOR:** install batts between the rafters, collar beams, and the studs on the end walls.

CONTRACTOR INSTALLED

Types of materials contractors use

Blown-in insulation
glass fiber
rock wool
cellulosic fiber




Preparation

Do you need ventilation in your attic? See page 54.

Check for roof leaks, looking for water stains or marks. If you can find any leaks, make repairs before you insulate. Wet insulation is useless and can damage the structure of your house.

What your contractor will do

The insulation is installed by blowing the insulating material under air pressure through a big flexible hose into the spaces between the attic floor and the ceiling of the rooms below. Bags of insulating material are fed into a blowing machine that mixes the insulation with air and forces it through the hose and into place. Before starting



the machine, the contractor will locate the cross bracing between the joists in the attic. He'll then remove the floor boards above the cross bracing and install the insulation by blowing it in on each side of the cross bracing to make sure there are no spaces left unfilled. Since there's no effective way to partially fill a space, all of the spaces should be completely filled to ensure proper coverage. Normally the job will take no longer than a day.

What you should check

First be very careful about choosing a contractor. See page 66 for advice on how to make a selection.


Before you sign an agreement with your contractor, decide how much and what kind of insulation you're buying and make sure it's included in the contract. Insulation material properly installed will achieve a single insulating value (R-Value) for the depth of your joist space. You should agree on what that insulating value is with the contractor, before the job begins. Next check a bag of the type of insulation he intends to use. On it, there will be a table which will indicate how many square feet of attic floor that bag is meant to cover while achieving the desired insulating value. The information may be in different forms (number of square feet per bag or number of bags per 1000 square feet), so you may have to do some simple division to use the number correctly. Knowing this and the area of your attic, you should be able to figure out how many bags must be installed to give you the desired R-Value. This number should be agreed upon between you and the contractor before the job is begun. While the job is in progress, be sure the right amount is being installed. There's nothing wrong with having the contractor save the empty bags so that you can count them (5 bags more or less than the amount you agreed on is an acceptable difference from the estimate).

After the job is finished, it's a good idea to drill 1/4" diameter holes in the floor about a foot apart. This will help prevent condensation from collecting under the floor in winter.

IN THE BANK ... OR UP THE CHIMNEY

DO-IT-YOURSELF

Install batts or blankets in your attic between the rafters and collar beams, and the studs on the end walls.






This measure will involve installing 2x4 beams which span between each roof rafter at ceiling height, if your attic doesn't already have them. This gives you a ventilation space above for the insulation (see page 54).

NOTE: The materials, methods, and thicknesses of insulation are the same for both do-it-yourself and contractor jobs. For advice on choosing a contractor, see page 66.

Safety

1. Provide good lighting
2. Be careful of roofing nails protruding through the roof sheathing
3. If you use glass fiber or mineral wool, wear gloves and a breathing mask and keep the material wrapped until you're about to use it

Tools

1. Temporary lighting 
2. Heavy duty staple gun and staples 
3. Linoleum knife or heavy duty shears to cut the insulation 
4. Duct or masking tape (2" wide) 
5. Hammer; nails (only if you're putting in collar beams) 
6. Power or hand saw (only if you're putting in collar beams) 

Materials

What you'll need

Buy either batts or blankets, made out of glass fiber or rock wool.


Do you need insulation with an attached vapor barrier? Follow the guidelines on page 54.

Exception: For the area between the collar beams, if you're laying the new insulation on top of old insulation, buy insulation without a vapor barrier if possible, or slash the vapor barrier on the new insulation.

How Thick?

1. For the area between the collar beams, follow the guidelines on page 44. ("Existing insulation" means either insulation between the collar beams or in the attic floor.)
2. For the rafters and end walls, buy insulation that's thick enough to fill up the rafter and stud spaces. If there's some existing insulation in there, the combined thickness of the new and old insulation together should fill up the spaces.

How much



1. Figure out the area you want the insulation to cover between your rafters and collar beams (shown above). In general, figure each area to be covered, and add the areas up. If your attic is like the one shown, measure distances a, b, and c, enter them below, and do the figuring indicated (the .9 allows for the space taken up by rafters or collar beams.):

$$\frac{\text{distance } a}{\text{distance } b} \times \text{distance } b \times .9 = \text{Area 1}$$

$$\frac{\text{distance } a}{\text{distance } b} \times \text{distance } b \times .9 = \text{Area 2}$$

$$\frac{\text{distance } b}{\text{distance } c} \times \text{distance } c \times .9 = \text{Area 3}$$


TOTAL

total area of insulation needed for rafters and collar beams.

2. Calculate the length of 2x4 stock you'll need for collar beams. Measure the length of span you need between rafters (c) and count the number of collar beams you need to install. Multiply to get the length of stock you need. You can have the lumber yard cut it to length at a small charge. If you cut it yourself, allow for waste. If you plan to finish your attic, check with your lumber yard to make sure 2" X 4" 's are strong enough to support the ceiling you plan to install.




3. Figure out the area of each end wall you want to insulate. Measure (d) and (e) and multiply to determine the area. Multiply by (.9) to correct for the space taken up by the studs, then multiply by the number of end walls.



Installation

Preparation

Check for roof leaks, looking for water stains or marks. If you can find any leaks, make repairs before you insulate. Wet insulation is useless and can damage the structure of your house. Determine your need for more ventilation by referring to page 54. Put up your temporary lights and:



1. Install 2x4 collar beams spanning from rafter to rafter at the ceiling height you want. Every pair of rafters should have a collar beam spanning between them.

Note: If you're installing new insulation over existing insulation:

Between the Rafters and Between the End Wall Studs, cut the old insulation loose where it has been stapled, push it to the back of the cavities, and slash the old vapor barrier (if any) before you lay the new insulation over it.

Between the Collar Beams, lay the new insulation above the old. Lay it over the tops of the collar beams in an unbroken layer at right angles to the beams. Use insulation that does not have a vapor barrier for this part of the job. If you can't get insulation without a vapor barrier, slash the vapor barrier before laying it down, so that moisture won't get trapped in the insulation.



2. Install batts or blanket sections in place between the rafters and collar beams. Install with the vapor barrier on the inside, the side toward you. Don't try to use a continuous length of insulation where the collar beams meet the rafters. It will only result in gaps that are very hard to fill. Install batts in the end walls the same way. Be sure to trim carefully to fit the angles on the end walls.



3. Install batts or blanket sections by stapling the facing flange to the edge of the rafter or collar beam. Don't staple to the outside of the rafters; the vapor barrier will have a break at every rafter; and you may compress the insulation against the sheathing, reducing its insulating value.

INSULATE YOUR FINISHED ATTIC




TWO OPTIONS AVAILABLE

(and worth considering if there's under 4 inches of insulation already there.)

1. **Contractor Installation:** insulation blown into the ceiling, sloping rafters and outer attic floors; batts installed in the knee walls.
2. **Do-it-yourself:** installation of batts, blankets or loose fill in all attic spaces you can get to.

Where the insulation needs to be installed



- | | |
|------------------|---------------------------|
| 1. Attic Ceiling | 4. Outer Attic Floors, or |
| 2. Rafters | 5. Outer Attic Rafters |
| 3. Knee Walls | 6. End Walls |

CONTRACTOR INSTALLED

Types of materials contractors use

Blown-in insulation

- glass fiber
- rock wool



Batts or blankets

- glass fiber
- rock wool



Preparation

How thick should the insulation be? See page 44.


Check your need for ventilation and a vapor barrier. See page 54.

Check for roof leaks, looking for water stains or marks. If you can find any leaks, make repairs before you insulate. Wet insulation is useless and can damage the structure of your house.

What your contractor will do

Your contractor will blow insulation into the open joist spaces above your attic ceiling, between the rafters, and into the floor of the outer attic space, then install

batts in the knee walls. If you want to keep the outer attic spaces heated for storage or any other purpose, you should have the contractor install batts between the outer attic rafters instead of insulating the outer floors and knee walls.



Page 50 describes how blown-in insulation is installed under an unfinished attic floor. This process is much the same for open joists with no floor over them. Pages 51-52 describe the right way to install batts.

DO-IT-YOURSELF

You can insulate wherever you can get into the unfinished spaces.

Installing insulation in your attic ceiling is the same as installing it in an unfinished attic. Look at pages 47-49 to see how this is done.

If you want to insulate your outer attic spaces yourself, install batts between the rafters and the studs in the small triangular end walls. Look at page 52 to see how to do this.

DO YOU NEED A VAPOR BARRIER OR MORE VENTILATION IN YOUR ATTIC?



CONTRACTOR INSTALLED OR DO-IT-YOURSELF

Whenever you add insulation to your house, you should consider the need for a vapor barrier or more ventilation where you're doing the work.

A vapor barrier will prevent water vapor from condensing and collecting in your new insulation or on the beams and rafters of your house.

Added ventilation will remove water vapor before it gets a chance to condense and will also increase summer comfort by cooling off your attic.

What you need

If you're insulating your attic and:


... you live in Zone I

1. Install a vapor barrier (unless you are blowing insulation into a finished attic)
2. Add ventilation area equal to 1/300 your attic floor area if:

Signs of condensation occur after one heating season

OR

You can't install a vapor barrier with your insulation



... if you live in Zone II and don't have air conditioning

1. Install a vapor barrier toward the living space if you are insulating a finished attic (with other attics a vapor barrier is optional).
2. Add ventilation area equal to 1/300 your attic floor area if signs of condensation occur after one heating season.

... you live in Zone II and have air conditioning

1. Install a vapor barrier toward the living space if you are insulating a finished attic (with other attics a vapor barrier is optional).
2. Add ventilation area equal to 1/150 your attic floor area.

What should be installed

Vapor barriers: If you are installing batt or blanket insulation, and you need a vapor barrier, buy the batts or blankets with the vapor barrier attached. Install them with the vapor barrier side toward the living space.

If you are installing a loose fill insulation, lay down polyethylene (heavy clear plastic) in strips between the joists first.

DON'T BLOCK VENTILATION PATH



Ventilation: Install ventilation louvers (round or rectangular) in the eaves and gables (ridge vents are also available but are more difficult and costly to install in your house). The total open area of these louvers should be either 1/300 or 1/150 of your attic area (see "What You Need" above), and evenly divided between the gables and the eaves.




Ventilation louvers should be installed by a carpenter unless you are an experienced handyman.

Don't Block Ventilation Path with Insulation.

IN THE BANK ... OR UP THE CHIMNEY

INSULATE YOUR WOOD FRAME WALLS



CONTRACTOR INSTALLED

Normally, insulating material is blown or pumped into the spaces in a wood frame wall through holes drilled from the outside or from the inside.

NOTE: Condensation in insulated walls may be a problem; see box on condensation, p.19.

Types of materials contractors use

Blow-in insulation:

glass fiber
rock wool
cellulosic fiber



Foam-in insulation:

plastic foam installed as a foam under slight pressure which hardens to form insulation. Quality of application to date has been very inconsistent — ask your local HUD/FHA office to recommend a qualified installer.

What your contractor will do

The contractor will measure the area you want insulated to determine how much material he will need and to estimate the cost. To install the insulation, the contractor must be able to get all the spaces in the wall. For each space he must drill a hole, usually in the outside wall, after removing the finished layer (usually clapboard or shingle). This always amounts to a lot of holes, but once the job is complete, a good contractor will leave no traces behind.

If you have brick veneer on the exterior, the procedure is much the same, except that it may be cheaper to do it from the inside.

Once the holes in the wall have been made your contractor is then ready to install the insulation. If the insulation is blown-in insulation he'll be following the process outlined on page 50. If he's using foam, he'll pump the foam into the wall spaces through a flexible hose with an applicator. With either method, each space will be completely filled, and the siding replaced.


What you should check

First be very careful about selecting a contractor. See page 66 for advice on how to make a choice.

Before you sign an agreement with your contractor, define what you're buying and make sure it's spelled out in the contract. Insulation material properly installed will add an R-Value of 8 for rock wool, 10 for cellulosic fiber, or 11.5 for ureaformaldehyde in a standard wood frame wall. You should agree on what that R-Value is with the contractor before the job begins. Next, check a bag of the type of insulation he intends to use (there will only be bags of mineral fiber or cellulosic fiber — there's no good way to check quantity with foam). On it, there will be a table which will indicate how many square feet of wall space that bag is meant to fill while giving your house the desired R value. The information may be in different forms (number of square feet per bag or number of bags per 1000 square feet), so you may have to do some simple division to use the number correctly.

Knowing this and the area of your walls, you should be able to figure out about how many bags should be installed to give you the desired R-value.

This number should be agreed upon between you and the contractor before the job is begun. While the job is in progress be sure the correct amount is being installed. There's nothing wrong with having the contractor save the empty bags so you can count them — 4 or 5 bags more or less than the amount you agreed on is an acceptable difference from the estimate.



TWO OPTIONS AVAILABLE

(1) **Do-It-Yourself:** Install batt or blanket insulation around the walls and perimeter of your crawl space. Lay a plastic vapor barrier down on the crawl space earth.

(2) **Contractor Installed:** If your crawl space presents access or working space problems, you may want to consider having a contractor do the work for you. The contractor will probably follow a method similar to the do-it-yourself method described below. But if he suggests something different, have him price both methods and show you which is better. See page 66 for advice on how to select a contractor.

NOTE: The method of insulation shown here should not be used by residents of Alaska, Minnesota, and northern Maine. The extreme frost penetration in these areas can cause heaving of the foundation if the insulation method shown here is used. Residents of these areas should contact local HUD/FHA field offices for advice.

Tools

1. Staple gun 
2. Heavy duty shears or linoleum knife 
3. Temporary lighting 
4. Portable fan or blower to provide ventilation 
5. Tape measure 
6. Duct or Masking Tape (2" wide) 


Safety

1. Provide adequate temporary lighting
2. Wear gloves and a breathing mask when working with glass fiber or rock wool
3. Provide adequate ventilation
4. Keep lights, fan, and all wires well off wet ground

Materials

What you'll need

1. R11 (3-3½" thick) blankets of rock wool or glass fiber; without a vapor barrier



2. Six mil polyethylene plastic to lay on earth for vapor barrier (mil's are a measure of thickness)



How much

1. Determine area to be insulated; measure the length and average height of the wall to be insulated; add 3" to the height (for perimeter insulation) and multiply the two to find total insulation area

$$\text{(length)} \times \text{(height} + 3') = \text{area}$$

$$\underline{\hspace{2cm}} \times \underline{\hspace{2cm}} + 3' = \underline{\hspace{2cm}}$$

2. Determine the area to be covered by the vapor barrier by finding the area of your crawl space

$$\text{(length)} \times \text{(width)} = \text{area}$$

$$\underline{\hspace{2cm}} \times \underline{\hspace{2cm}} = \underline{\hspace{2cm}}$$


You may have to divide your crawl space into several rectangles — measure them and add up the areas.

| | | | | |
|----------|---|-------------------|---|-------|
| (length) | X | (width) | = | |
| _____ | X | _____ | = | _____ |
| _____ | X | _____ | = | _____ |
| _____ | X | _____ | + | _____ |
| | | TOTAL AREA | = | |

Installation



Drawing 1: Where the joists run at right angles to the wall, press short pieces of insulation against the header — they should fit snugly. Then install the wall and perimeter insulation by stapling the top of each strip to the sill. Make sure the batts fit snugly against each other, and that you cut them long enough to cover 2 feet of floor as in Drawing 2.



Drawing 2: Where the joists run parallel to the wall, you don't need the short pieces of insulation, just install the wall and perimeter insulation by stapling the top of each strip to the band joist.

When all batts have been installed, lay down the polyethylene vapor barrier, tucking it under the batts all the way to the foundation wall. Turn it up at least 6" at the wall. Tape the joints of the vapor barrier or lap them at least 6". Plan your work to minimize stepping or crawling on the vapor barrier.

VENTILATING YOUR CRAWL SPACE

Even with a plastic vapor barrier on the floor, the air in your crawl space will be too damp if fresh air doesn't get in there from time to time. This will mean your new insulation will be wet, and it won't keep your house as warm. It will also mean that wooden members that hold up your house will be wet, and they'll rot. Proper ventilation will prevent both of these problems:

1. If your crawl space is part of your forced-air heating system (in other words, if air from your furnace moves through it), seal your crawl space as tightly as possible—the air moving through it from your furnace is enough ventilation in winter. If you have crawl space vents, keep them shut in winter, open in summer. If there are no vents, run the blower on your furnace 3 or 4 times during the summer to keep the air in the crawl space from getting too damp.

2. All other crawl spaces should have vents in them that can be opened in summer (to clear out the damp air), and closed tightly in winter to make the most of your new insulation. You can make a cover for them to install in winter. Note: Your furnace may get its combustion air from the crawl space. If so, some of the vents should be left open. Check with your local HUD/FHA office.



INSULATE YOUR FLOOR



TWO OPTIONS AVAILABLE

1. DO-IT-YOURSELF

Install batts or blankets between the floor joists by stapling wire mesh or chicken wire to the bottom of the joists and sliding the batts or blankets in on top of the wire. Place vapor barrier up.

The job is quite easy to do in most cases. If you are insulating over a crawl space there may be some problems with access or working room, but careful planning can make things go much more smoothly and easily.

Check your floor joist spacing — this method will work best with standard 16" or 24" joist spacing. If you have non-standard or irregular spacing there will be more cutting and fitting and some waste of material.

2. CONTRACTOR INSTALLED

See page 59.

DO-IT-YOURSELF Tools


1. Heavy duty shears or linoleum knife

2. Temporary lighting with waterproof wiring and connectors

3. Portable fan or blower to provide ventilation

4. Tape measure

5. Heavy duty staple gun and staples



Safety

1. Provide adequate temporary lighting
2. Wear gloves and breathing mask when working with glass fiber or rock wool
3. Provide adequate ventilation
4. Keep lights and all wires off wet ground

Materials

What you'll need

1. R11 (3"-3½") batts or blankets or rock wool or glass fiber, preferably with foil facing (See Installation).



2. Wire mesh or chicken wire of convenient width for handling in tight space.



How much

Determine the area to be insulated by measuring the length and width and multiplying to get the area.

$$(\text{length}) \times (\text{width}) = \text{area}$$

$$(\text{---}) \times (\text{---}) = \text{---}$$

You may find it necessary to divide the floor into smaller areas and add them.

$$(\text{length}) \times (\text{width}) = \text{area}$$

$$(\text{---}) \times (\text{---}) = \text{---}$$

$$(\text{---}) \times (\text{---}) = \text{---}$$

$$(\text{---}) \times (\text{---}) = \text{---} +$$

$$\text{total area} = \text{---}$$


$$(.9)(\text{total area}) = \text{area of insulation}$$

$$(.9)(\text{---}) = \text{---}$$


$$\text{total area} = \text{area of wire mesh or chicken wire}$$

IN THE BANK ... OR UP THE CHIMNEY

Installation




Start at a wall at one end of the joists and work out. Staple the wire to the bottom of the joists, and at right angles to them. Slide batts in on top of the wire. Work with short sections of wire and batts so that it won't be too difficult to get the insulation in place. Plan sections to begin and end at obstructions such as cross bracing.



Buy insulation with a vapor barrier, and install the vapor barrier facing up (next to the warm side) leaving an air space between the vapor barrier and the floor. Get foil-faced insulation if you can; it will make the air space insulate better. Be sure that ends of batts fit snugly up against the bottom of the floor to prevent loss of heat up end. Don't block combustion air openings for furnaces.

INSULATE YOUR BASEMENT WALLS




A MODERATELY EASY DO-IT-YOURSELF PROJECT

Install 2" X 4" studs (needed for thickness of insulation) along the walls to be insulated. Add glass fiber insulation between the studs. If you wish, finish with wallboard or panelling. The thickness of the finished wall material will determine the spacing of the studs.

NOTE: The method of insulation shown here should not be used by residents of Alaska, Minnesota, and northern Maine. The extreme frost penetration in these areas can cause heaving of the foundation if the insulation method shown here is used. Residents of these areas should contact local HUD/FHA field offices for advice.

Tools

1. Saw 
2. Hammer, nails 
3. Heavy duty staple gun, or hammer and tacks 
4. Tape measure 
5. Linoleum knife or heavy duty shears 
6. Level 
7. Small sledge hammer, masonry nails 

Safety

1. Provide adequate temporary lighting
2. If you use glass fiber or rock wool, wear gloves and a breathing mask, and keep the material wrapped until you are ready to use it

Materials

What you'll need

1. R-11 (3½ inch) batt or blanket insulation, glass fiber or rock wool, with a vapor barrier (buy polyethylene if you can't get batts or blankets with a vapor barrier).




2. 2" X 4" studs



3. Drywall or panelling, if desired.



4. Waterproof paint, if necessary



How much

Measure the height and length of the walls you intend to insulate. Multiply these two figures to determine how many square feet of insulation is needed.

$$(\text{height}) \times (\text{length}) = \text{area}$$

$$\underline{\quad} \times \underline{\quad} = \underline{\quad}$$

2. Find the linear feet of studs you'll need by multiplying the length of the walls you intend to insulate by (6).

$$(6) \times (\text{length}) = (\text{linear ft.})$$

$$(6) \times \underline{\quad} = \underline{\quad}$$


3. The area of wall covering equals the basement wall height times the length of wall you intend to finish.

$$(\text{height}) \times (\text{length}) = \text{area}$$


$$\underline{\quad} \times \underline{\quad} = \underline{\quad}$$

Installation


Check to see whether or not moisture is coming through your basement walls from the ground outside. If it is and your walls are damp, you should eliminate the cause of the dampness to prevent the insulation you're going to install from becoming wet and ineffective. To be sure, install the new studs and insulation slightly away from the wall.




Nail the bottom plate to the floor $\frac{3}{4}$ " out from the base of the wall with a hammer and masonry nails. Install studs 16 or 24 inches apart after the top plate is nailed to the joists above. (Where the wall runs parallel to the joists, you may not be able to fasten the top plate in this way, but may have to fasten a $\frac{3}{4}$ " thick horizontal furring strip to the wall near the top, and fasten the studs to it. Block between studs at ceiling after studs are in place if you need backing for finish wall material.



Cut blankets into sections the height of the wall. Staple them into place, with the vapor barrier toward the living space.




Install another small piece of insulation above the new studs and against the sill to insulate the sill and band joist.



For a more finished look, install finish wall board or panelling over the insulation and studs.

SAVING ENERGY WITH YOUR HEATING, AIR CONDITIONING & WATER HEATING



TWO OPTIONS AVAILABLE

1. **Routine Servicing** – your serviceman should check all your heating and cooling equipment and do any needed maintenance once a year.
2. **Repair or Replacement** – some of your heating and cooling equipment may be so badly worn or outmoded that it will pay you to replace it now and get your money back in a few years.

Routine Servicing

A periodic checkup and maintenance of your heating and cooling equipment can reduce your fuel consumption by about 10 per cent. Locating a good heating/cooling specialist and sticking with him is a good way to ensure that your equipment stays in top fuel-saving condition. Your local fuel supplier or heating/cooling system repair specialist are the people to call – you can find them in the Yellow Pages under:

| | |
|----------------------------|----------------------|
| Heating Contractors | Electric Heating |
| Air Conditioning Equipment | Oil Burner-Equipment |
| Furnaces-Heating | and Service |

Check out the people you contact with the Better Business Bureau and other homeowners in your area. Once you're satisfied you're in touch with a reputable outfit, a *service contract* is the best arrangement to make. For an annual fee, this gets you a periodic tuneup of your heating/cooling system, and insures you against repairs of most components. A regular arrangement like this is the best one – the serviceman gets to know your system, and you're assured of regular maintenance from a company you know.

In this section, there are lists of items your serviceman should check for each type of heating or cooling system. Some items may vary from brand to brand, but go over

the list with your serviceman. Also listed here are service items you can probably take care of yourself and save even more money. If you don't want to service your system yourself, *make sure* you add those items to your serviceman's list.

Repair or Replacement


... of your equipment may be necessary.

When you are faced with major repairs, inevitably the question comes up: should we fix what we've got, or buy new equipment? It's an important question but not difficult to answer if you consider the right things:

1. Get several estimates – the larger the job the more estimates. The special knowledge of the equipment dealer and installer is most needed here – they'll study your house, measure the walls and windows, and should give you *written* estimates.
2. Check to see what your fuel costs are now. See page 25 to estimate your heating bill if it's mixed in with other utilities.
3. Ask each contractor who gives you an estimate to tell you how many years he thinks it will take before the amount you save by having the new system equals what you paid for it. Remember, fuel costs are going up.

IN THE BANK ... OR UP THE CHIMNEY

Furnace Maintenance



OIL BURNER

Every Year

- Adjust and clean burner unit
- Adjust fuel-to-air ratio for maximum efficiency
- Check for oil leaks
- Check electrical connections, especially on safety devices
- Clean heating elements and surfaces
- Adjust dampers and draft regulator
- Change oil filters
- Change air filter
- Change oil burner nozzle
- Check oil pump
- Clean house thermostat contacts and adjust

There are several tests servicemen can use to check oil furnace efficiency:

Draft Test to see if heat is being lost up the chimney or if draft is not enough to properly burn your oil.

Smoke Test to see if your oil is being burned cleanly and completely.

CO₂ test to see if fuel is being burned completely.

Stack Temperature Test to see if stack gases are too hot or not hot enough.

COAL FURNACE

At the end of each heating season

- Adjust and clean stoker
- Clean burner of all coal, ash and clinkers
- Oil the inside of the coal screw and hopper to prevent rust

GAS FURNACE (bottled, LP or natural)

Every 3 Years

- Check operation of main gas valve, pressure regulator, and safety control valve

Adjust primary air supply nozzle for proper combustion
Clean thermostat contacts and adjust for proper operation

See Draft Test and Stack Temperature Test above

ELECTRIC FURNACE

Very little maintenance required. Check the manufacturer's specifications.

Heat Distribution Systems

Some items here you can do yourself to keep your system at top efficiency. For the ones you can't, check above on how to pick a serviceman. Note: except where it says otherwise, these are all once a year items.


HOT WATER HEATING SYSTEM

Serviceman:

- Check pump operation
- Check operation of flow control valve
- Check for piping leaks
- Check operation of radiator valves
- Drain and Flush the boiler
- Oil Pump Motor

You can do this yourself:

Bleed air from the system. Over time, a certain amount of air will creep into the pipes in your system. It will find its way to the radiators at the top of your house, and wherever there's air, it keeps out hot water. There's usually a small valve at the top of each radiator. *Once or twice a year* open the valve at each radiator. Hold a bucket under it, and keep the valve open until the water comes out. Watch out, the water is hot.



Draining and Flushing the boiler is also something you can do yourself. Ask your serviceman to show you how.

FORCED HOT AIR HEATING SYSTEM

Once a Year

Serviceman:

- Check blower operation
- Oil the blower motor if it doesn't have sealed bearings.
- Check for duct leaks where duct is accessible.


You can do these yourself:

Clean or replace air filters — *this is important, easy to do, and is something that needs to be done more often than it pays to have a serviceman do it.* Every 30 to 60 days during the heating season you should clean or replace (depending on whether they're disposable) the air filters near the furnace in your system. Ask your serviceman how to do it, buy a supply, and stick to a schedule — you can save a lot of fuel this way.



Clean the fan blade that moves the air through your system — it gets dirty easily and won't move the air well unless it's clean. Do this every year.

Keep all registers clean — Vacuum them every few weeks. Warm air coming out of the registers should have a free path unobstructed by curtains or furniture.



STEAM HEAT SYSTEM

With steam heat, if your serviceman checks your burner, (see Furnace Maintenance above) and the water system in your boiler, most of his work is done. There are two things you can do to save energy, though:

Insulate steam pipes that are running through spaces you don't want to heat.

Every 3 weeks during the heating season, drain a bucket of water out of your boiler (your serviceman will show you how) — this keeps sediment off the bottom of the boiler. If the sediment is allowed to stay there, it will actually *insulate* your boiler from the flame in your burner and a lot of heat will go up the chimney that would have heated your home.

Whole-House Air Conditioning

Once a Year

(Got room air conditioners? — many of these hints apply, ask your dealer about what you can do to your room air conditioners)

Serviceman:

Oil bearings on fan and compressor if they are not sealed

Measure electrical current drawn by compressor

Check pulley belt tension

Check for refrigerating fluid leaks and add fluid if needed

Check electrical connections

Re-adjust dampers — if your air conditioner uses the same ducts as your heating system, different settings are usually required for summer cooling than for winter heating.


Flush evaporator drain line.

You Can Do These Yourself

Clean or replace air filters — *this is important, and if done every 30 to 60 days will save you far more money in fuel than the cost of the filters.*

Clean the condenser coils of dust, grass clippings, etc.

NOTE: Your condenser is the part of your air conditioner that sits outside your house. It should be shaded — if it has to work in the sun it wastes a lot of fuel. When you shade it, make sure you don't obstruct the flow of air out and around it.



Buying a room air conditioner? — see Part 4.

IN THE BANK... OR UP THE CHIMNEY

Water Heaters


Once a Year

Serviceman:


- Adjust damper (for gas or oil)
- Adjust burner and clean burner surfaces (for oil)
- Check electrodes (for electric)
- De-lime tank

You can do this yourself:

1. Once or twice a year, drain a bucket of water out of the bottom of the heater tank — this will let out any



sediment that has collected there. The sediment insulates the water in the tank from the burner's flame or electrode — *that* wastes energy.




2. Insulate your water heater tank. This will greatly reduce the amount of fuel the heater uses when you are not using any hot water but when the heater must still keep the water hot. To insulate the heater, use 3" batts or blankets with a paper or foil facing, and duct tape. For a more finished looking job, use duct insulating blankets. There are some water heater insulating kits now being sold at home improvement centers.

Note: With oil or gas heaters, do *not* insulate the top or bottom of the heater. At the top, you may interfere with the draft of the heater's flue. At the bottom, you may cut off air to flame. *Only* insulate the sides.

3. Don't set the temperature of your water heater any higher than you need to — your heater burns fuel keeping your water hot when you're not using it — the higher you set it, the more it burns. If you've got a dishwasher, 140° is high enough — if not, 120° is plenty. Depending on the type of fuel you use, this simple setback will save you \$5 to \$45 a year. (You say your heater says HIGH, MED, LOW? — Call your dealer and ask him which setting means 140 or 120 degrees.) Note: settings over 140° can shorten the life of water heaters, especially those that are glass-lined.

More about hot water conservation — See Part 4.

Duct Insulation



If the ducts for either your heating or your air conditioning system run exposed through your attic or garage (or any other space that is not heated or cooled) they should be insulated. Duct insulation comes generally in blankets 1 or 2" thick. Get the thicker variety, particularly if you've got rectangular ducts. If you're doing this job at all, it's worth it to do it right. For air conditioning ducts, make sure you get the kind of insulation that has a vapor barrier (the vapor barrier goes on the outside). Seal the joints of the insulation tightly with tape to avoid condensation.

NOTE: Check for leaks in the duct and tape them tightly before insulating.

CHOOSING A CONTRACTOR

If you decide that a particular home improvement you want to make should be done by a contractor, there are some things you should know about finding the right person for the job. The large majority of contractors take

pride in their business, are conscientious, and honest. But you should still spend some time and effort in making your choice, and once the choice is made, in clearly defining the job.

1. Where to start looking

Yellow Pages under "Insulation Contractors - Cold and Heat." Don't be suspicious of the small operation - even just a carpenter and his helper. You're doing a relatively small project and often the small business man will give you an excellent job.

Local Chapter of the National Association of Home Builders or Home Builders Association. They will be very helpful in recommending contractors.

Your banker. It's in his interest to recommend a man who will do a good job if he's loaning you the money to do the work.

Local government offices for government funded or non-profit operated home improvement assistance centers. They don't exist everywhere but the ones that do are interested in helping, and maintain files on contractors that they recommend.

From these sources, establish a list of three or four contractors from which to select.

2. How to select from your list

Ask each contractor for a list of past customers, and check their satisfaction with his work.

See how long each contractor has been in business - in general, the longer the better.

Call your local Better Business Bureau and ask if there have been any complaints against each of the contractors on your list.

Get estimates from each on any job you think will cost more than \$200.00.

3. Once you've selected a contractor - put it IN WRITING

Have him write up a specific contract for your job.

Check the contract carefully for work content and warranty. The best way to do this is to make a list of all the things you feel he should do in the course of the job (use the applicable Part 3 pages for assistance here). Then check what you know should be included against what's in the contract.

Sign the contract only when you are fully satisfied that it details everything you want done. Insisting on a detailed contract doesn't mean that you don't trust your contractor. But once you have a contract, each of you knows his limit of responsibility before the job begins.

GETTING FINANCING

If you don't want to pay for your energy fix-up program out of your savings, and you want to get a much better interest rate than either a loan on your credit card or refinancing your present home mortgage will give you, try one of these:

Where to Get Financing (and Information)

What Kind of Financing

How Long to Repay

Commercial Bank
Savings and Loan
Mutual Savings Bank

1. Home Improvement Loan
2. FHA/HUD Title I

2-5 years

12 years

NOTE: Lenders are not allowed to charge fees of any kind for this type of loan. Almost all of the improvements mentioned in this manual are eligible under Title I.

Your Credit Union

Depends on the Credit Union, but usually includes Title I loans; see above.

Repayment time varies with the type of loan.


PART 4: MORE... on how to save heating & cooling energy

| | | | |
|-------------------------|----|---------------------------------------|----|
| Doors and Windows | 69 | Buying a Room Air Conditioner | 71 |
| Attic and Roof | 69 | The Heat Pump | 72 |
| Basements | 70 | Fireplaces | 72 |
| Shading Your Home | 70 | Lights | 72 |
| Hot Water | 70 | Energy From the Sun | 73 |
| Heating | 71 | Energy From the Wind | 73 |
| Air Conditioning | 71 | New Ways to Get Back Waste Heat | 73 |

Doors and windows

Keep doors and windows firmly shut and locked to cut down heat loss in winter and heat gain in summer. Check your windows and door latches to see whether they fit tightly and, if necessary, adjust the latches and plug any air leaks. You don't really need to open windows in winter - you usually get enough fresh air just from normal air leakage even if your house is well caulked and weatherstripped.


Use heavy or insulated draperies, keep them closed at night, and fit them tightly at the top. In the summer and in warm climates, light colored curtains that you can't see through will reflect the sun and help keep your house cool.



The tightest storm door in the world doesn't work when it's open - try to cut down the number of times that you go in and out. Adding a vestibule at your front and back doors will also help to tighten up your house.

Attic and roof

Seal any openings between your attic and the rest of your house where air might escape, such as spaces around loosely-fitting attic stairway doors or pull-down stairways, penetrations of the ceiling for lights or a fan, and plumbing vents, pipes, or air ducts which pass into the attic - they don't seem like much, but they add up!



One alternative to energy-consuming air conditioning is the use of an *attic fan* to cool your home. Normally a house holds heat, so that there's a lag between the time the outside air cools after sunset on a summer night and the time that the house cools. The purpose of the attic fan is to speed up the cooling of the house by pulling air in through open windows up through the attic and out.

When the fan's on, you can let air through to the attic either by opening the attic door part way or by installing a louver that does the same thing automatically.

In a part of the country that has hot days and cool nights, using an attic fan in the evenings and closing the windows and curtains during the day can replace air conditioning. The size of the fan you buy should be determined by the amount of space you want to cool. You can figure out the fan size you need by finding the volume of your house: Rounding off to the nearest foot, multiply the length of your house by its width, then multiply by its height (from the ground to just below the attic). This will give you the volume in cubic feet. The capacity of all fans is marked on the fan in CFM's - Cubic Feet of air moved per Minute. Divide the volume of your house by 10; this will give you the CFM rating of the fan you need to change the air in the house 6 times an hour.


$$\frac{\text{volume of house}}{10} = \text{CFM fan rating}$$

Basements


If you can't afford to insulate the exposed portions of your basement or crawl space for the winter, you can still create some barriers against wind and cold by planting shrubs around the foundation. You can also tarpaper the exposed walls and rake leaves against the foundation, covering them with a weighted tarp (the tarpaper keeps moisture off your house that would otherwise come in through the leaves.)

Shading your home

A good way to keep your house cool in the summer is to shade it from the outside. The east and west sides are where the most heat comes through - if you can shade here, it'll show up right away in a smaller air conditioning bill and a cooler home. Any way that stops the sun before it gets in through the



glass is seven times as good at keeping you cool as blinds and curtains on the inside. So trees and vines that shade in the summer and lose their leaves for the winter are what you want - they'll let the sun back in for the winter months. If you can't shade your house with trees, concentrate on keeping the sun out of your windows - awnings, sun shutters, sunshades, or reflective foil will help do the job.



Hot water

See page 65 for hot water heater maintenance, and turn your heater down to 120° if you haven't already.




All your leaky faucets should be fixed - particularly the hot ones - one leaky faucet can waste up to 6000 gallons of water a year. You can also save by turning your water heater down when you'll be away from home for a weekend or more. Always use full loads in your dishwasher and clothes washer, and use warm wash and cold rinse. Take showers - they use less hot water than baths. You should use cold water to run your garbage disposal - in general, you save every time you use cold water instead of hot.

IN THE BANK ... OR UP THE CHIMNEY

Heating

(See Part 3 for the details on how to keep your system tuned)

In Part 2 (page 25), you can figure out how much you can save by lowering your thermostat. For an extra investment of about \$80, you can install a clock thermostat, which will automatically turn your heat down every night and turn it up in the morning. Something that'll do the same job for about \$40 is a time-delay thermostat, which is a wind-up timer wired into your thermostat.



More efficient oil burners are available now. If you have oil heating, you can check with your oil company about the new high-speed flame-retention oil burners — they can save you 10% on your oil bill.

Your furnace may be too big. If your house has been insulated since it was built, then your furnace may be too big for your home. In general that means it's inefficient, and would use less fuel overall if it were smaller. Here's how to tell: wait for one of the coldest nights of the year, and set your thermostat at 70°. Once the house temperature reaches 70°, if the furnace burner runs less than 40 minutes out of the next hour (time it only when it's running), your furnace is too big. A furnace that's too big turns on and off much more than it should, and that wastes energy. Call your service company — depending on your type of fuel burner, they may be able to cut down the size of your burner without replacing it.

Don't overheat rooms and don't heat or cool rooms you're not using. It's important that no room in your house get more heating than it needs, and that you should be able to turn down the heating or cooling in areas of your home that you don't use. If

some of your rooms get too hot before the other rooms are warm enough, you're paying for fuel you don't need, and your system needs *balancing* — call your serviceman. If your house is "zoned," you've got more than one thermostat and can turn down heating or cooling in areas where they're not needed.

But if your house has only one thermostat, you can't properly adjust the temperature in rooms you're not using, and that wastes energy too. You can correct this situation fairly cheaply — try these steps on your system:

Steam Radiators — most valves on radiators are all-on or all-off, but you can buy valves that let you set any temperature you like for that radiator.

Forced-Air Heating or Cooling — Many registers (the place where the air comes out) are adjustable. If not, get ones that are, so you can balance your system.

Hot-water Radiators — if there are valves on your radiators at all, you can use them to adjust the temperature room by room.

Air conditioning


Controlling your air conditioner's thermostat is discussed in detail in Part 2 (see page 25). Closing off unused rooms is just as important in saving on air conditioning as it is for heating. Keep lights off during the day — most of the electricity they use makes heat, not light. You can also reduce the load on your air conditioning system by not using heat-generating appliances like your dishwasher during the hot part of the day (or stop the dishwasher when the drying cycle begins).

If you have central air conditioning, you may want to look into the *air economizer*, a system which turns off the part of your air conditioner that uses a lot of electricity, and circulates outside air through the house when it's cooler out than it is in. By using the cooler outside air, the system reduces its own job and saves money for you. Ask your air conditioning dealer if he can install one on your system.

Buying a room air conditioner

When you go to buy a room air conditioning unit, check the EER — Energy Efficiency Ratio. The higher the EER number, the less electricity the unit will use to cool the same amount of air — you should consider your possible fuel savings when deciding how much to spend on your air conditioning unit. A unit

JUST THE
HIGH E.E.R.
MODELS,
PLEASE



which costs more to begin with may save enough money over the next summer to make it worth it.

Typical EER's available range from 4 to 12; a unit with an EER of 4 will cost about 3 times as much to operate as one with an EER of 12.

The heat pump

A heat pump runs on electricity, and is just like an air conditioner, except it can run in reverse — it can use electricity to heat, and gets more heat out of a dollar's worth of electricity than the resistance heaters in baseboard units and electric furnaces.

How? — there's heat in the air outside your home, even when the temperature's below freezing, and a heat pump can get that warmth out and into your house. When should you consider installing one? — If you presently have a central electric heating system, it may pay to install a heat pump in the system, next to the furnace. Keep your electric furnace — once the temperature drops below 20° or so, the heat pump will need help from the furnace. Installation of a heat pump large enough for most houses should cost a little under \$3000, but you're getting central air conditioning as well as a "furnace" that's more than 2 times as efficient as your electric furnace.


If you're adding a room, consider adding a heat pump — like air conditioners they come in room size units. A heat pump for a room comes with its own electric resistance coil (like a baseboard electric heater) for the times of the year when it's too cold for the heat pump itself to work well. Call your air conditioner dealer for details on both central and room-size heat pumps. If your furnace runs on gas or oil, and the prices of those fuels continue to rise faster than the price of electricity, then you'll want to consider a heat pump too.

Fireplaces

The warm, cozy fireplace is one of the biggest energy wasters there is. Even when it's burning, it pulls more heated air up the chimney than it replaces, and pulls cold air into the house through cracks in the exterior. Even

when you're not using your fireplace and you have no damper, or the damper is left open, or if the damper is closed but doesn't fit properly, lots of air you've paid to heat will still go up the chimney.


There are many devices on the market that make your fireplace a more efficient wood burner. These range from special andirons to folding glass doors, to wood stoves that replace the fireplace. But unless you live in an area where wood is fairly inexpensive, it almost never pays to invest in these as a replacement for oil, gas, or electricity you now use. All these devices cut the amount of fuel you now waste in a fireplace, but seldom enough to justify their cost, considering that most fireplaces are not used very often.



The most effective ways to cut the amount of fuel your fireplaces waste are free: if you don't use a fireplace, make the flue airtight by making a cover for the front of the fireplace. If you use a fireplace, be sure the damper is closed as soon as the fire is completely out. Normally, an open damper has the same effect on your fuel bill as a hole in the wall twice the size of the damper. A very tall chimney or high winds will increase this effect.

Lights

Plan your lighting sensibly — reduce lighting where possible, concentrating it in work areas or reading areas where it is really needed. Fluorescent bulbs should be used rather than the incandescent kind.



A 25-watt fluorescent bulb gives off as much light as a 100-watt incandescent bulb, but costs one fourth as much to light.


Decorative gas lanterns should be turned off (call your gas company to do this), or converted to electric lamps — they will use much less energy to produce the same amount of light.

IN THE BANK ... OR UP THE CHIMNEY

...COMING SOON FOR YOUR HOME

Energy from the sun

Ways to use the sun's energy for your home are here now. Energy from the sun can be used to heat a home, or to heat domestic hot water. There are two basic ways the sun can be used to heat a home: active and passive. An active system uses a few simple parts: first, a series of large flat panels called *collectors*, that sit on the roof or on the ground next to the house. In the collector, the sun heats up either air or a water-antifreeze mixture that takes the heat into a *storage tank*. If the collector is filled with air, the tank will be filled with rocks or gravel through which the air moves. If the collector is filled with liquid, so is the tank. The tank is then used as a source of heat for the home heating system. What about nights and cloudy days? A solar heating system is never intended to fulfill *all* the heating needs of a house — the storage tank carries enough heat to get through a few overcast days and nights; after that your normal system must carry the load.



A passive system operates on the same principles as an active one, but uses less hardware and relies more on normal parts of the house — south facing windows may be used as collectors, and the heat both stored and distributed by masonry walls or floors. The cost for a solar heating system for an average new house is between \$8,000 and \$12,000.

Financially, it almost never makes sense to convert an existing home to solar heating or cooling. However, adding a solar unit just to heat your hot water can be a good investment. This is simply a small version of a solar heating system, usually an active one.

Energy from the wind

Windmills, that pump water and generate electricity have been around a long time. Recently 2 things are happening that make using a wind generator attractive as a generator for your home: first, windmills and the batteries for the electricity they store are getting more efficient — a modern windmill can grab and hold more electricity out of the same amount of wind. Second, the cost of your monthly electric bill is going up and once a windmill's installed, electricity is nearly free. Like solar heating, a windmill isn't designed to generate *all* your needs — you still need a standard source of electricity — but except for houses with electric heat, a wind generator may produce enough electricity to run your lights and most household appliances.

New ways to get back waste heat

A lot of the fuel you buy to heat your house is wasted — it goes up your chimney, and it goes up your chimney whether your furnace is running or not. There are 2 energy-saving devices coming that can grab that heat before it gets out. (Note: if you have electric heat these don't apply. Also, neither of these devices is presently approved for use, but they are coming soon.)

1. The heatpipe or stack heat exchanger — both of these are devices that can be installed to sit in the stream of hot flue gases running from your furnace to your chimney. Either device will take heat out of the flue gas, so it can be used in the house. With warm air heating systems, the extra heat can be sent to a warm air duct. So instead of going up the chimney, the heat stays in your house.
2. The motorized flue damper — you know that if you leave your fireplace damper open when there's no fire going, a lot of warm air that you've paid to heat goes up the chimney — this same thing happens with your furnace when it's not running. A motorized flue damper works just like the one in your fireplace, except it's automatic — when the furnace is running, the damper's open, and the instant the furnace shuts off the damper closes.

Index

| | |
|---------------------------------------|--------------------|
| air conditioning | 25, 26, 64, 71, 72 |
| attic, finished | 16, 53 |
| attic, unfinished | 12, 44, 47 |
| attic, unfinished, floored | 14, 44, 50 |
| basement | 21, 24, 60, 70 |
| caulking | 3, 4, 8, 34 |
| ceiling, attic | 16, 44, 53 |
| cellulosic fiber | 20, 46, 55 |
| collar beams | 51, 52 |
| condensation | 19, 54, 55 |
| contract | 66 |
| contractors | 66 |
| cost | 7 |
| crawl spaces | 21, 22, 56 |
| dishwasher | 71 |
| doors | 3, 4, 38, 39, 69 |
| drafts | 8 |
| ducts | 65 |
| end walls, attic | 14, 50, 51 |
| energy efficiency ratio | 71, 72 |
| fan, attic | 69, 70 |
| faucets | 70 |
| financing | 66 |
| fireplace | 72 |
| floors | 21, 23, 58 |
| foam, ureaformaldehyde | 20, 45, 55 |
| forced hot air | 63, 71 |
| furnace, coal | 25, 63 |
| furnace, electric | 25, 63 |
| furnace, gas | 25, 63 |
| furnace, oil | 3, 4, 25, 63 |
| gables, outer attic | 16, 17 |
| garage | 21 |
| glass fiber | 45, 46 |
| heat pump | 72 |
| heater, hot water | 70, 72 |
| hot water heat distribution | 63, 71 |
| insulation, blown-in | 46 |
| insulation, buying | 44 |
| insulation, foamed-in-place | 20, 45 |
| insulation, loose fill | 46 |
| insulation, rigid board | 45 |
| lights | 72 |
| louvers, ventilation | 54 |
| maintenance, air conditioner | 64 |
| maintenance, furnace | 63 |
| maintenance, heat distribution system | 63 |
| maintenance, water heater | 65 |
| oakum | 34, 35 |
| perlite | 46 |
| polystyrene | 45 |
| R-Value | 44 |
| rafters, attic | 14, 16, 17, 50, 52 |
| rock wool | 45, 46 |
| roof, flat | 11 |
| roof, mansard | 11 |
| Savings Factor | 7 |
| servicing, air conditioner | 64 |
| servicing, furnace | 63 |
| shading | 70 |
| solar energy | 73 |
| steam heat | 64, 71 |
| storm windows, combination | 10, 42 |
| storm windows, plastic | 10, 40 |
| storm windows, single pane | 10, 41 |
| thermostat | 25, 63, 71 |
| ureaformaldehyde foam | 20, 45, 55 |
| vapor barriers | 54 |
| ventilation | 54 |
| vermiculite | 46 |
| vestibule | 69 |
| walls, basement | 21 |
| walls, crawl space | 21 |
| walls, frame | 19, 55 |
| walls, masonry | 19 |
| waste heat recovery | 69 |
| weatherstripping | 8, 9, 36-39 |
| wind power | 73 |
| windows | 3, 4, 36, 37, 69 |

Acknowledgements

This manual was prepared by Abt Associates Inc. under Contract H-2179R for the Division of Energy, Building Technology and Standards, Office of Policy Development and Research, U.S. Department of Housing and Urban Development, and has been revised by Technology + Economics, Inc. under Contract H-2681 in August 1977.

The authors wish to thank Mr. Robert C. Jones, Jr. AIA, from the Division of Energy, Building Technology and Standards at HUD, for his untiring professional assistance and support. His concern that this manual be a useful and convenient tool for homeowners has guided us throughout the course of this project.

This manual was originally reviewed by an Advisory Committee of the American Society of Heating, Refrigerating and Air Conditioning Engineers, Inc. (ASHRAE) for general consistency with current good practice for modification of existing housing to reduce energy use. At review meetings and informal discussions, valuable constructive dialogue between the members of the Committee and the authors has greatly assisted in the resolution of many of the technical issues dealt with in this manual. The members of the Review Committee were:

Charles P. Robart, Jr., Chairman

Tamami Kusuda, Ph.D.

William Rudoy, Ph.D.

The authors wish to thank the following organizations, who by their assistance have made substantive contribution to the content and quality of this publication:

The National Bureau of Standards, for the assistance from the Center for Building Technology, in the technical and editorial review of the final drafts.

The Federal Energy Administration, for the constructive comments from their Building Branch, on the final draft.

Hittman Associates, Inc. whose scientific work in the field of residential energy conservation provided a starting point for our efforts.

The Reader's Digest, Inc. who kindly gave their permission to reference their illustrations in the preparation of some of the graphic work.

The American Gas Association; The Association of Home Appliance Manufacturers; Boston Edison Company; Boston Gas; The Brick Institute of America; Certain-Teed Products Corporation; The Davenport Insulation Company; Florida Power Corporation; HC Products Company; Honeywell, Inc.; The Illinois Power Company; Johns-Manville Corporation; Michigan Consolidated Gas Company; The National Association of Home Builders and the NAHB Research Foundation, Inc.; Owens-Corning Fiberglas Corporation; The National Environmental Systems Contractors Association; Sears, Roebuck and Company; W.R. Grace and Company.

Authors

Principal Authors:

Allan D. Ackerman, Project Manager
Bryan J. Burke
Peter T. Hogarth

Project Staff:

David J. MacFadyen, Project Director
Deborah Blackwell
Robert E. Stone
Tom Timko
Roy P. Nelson
Linda M. Wurm

Margaret Bucciero

Consultants:

James R. Simpson
Michael E. Brose
Steven Nelson
Designworks

Disclaimer

The research and studies forming the basis for this manual were conducted pursuant to a contract with the U.S. Department of Housing and Urban Development (HUD). The statements and conclusions contained herein are those of the contractor and do not necessarily reflect the views of the U.S. Government in general or HUD in particular. This manual is not an official standard, and neither the United States nor HUD nor ASHRAE nor the contractor makes any warranty, expressed or implied, or assumes responsibility for the accuracy or completeness of the information herein. However, HUD emphasizes that this manual may be reproduced freely by any interested party, so long as no material contained in the manual is changed or deleted in such reproduction, and so long as proper credit is given to HUD in such reproduction.

DIRECTIONS

THESE ARE THE TWO PAGES THAT PUT IT ALL TOGETHER. YOU ALREADY KNOW FROM PART 2 WHICH OF THESE LINES YOU WANT TO COMPLETE. HERE'S HOW TO FINISH THEM.

How to fill in lines 1-5:

First, use Part 2 to fill in the Cost and Savings Factor for each line you're interested in.

Lines 2 and 4:


Get your Heating Factor from page 28 and fill it into the oval (○) on lines 2 and 4. Find your yearly dollar savings like this:

MULTIPLY THESE

Heating Factor



Savings Factor



WRITE THE RESULT HERE

Yearly Savings

\$ _____

Lines 1,3, and 5:

Get your Heating Factor from page 28 and fill it into the Heating Factor oval (○).

If you do have whole-house air conditioning, get your Cooling Factor from page 28 and fill it into the oval (○).

If you don't have whole-house air conditioning, put zeros into the Cooling Factor oval, like this: (○).


Get your yearly dollar savings like this:

ADD THESE

Heating Factor



Cooling Factor



WRITE THE SUM HERE

MULTIPLY THESE

Savings Factor



WRITE THE RESULT HERE

Yearly Savings

\$ _____

How to fill in lines 6,7, and 8:

Just copy your yearly savings from pages 25, 26, and 27 into the appropriate boxes on the checklist.

WHAT ARE YOUR BEST INVESTMENTS?

There are two kinds of investments here — the kind you have to make each year, and the kind you only have to make once. Here's how to directly compare the two different kinds of investments and figure out which are your best bets:

For the investments that you have to make each year (lines 2a, 2b, 7, and 8), use this method: simply subtract the yearly cost from the yearly savings, and write the difference in the right-hand box on the line of the checklist dealing with the measure. This number is the net savings per year for the investment.

_____ - _____ = _____
savings cost net savings

For "one-shot" investments that you only have to pay for once (lines 1, 2c, 3-5), multiply the yearly savings by 13, subtract the cost from the result, and write the difference in the right-hand box on the line of the checklist dealing with the measure. This number is the net savings over the life of the investment.

_____ - _____ = _____
(savings x 13*) cost net savings

*Multiplying your estimated savings in the first year by 13 projects the savings (in terms of today's money) that a "one-shot" energy-saving improvement will deliver to you over its life. The figure 13 takes into account the rate of inflation, and assumes that you can borrow money at the average available interest rate.

HOW TO INTERPRET THE CHECKLIST

Now you're ready to figure out what are the best energy-savings steps for you.

First — look at the cost figures. Don't consider doing things you can't afford. But be sure you don't leave out things you can afford — read page 66, which tells you how to finance home improvements.

Second — for the measures you can afford, look at the net savings in the right-hand column. The things to do first are the things that have the highest net savings. Do the measures with the highest net savings, then the next highest, and so on — until you've done all you can afford. Don't do a measure if the net savings are less than 0.

Now you're ready to go on to part 3 — the "How-to" part. It starts on page 33.

ENERGY CHECKLIST

SAVINGS
FACTOR
FROM
PART 2

YEARLY
SAVINGS

COST
FROM
PART 2

NET
SAVINGS

1. CAULK AND WEATHERSTRIP

Heating factor + Cooling factor =

+ =

Savings factor

x =

\$

Total cost

2. ADD STORM WINDOWS

a) plastic storm windows
(with no new weatherstripping)

Heating factor Savings factor

x =

\$

Yearly cost

b) plastic storm windows
(with new weatherstripping -
be sure to fill out line 1 above)

Heating factor Savings factor

x =

\$

Yearly cost

c) glass or rigid plastic
storm windows
(with new weatherstripping -
be sure to fill out line 1 above)

Heating factor Savings factor

x =

\$

Total cost

3. INSULATE ATTIC

Fill out both lines if your attic is a combination of two basic attic types (see page 11).
Otherwise, fill out the top line only.

Heating factor + Cooling factor =

+ =

Savings factor

x =

\$

Total cost

Heating factor + Cooling factor =

+ =

Savings factor

x =

\$

Total cost

4. INSULATE CRAWL SPACE WALLS, FLOOR, OR BASEMENT WALLS

a) Insulate crawl space walls

Heating factor Savings factor

x =

\$

Total cost

b) Insulate floor

Heating factor Savings factor

x =

\$

Total cost

c) Insulate basement walls

Heating factor Savings factor

x =

\$

Total cost

5. INSULATE FRAME WALLS

Heating factor + Cooling factor =

+ =

Savings factor

x =

\$

Total cost

6. REGULATE THERMOSTAT

Down in winter, up in summer.

Degrees turndown

From Part 2

Yearly cost

\$0

7. SERVICE OIL OR COAL-BURNING FURNACE

From Part 2

Yearly cost

\$30-35

8. SERVICE WHOLE-HOUSE AIR CONDITIONER

From Part 2

Yearly cost

\$30-35